


ENGINEERING  
LIBRARY

F. M. FOSTER  
ANN ARBOR, MICHIGAN

# DIESEL PROGRESS



FIVE DOLLARS PER YEAR

JANUARY 1943

FIFTY CENTS PER COPY



Courtesy Nordberg Manufacturing Co.

## YOU'LL USE LESS FUEL

when you keep  
your Diesels  
clean and  
efficient with  
**Texaco Ursa Oils**

**K**EEP your Diesels *clean*—with world-famous *Texaco Ursa Oils*—and you'll use less fuel, get more power, spend less for maintenance year after year.

*Texaco Ursa Oils* prevent formation of power-stealing carbon, varnish, sludge and other deposits. They keep rings free for proper seal...assure active valves and open ports...prolong the life of bearings, pistons, rings and liners. Use them in *your* Diesels—whatever their type or size—for maximum efficiency and economy.

All leading Diesel manufacturers approve *Texaco Ursa Oils*, and—  
*More stationary Diesel horsepower and more Diesel locomotives in the U. S. are lubricated with Texaco Ursa Oils than with any other brand.*

For Texaco Products and Lubrication Engineering Service, call the nearest of the more than 2500 Texaco Distributing Plants in the 48 States, or write The Texas Company, 135 East 42nd Street, New York 17, New York.



# TEXACO URSA OILS

FOR ALL DIESEL ENGINES

TUNE IN . . . TEXACO STAR THEATRE presents the TONY MARTIN show every Sunday night. • METROPOLITAN OPERA broadcasts every Saturday afternoon.

DIESEL PROGRESS, for January, 1948. Volume XI, Number 1. DIESEL PROGRESS is published monthly by Diesel Engines, Inc., 2 W. Forty-fifth St., New York 19, N. Y. Rex W. Wadman, President. Acceptance under the Act of June 3, 1934, at East Stroudsburg, Pa., authorized Mar. 27, 1940. Subscription rates: \$5 per year, single copy 50c.



Engine lib.  
Gift

Engineering  
TJ  
795  
AI  
D57

# DIESEL *and* GAS ENGINE PROGRESS

IN INDUSTRY • IN TRANSPORTATION • ON THE SEA • IN THE AIR

## CONTENTS

JANUARY 1948

**REX W. WADMAN**

**Editor & Publisher**

**WILBUR W. YOUNG**

**Managing Editor**

**BRUCE C. SISSON**

**Assistant Editor**

**CHARLES F. A. MANN**

**Associate Editor**

**RICHARD SALA**

**Art Director**

Member National Business Papers  
Association and Controlled  
Circulation Audit, Inc.

**NBP**  
ASSOCIATION

**CCA**

Diesel Luxury Yacht "Sotavento" .....	32
Motor Boat Show Features .....	35
American-Built Diesel Ship for France .....	36
New Diesel Towboats .....	39
Gas Engines for Shrimp Processing .....	40
European Motorship Development Part I .....	42
Diesel Towboats in the Pacific Northwest .....	44
Dieselized European Piledrivers .....	46
Diesel Oil Filtration .....	48
D.E.M.A. Holds Annual Meeting .....	50
Diesels Move 200 Inch Mirror .....	52
Developments in High Temperature Cooling .....	54
A New 2-cycle Marine Diesel .....	56
A Great Lakes Diesel Cruiser .....	58
New Machining Methods Aid Diesel Production .....	59
Recent and Future Developments in Diesel Engines .....	62
Diesels Modernize Ancient Ferry Service .....	66
A New Diesel by Caterpillar .....	68

**FRONT COVER ILLUSTRATION:** The auxiliary yawl, "Thistle," long prominent in the New York Yacht Club fleet, was recently repowered with a General Motors 71-series Diesel and is now back in service. 102 feet l.o.a. and 74.4 feet at the water line, she is a thing of beauty and speed.

**DIESEL PROGRESS** for January, 1948, Vol. XIV, No. 1. Published monthly by Diesel Engines, Inc., 2 West 45th Street, New York 19, N. Y. Tel. MUrray-Hill 2-7333. Subscription rates are \$5.00 for U.S.A. and possessions. All other countries \$7.50 per year. Subscriptions may be paid the London office at £1-17s per year.

### BUSINESS OFFICES

**NEW YORK 19:**  
Earle L. Townsend  
2 West 45th Street  
MUrray Hill 2-7333

**CHICAGO 1:**  
Willard R. Cotton  
and G. H. Gannett  
307 N. Michigan Av.  
Franklin 2508

**CLEVELAND 14:**  
Frank J. Enright  
Union Commerce Bldg.  
Main 5693

**LONDON S. W. 1:**  
E. H. Doddrell  
10 Bury Street  
St. James's

**DETROIT 2:**  
R. F. Pickrell  
314 Stephenson Bldg.  
Trinity 1-0790

**TULSA 3:**  
O. F. Cozler  
515 McBirney Bldg.  
4-5555

**LOS ANGELES 14:**  
Walter S. Johnson  
412 West 4th Street  
Mutual 1391

# SOTAVENTO

## 168-foot Higgins-Built Diesel Yacht for Mexico's President Aleman

By DOUGLAS SHEARING

**T**HERE have been many fine yachts built in American shipyards since the days when the good people of this hemisphere first began to consider themselves sufficiently well-to-do to begin to spend a little money on diversion instead of laying it all away against the probable coming of a rainy day or a hard winter. Some of these fine yachts were sailing craft which not only gave comfort and fun to their owners but also won and kept on winning cups galore, regardless of the efforts of men like Lipton. Other yachts were built for steam power, some little ones eventually had those tricky little naphtha engines; others tried gasoline motors and finally the Diesels came into the picture, bulky and weighty at first, then gradually becoming lighter and stronger and with a higher ratio of horsepower to engine weight. Supercharging finally has said just about the last word in extracting unsuspected horsepower from Diesels—especially the larger ones—without adding appreciably to the weight of the engine.

Now there is open to prospective owners of big,

fine yachts the possibility of installing more than double the power at the same engine weights of the Diesels of just a few years ago, giving fleetness and added seaworthiness and greatly increased maneuverability to hulls which with the older atmospheric pressure Diesels would have been lucky to log ten knots. Supercharging the Diesel has in fact revolutionized yacht performance and construction in the United States.

As in the *Sotavento*, for instance, probably the largest and certainly the finest steel yacht built in this country since the ruinous stock market crash days of '29. Here is an all-welded steel hull, designed and built with sufficient weight and strength of metal to endure any seas anywhere, yet formed for fast, smooth yacht performance because the designers knew that 1800 and more real horsepower could be expected from the same engine weight that about ten years ago would have produced possibly 800. And instead of a ten or 12 knot speed, this magnificent vessel materially exceeded her stipulated 17 knots on her trials, which is fast going for a 168 ft. steel boat.

*Sotavento* is 168 ft. in overall length, with a beam

of 28 ft., a depth of hull of 16 ft. 6 in., and a draft of 10 ft. 6 in., and she is a gift. Fact!

The man who placed the order and paid the bill—over \$800,000 it is understood—is said to be one of Mexico's best known financially able citizens, and he has placed *Sotavento* at the disposal of His Excellency Sr. Miguel Aleman, President of the Republic of Mexico; and the ship is now manned by officers and men of the Mexican navy, turned over to them at the commissioning ceremonies on November 19, 1947. The initial trip was from New Orleans via the Panama Canal to Acapulco, Mexico; quite a voyage, but it might as well have been around the world and could have been, for with a 24,000 gallon fuel capacity and 15,000 gallons of fresh water, this big yacht has a cruising range of 4,000 miles.

Higgins, Inc., New Orleans, designed the craft and built it at the Higgins plant on the Industrial Canal, the waterway connecting Lake Pontchartrain with the Mississippi. From this big plant an endless stream of big and little boats went to the armed forces during the war, but it is doubtful if anything more seaworthy than *Sotavento* ever



*Sotavento* under full speed ahead, making about 20 knots with the supercharged Enterprise Diesels turning out a total of 2200 hp.



Engine Room  
6 ft

Corner of cocktail-lounge-bar room which was designed by Martin-Parry of New York.

hailed from the Port of Higgins. And according to A. J. Higgins, Sr., president of the firm, credit for the creation of the vessel and its construction should be given to H. E. Breit, naval architect of the designing staff, George O. Huet, chief, engineering department, and A. J. Higgins, Jr., vice-president of the firm and plant manager.

*Sotavento* is a twin-screw vessel and her engines are two Enterprise Diesels, Model DMG-38, supercharged, using Elliott Buchi system turbochargers, and developing 900 hp. each at the comparatively low engine speed of 450 rpm. The engines are of 8 cylinders, of 12 in. bore and 15 in. stroke, and are true right and left hand, turning outboard.

Fuel injection is Bendix-Scintilla, with an individual pump for each cylinder. Winslow fuel filters equip each engine, and another feature is a larger lube oil cooler than conventionally installed with engines of this size, as the use of cast-iron oil-cooled pistons needs more cooling lube oil. The turbochargers on these engines are mounted on the forward ends, an Enterprise design which shortens the exhaust outlet piping; desirable particularly in this instance as the stack is directly over the forward ends of the Diesels.

The pyrometer system is Alnor, with the master gauge mounted on the instrument panel forward of the two engines, and with 13 thermocouples for each engine: 8 on the cylinders, 4 on the 4 ports entering the turbine, and one for registering the temperature of the gases after leaving the turbine. Tachometer is Weston. Westinghouse Air Brake controls are installed, with identical controls in both engine room and pilot house, so that by this pneumatic system the pilot house personnel may start, stop or control the main engines. Each engine also may be operated separately at the engineer's stand using the standard Enterprise controls.

Starting and reversing is by air, with the Enterprise air-ram type of reversing mechanism; each engine has a D-330 Quincy air compressor V-belt driven off the flywheel.

These engines present a beautiful appearance in the engine room; for one angle, there is ample room and good lighting to show them off to advantage and the gleaming, highly-polished aluminum valve covers and crankcase inspection doors add a decided touch of elegance. In this installation, the engines are not level but are inclined slightly, and another instantly noticed feature of this installation is that the engine room floor—of non-skid steel—is laid over the drive shafts, about at a level with the top of the flywheel. This makes it easier on the engineer's gang; valve covers may be removed without resorting to ladders, and one can-

Pilot house; Westinghouse Air Brake controls; RMC radar set at left, Sperry steering and Gyro, center.





not help wondering why this higher floor level is not worked into more engine rooms as it appears practical in the extreme.

Sale of the Enterprise Diesels was handled through Enterprise Engines, Inc., the New Orleans branch of the Enterprise Engine & Foundry Co., under management of Paul Wabnig. Mr. Wabnig closely supervised the installations, was on hand for sea trials and instructed the Mexican navy engineer personnel in the handling and maintenance of the Diesels. "And incidentally," says he, "on the


trials at full speed, we took 2200 hp. out of those engines at 450 rpm. without a bit of trouble whatever!"

Auxiliary engines are 3 General Motors 6-71 Diesels direct connected to Crocker-Wheeler generators, 75 kw., 3 phase, 440 volt, 60 cycle, A.C. There is an electrically driven Quincy air compressor, a Viking fire pump, with a bilge pump cross-connected. Electricity is also supplied for two sewage tanks and pumps, a sanitary fresh water pressure unit, a drinking water pressure





Aft end of Enterprise diesels, looking from port to starboard. Quincy compressors V-belt driven from flywheels. Note height of engine-room flooring. Air tanks at right rear. Winslow filters on engines.



The Elliott turbocharger on the forward end of the starboard engine. In foreground, 2 of the 3 General Motors 6-71 Diesels turning Crocker-Wheeler generators. Upper left, lube oil cooler and heat exchanger for cooling water.

unit with 2 pumps and a fuel oil transfer pump. Other electrical uses are the Bendix automatic laundry and dryer in the ship's laundry, the General Electric Hot Point range in the galley, the G-E toasters and coffee urns, the walk-in refrigerator complete with Dole plates and another electric refrigerator just aft of the dining room. Pilot house electrical requirements are for the Radio Marine Corporation radar set with gyro repeater, the RMC loran unit for locating the ship's position up to 1400 miles from shore, the Bendix depth recorder, the Sperry gyroscope, the Sperry rudder indicator, the RMA direction finder and of course the radio room's Westinghouse radio transmitter and radio telephone. The radio broadcast receiver is a product of National Radio Co., with three radios adjusted to operated on a common antenna. The Sperry gyroscope incidentally has a course recorder tie-in with steering engine for automatic steering.

Accommodations include the roomy owner's stateroom, extending across the entire width of the vessel under the quarter deck, furnished with 2 double beds, built-in wardrobes, a ladies' dressing table and a gentlemen's bureau; a private bath is attached; seven double staterooms and six baths, all completely air-conditioned, serve the owner's party of fourteen.

Deckhouse arrangement features a spacious dining room in a sunken house forward, and a roomy lounging salon aft, complete with a bar as fancy as a swanky hotel cocktail lounge. The interior decoration is strikingly beautiful and was supervised in detail by Mrs. A. J. Higgins, Sr.; furniture was especially designed and built by Martin-Parry, New York for the *Sotavento*.

Along with the perfect decoration, an unusually effective job of sound-proofing was done on this finest of yachts. The engine room even at full speed of the engines is remarkably quiet, with none of the clang and clatter common to most steel vessels. On the afterdeck, directly over the propellers, there is hardly no cavitation rumble except when engines are thrown from full ahead to full astern; there is no perceptible vibration. In the staterooms and accommodations below decks, even when under way one has trouble in realizing that this is aboard ship and not in some unusually quiet hotel apartment.

Yet with all this luxury and modern convenience, this is still a boat, make no mistake about that. Decks are wide, well sheltered; there is strength everywhere, even in the jackstaff and flagstaff.

**A**MC  
will be  
which  
Boat ow  
ested to

**GENER**  
vision w  
propulsio  
to 400 sh  
of 1:1 g  
sizes. In  
in the  
scavengin  
the excep  
all engine  
operated  
tional ge

6-cylinder  
Diesel

A matche  
twin screw  
have opp  
principal  
of each e  
tion there  
which dev  
well as at  
generator


**INTROD**  
uct's Fluid



# EXHIBITS AT MOTOR BOAT SHOW

**A**MONG the exhibits at the Motorboat Show will be several new developments in application which have been introduced during the past year. Boat owners and prospective owners will be interested to note some of these.

**GENERAL MOTORS** Detroit Diesel Engine Division will show a variety of models designed for propulsion and auxiliary power ranging from 60 to 400 shaft hp. New this year is the introduction of 1:1 gear ratio models in 3, 4, and 6 cylinder sizes. In addition, the enlargement of intake ports in the 1948 engines has made possible better scavenging and reduced fuel consumption. With the exception of the 2-cylinder auxiliary models, all engines are equipped with the hydraulically operated reverse gears which cut down conventional gear box space considerably.




6-cylinder 200 hp. General Motors Series 71 Marine Diesel engine equipped with hydraulic gear.

A matched pair of 200 hp. Diesels arranged for twin screw propulsion will also be shown. Engines have opposite rotations and are so mounted that principal accessories are fitted to the inboard side of each engine making servicing easier. In addition there will be a twin six Diesel on exhibit which develops 400 hp. through a single shaft, as well as an 800 hp. twin eight. A 60 and 20 kw. generator round out the exhibit.


**INTRODUCED LAST YEAR** Anchor Post Product's Fluid Heat Marine Cabin Heater made many

Fluid Heat Marine Cabin Heater



converts at the '47 Show. This year the Fluid Heat Division will present a complete line of heaters ranging from the 15,000 Btu. size for cabin heating to the 70,000 Btu. size for stand-by engine heating, domestic hot water and a combination hot water heating system. These units burn gasoline, kerosene or Diesel fuel and will operate on 6, 12 or 32 volt DC current.

**THE CUMMINS ENGINE COMPANY** will show several models of its Marine Diesel line including




Model NHM-600 Cummins Marine Diesel has maximum rating of 200 hp. at 2100 rpm.

the supercharged Model NHM-600, with a rating of 132 hp. at 1800 rpm. for continuous duty it will be equipped with a Twin Disc reverse and reduction gear. The other model shown will be the LM-600, a six cylinder Diesel rated for marine service at 177 hp. at 800 rpm. This engine has a maximum rating of 250 hp. at 1000 rpm.

Of interest to visitors of the Cummins exhibit will be an actuated cutaway model of a Cummins Diesel which will show actual motion of pistons, valves and other moving parts.


**CLEVELAND DIVISION** of General Motors will show its 12 cylinder, 1200 hp., model 278A at its exhibit. This Diesel features the unit fuel injection system and uniflow scavenging. It is available in 6, 8 and 12 cylinder units and can be supplied with direct-connected generators for electric drive or with Airflex clutch and Reverse Gear.

12 cylinder, 1200 hp. Cleveland Diesel



**LATHROP ENGINE COMPANY** will show its line of marine engines and will include its Type D-60 Diesel, a four cylinder, four cycle marine engine fitted with aluminum pistons and a mechanical governor. This type Diesel is becoming increasingly popular in the work boat field.

**UNITED STATES MOTORS CORPORATION** will have in its exhibit a new 10 kw. Diesel generating set for shipboard auxiliary use. Driven by a 22 hp. 1200 rpm. Diesel the set weighs 1300 lbs. In addition, the company will show several smaller gasoline driven generating sets.




10 kw. Marine Diesel-electric set to be shown by U. S. Motors Corporation.

**CUTLESS RUBBER BEARINGS** will be featured in the exhibit of Lucian Q. Moffitt, Inc., a synthetic rubber compound, Ameripol, which is said to be oil and heat resistant, is now being used by the Goodrich firm making these bearings.

**LATEST DEVELOPMENTS** in heat exchanging equipment for marine engines will be featured at the Harrison Radiator Division booth. This exhibit will feature a supercharger aftercooler, a new development designed to reduce the temperature of intake air after it has been supercharged. Also a new line of oil and water coolers will be shown which will introduce fabricated metal housings instead of cast housings as previously were used for cooling equipment. A wide range of coolers is now being manufactured.

Harrison Model 1260 plate type oil cooler.



from port to  
even from fly-  
ing. Air tanks  
engines.

transfer pump.  
x automatic  
try, the Gen-  
e galley, the  
alk-in refrig-  
and another  
lining room.  
are for the  
t with gyro  
locating the  
n shore, the  
roscope, the  
ection finder  
ghouse radio  
radio broad-  
Radio Co.,  
d on a com-  
incidentally  
ering engine

owner's state-  
width of the  
ished with 2  
lies' dressing  
ivate bath is  
nd six baths,  
the owner's


ous dining  
and a roomy  
bar as fancy  
The interior  
d was super-  
Sr.; furniture  
Martin-Parry,

an unusually  
lone on this  
even at full  
quiet, with  
mon to most  
ctly over the  
n rumble ex-  
full ahead to  
vibration. In  
below decks,  
e in realizing  
me unusually

convenience,  
e about that.  
e is strength  
and flagstaff.

d end of the  
the 3 General  
ler generators.  
exchanger for

EL PROGRESS



Two control stands located forward in Engine Room. Each control operation of three Nordberg Diesels.



Looking forward over tops of port engines. Six of these 1,200 hp. Nordberg Diesels give vessels a top speed of over 17 knots. They are six cylinder, four cycle with a 16-inch bore and a 22-inch stroke, supercharged.

## American-Built French Ships Feature Compact Diesel Installations

By CLAYTON R. SLAWTER

**L**AATEST Paris fashions in naval architecture were shown at the Tampa Shipbuilding Company, Tampa, Florida, with the launching on August 21 of the French ship *Amienois*. Thunder and lightning provided an impressive accompaniment to the stirring strains of the Marseillaise as the smart new vessel slipped off the ways and made a graceful curtsy to the launching party. *M. S. Amienois* is one of a group of six ships contracted for by the French Supply Council in the United States with the Tampa Shipbuilding Company, as a step in the rehabilitation of the French merchant marine. Construction of these vessels is in line with the policy of making that country's new cargo fleet almost entirely of fast motorships.

The design for these six sister ships was prepared by M. le Reverend, Technical Manager for the Societe Anonyme de Gerance et d'Armement, or more briefly, S.A.G.A. Her design was worked out in such detail, including towed and self-propelled model tests, that preparations for her construction were begun as soon as the war ended. Contract plans and specifications were prepared by the Paris firm of naval Architects known as F.E.R.M.I., under the direction of M. Kervarec.

Of necessity, the contract plans were drawn up to Bureau Veritas rules, in the metric system, and to French standard of construction and equipment.

On the basis of building to Bureau Veritas rules for full construction, but substituting American standards and equivalent American equipment, the contract for these six ships was awarded to the Tampa Shipbuilding Company.

Principal characteristics of the ships are as follows:

Length overall .....	371 ft. 10 9/16 inch
Breadth molded .....	59 ft. 1 3/4 inch
Depth .....	29 ft. 2 3/4 inch
Draft .....	19 ft. 1 1/2 inch
Deadweight .....	3,770 tons
Cargo capacity, grain .....	251,000 cubic feet
Cruising radius .....	4,500 miles

The ships are twin-screw shelter deckers, with raked stems, modified cruiser sterns, midships houses, and machinery aft. They are fitted with 7,200 horsepower in Diesel engines. They are of all welded construction except that frames and gunnel bars are riveted to the shell plating and gunnel bars are also riveted to stringer plates.

Frames are spaced 27-5/32 in., with a spacing of 24 in. at the ends. An inspection of the lines and characteristics of these ships gives the impression that high speed was a primary consideration in their planning. This impression is correct, although there is no speed stipulation or guarantee in the contract, which merely requires a guarantee of power. That the vessels will have an unusual turn of speed is evidenced by their relatively small tonnage, fine-lined hulls, and their 7,200 hp.

The shapely hulls of these smart short-sea traders are divided transversely into fore peak, Nos. 1, 2, 3 and 4 holds, machinery space, and after peak. A continuous double bottom is provided, with a duct keel on the center line in the way of Nos. 2, 3, and 4 holds. Main and shelter decks extend the full length of the ships. Above the shelter deck there is an extended forecastle, a midship house, and a long poop.

On the shelter deck forward in the way of No. 1 hatch there are strong rooms, emergency generator room, CO<sub>2</sub> cylinder room, paint and lamp lockers, and a winch-resistor room. Four refrigerated cargo boxes with a total capacity of 11,300 cubic feet are located on the shelter deck.

The ships will carry a total complement of thirty-four crew members and twelve passengers. Unusually commodious quarters are provided for all hands, with separate single-bed rooms for each member of the crew—an unusual innovation for ships of this type and class. Berthing spaces for both passengers and crew have natural ventilation, augmented by electric fans, and hot-water heating. Interior sanitary spaces are equipped with mechanical ventilation.


Quarters for deck officers and an owner's suite

are provided. Above these flying bridges for engineers' passenger spaces, notice by

Most cargo ships have quarters for passengers and they mess with space of their they are providing saloon. The poop and also reserved

One of the unique ships is machinery. The engines each, and reduction unit are in the ahead. Nordberg six Diesels. They twenty-two in horsepower at 1158 shaft horse





Diesel ship *Algerie* on trial run. She is one of six sisterships built for France.

sea traders  
Nos. 1, 2,  
after peak.  
led, with a  
y of Nos. 2  
ecks extend  
the shelter  
a midship

are provided on three decks of the midship house. Above these are the wheel house and lower and flying bridges. On the poop are accommodations for engineers, officers' recreation rooms, and passenger spaces. The latter deserve more than passing notice by the reader.

y of No. 1  
y generator  
mp lockers,  
erated cargo  
cubic feet

Most cargo ships do little more than provide sleeping quarters for such passengers as they may carry. Passengers are berthed separately, of course, but they mess with the ship's officers and have no deck space of their own. In *M.S. Amienois*, however, they are provided with a light, airy, well-decorated dining saloon, and a bar and cocktail lounge. The poop and boat decks, which are planked, are also reserved for their exclusive use.

at of thirty-  
ngers. Un-  
ided for all  
as for each  
novation for  
g spaces for  
ventilation,  
ter heating.  
d with me-  
wner's suite

One of the most interesting features of these unique ships is the arrangement of their propelling machinery. The two shafts are fitted with three engines each, driving through electric couplings and reduction gears. Two engines of each propulsion unit are reversible, while the third operates in the ahead direction only. The engines are Nordberg six-cylinder, four-cycle, supercharged Diesels. They are of sixteen inches bore and twenty-two inches stroke, developing 1200 brake horsepower at 320 rpm., which would result in 1158 shaft horsepower at 200 rpm. of the propeller.

The non-reversible engine of each propelling set has a dual function. It may be de-clutched from the reduction gear and connected to a 600 kw. generator. When it is desired to operate the ship at full power in the ahead direction the generator is disconnected and the engine becomes a propelling unit. This arrangement permits either one of two main engines to be employed as generator engines in port when working cargo and eliminates the necessity for auxiliary generator sets usually found in more conventional motorships. The system of controls devised by Nordberg engineers for handling this unique propelling installation is worthy of more than passing attention. Amidships, against the forward engine-room bulkhead are two control stands, one for each group of engines installed.

Each stand combines direct controls for two maneuvering engines with switches and levers for three electric couplings. The generator engines are operated by local controls on the engines.

When working as propelling units, these engines are coupled to the propulsion system through the medium of their electric couplings, which are operated from the central control stand forward.

The basic feature of the installation is that any

one engine or all six may be idled under no load and clutched or declutched to or from the propeller shafts. To take care of such widely varying load conditions all six engines are fitted with Woodward idling and overspeed governors especially developed in collaboration with Nordberg engineers for such drives. When an engine is started under no load, it is, therefore, idled under automatic governor control at 150 rpm. After the load has been picked up by the electric couplings, however, its control and speed regulation is entirely mechanical.

The propelling machinery installed in *Amenois* and her sister ships affords a wide variety of operating combinations. These are,

- a. Both main maneuvering engines, of the port or starboard groups, coupled to their respective shafts and running in the ahead or astern direction.
- b. One main maneuvering engine only coupled to either propeller shaft, working ahead or astern.
- c. Both engines of either the port or starboard groups idling in opposite directions of rotation making possible a quick reversal of propeller shaft rotation.
- d. Both main propelling groups running in the ahead direction, with couplings energized and

combined generating and propelling engines also coupled to the propeller shafts.  
e. Emergency stop and reverse.

These operating combinations are made through the control stands mentioned above. Each stand is fitted with two latched levers, one for each of the two maneuvering engines of its group. These levers can be worked individually, as may be required by conditions (b) and (c) mentioned above, or they may be clutched together for operating conditions (a) and (b). A knobbed lever on the control stand actuates the clutch which connects or disconnects the two control levers. Another knobbed lever makes it impossible to move the engine control lever directly from the stop position into the fuel range on its quadrant without pausing in the start position. Another knobbed lever operates the electric couplings of the maneuvering engines, while a fourth one is provided for operating the coupling which connects the combination engine to the propelling system.

Assuming that it is intended to operate two maneuvering engines on one shaft in either direction, the control levers are clutched together and the engines started, with one lever working both units. The clutch between the two engine control levers is connected to a clutch control switch which is closed only when the clutch is engaged. This insures that both couplings of two maneuvering engines of one group can only be energized simultaneously when those two engines are being operated as a single unit by means of one lever.

With the engine idling under governor control, the coupling lever is moved in the same direction as the engine control lever. When two engines of the same group are idling in opposite directions, either may be instantly connected to its propeller shaft by energizing its coupling. Under such operating conditions, it is mechanically impossible to energize both couplings.

It should also be noted that an engine control lever, if moved to the stop position automatically de-energizes the electric coupling of that engine. Should one of the combination engines be required for propulsion, it is started, with its governor set ten to fifteen rpm. above the speed of the maneuvering engines. Its handwheel is then set to the same fuel position as control levers of the other engines. Its coupling lever is then moved to the ahead position, connecting the engine to the propelling system. When working one of these units as a generating engine the overspeed latch knob of the governor is depressed and turned and the overspeed knob is set at 320 rpm. With these settings the governor will regulate the engine at the desired speed.

At sea when all six engines are employed for propelling the ship, electric current is furnished by a 250 kw. turbo-generator set, steam for which is supplied by an automatic waste-heat-oil-fired boiler. This unit is of the forced circulating type,

supplying superheated steam at 171 pounds per square inch pressure and 617 degrees Fahrenheit. Auxiliary steam for feed pumps, oil heaters, feed-water heaters, and evaporators is supplied through a desuperheater in the steam drum. The waste-heat elements of this boiler will normally supply steam requirements of the vessels when underway at full power. The oil-fired element will cut in through the medium of an automatic pilot should operating conditions require additional boiler power at any time.

There are two motor-driven fuel-oil transfer pumps and two fuel-oil centrifuges. There are lubricating oil filters and strainers for each main engine, although engine lube oil can be centrifuged by means of a cross connection to the fuel-oil centrifuges.

Through the medium of bilge pump and bilge and ballast pump, the usual drainage and ballasting operations can be conducted. There is also a fire pump and a general service pump. At main deck level in the machinery space there is a machine shop containing an eighteen inch by seventy inch lathe, a drill press, and a grinder.

While *M.S. Amienois* and her sisters were designed for a trade in which cargo is generally worked by shoreside cranes, they have been fitted with complete cargo-handling gear of their own. There are ten eight-ton cargo booms, each with its own electric winch.

Navigating equipment, in addition to being extremely complete and above the general installations found in vessels of this class, contains several electronic devices of the latest post-war models. There is a radar set installed.

Another aid to navigation installed in these ships is an underwater sound fathometer with an electronic recording device. In addition to these items there is a gyro-compass with four repeaters, including one on each wing of each bridge.


The steering gear is of the electro-hydraulic, Rapson-slide, opposed piston type. It is fitted with two similar power units capable of operation individually or in parallel. Steering is controlled through a telemotor gear from the bridge.

The emergency generating set installed in these ships is somewhat larger than is ordinarily found in such vessels. It is a Diesel-driven unit of sixty kw. capacity, which enables it to handle normal port loads when not working cargo.

One of these ships, the *M.S. Algerie*, was commissioned at Tampa on September 6, 1947, took on cargo at Houston and Corpus Christie, Texas, and when loaded underwent trials over the measured mile at Guantanamo Bay September 23. With six engines developing 7149 hp., which is approximately the normal full load with all engines in operation, and with each engine operating at 318 rpm. turning the propeller shaft at 194 rpm., a ship speed of 17.4 knots was obtained.

At first glance it might appear that the ships have an unusually large electrical generating capacity. The two 600 kw. units, however, have been installed for a very good reason. It is contemplated that at some future date the refrigerated cargo capacity of the vessels will be increased, and it is desired that this can be done without the installation of additional generating sets. These ships reflect a great deal of credit on their builder and suppliers who with American equipment matched the original specifications.

Space-saving Diesel installation is unique in ship design.





these ships  
h an elec-  
to these  
repeaters,  
idge.

aulic, Rap-  
fitted with  
operation  
controlled  
ge.

l in these  
rily found  
it of sixty  
lle normal

as commis-  
7, took on  
Texas, and  
e measured  
23. With  
is approxi-  
engines in  
ting at 318  
94 rpm., a

the ships  
ating capac-  
have been  
ntemplated  
rated cargo  
d, and it is  
the intalla-  
These ships  
uilder and  
nt matched

L PROGRESS



Diesel towboat *Wm. Pitt*, Dravo-built, develops 1000 hp. hauling coal, sand and gravel for Keystone Division.

# **NEW TOWBOATS DELIVER 34,000 LB. "PUSH"**

**T**HE *Wm. Pitt* and the *Freedom*, two of the latest Dravo towboats to be put in operation have demonstrated their ability as sterling "pushers." Tests have shown that these vessels have "push power" of 34,000 lbs. against the dock and 25,000 lbs. at a towing speed of five mph.


A combination of factors permit this extra power for the relatively small hulls of the *Wm. Pitt* and the *Freedom*: The utilization of lightweight, high-speed geared Diesels; improved Kort nozzle efficiency and greater draft. Effective thrust of the vessels is increased because of the new hull design which eliminates the necessity of stern tunnels for the Kort nozzles and permits a free flow of water to them and more efficient propulsion.

Power for each towboat is supplied by two Gen-


eral Motors supercharged, 6 cylinder, 2 cycle Diesels which deliver 500 hp., each at 700 rpm. to the Falk Airflex reverse and reduction gears. The four bladed propellers turn at 280 rpm. The main engines are equipped with Briggs lube oil clarifiers, Ross jacket water and lube oil coolers, and two General Motors air compressors driven by 5 hp. motors, controlled by magnetic type starter.

Auxiliary power is supplied by 2 General Motors 3 cylinder Diesels driving 30 kw. 120 volt dc generators at 1200 rpm.

Each vessel is 116 ft. long with a 27 ft. beam and 10 ft. moulded depth. Draft with  $\frac{3}{4}$  fuel and supplies is 7 ft. A crew of thirteen operate each vessel. The engines are pilot house controlled.



Two 500 hp. General Motors Diesels power *Wm. Pitt*, they are 6-cyl. 2 cycle engines driving through Falk reverse and reduction gears.



# GAS ENGINES AID TEXAS SHRIMP INDUSTRY

By WILL H. FULLERTON

Municipal Dock, at Port Lavaca, equipped for receiving, packing, freezing, cold storage and shipping shrimp.

**A**LTHOUGH the annual production of shrimp in Texas runs into sizeable figures and heavy money, Texas has no one home port of the industry which can be compared in number of boats and seafood packing and shipping plants to Morgan City, Houma or Golden Meadow in Louisiana, or with Biloxi in Mississippi. Those ports number their big trawlers by the hundreds and their annual production is enormous in a good season; Morgan City and the near-by Berwick Bay communities in Louisiana really have been largely responsible for putting jumbo shrimp in the nation's markets.

Texas has a long coastline; aside from Galveston, its fishing ports are small. And to offset the smaller size of the average Texas boats and smaller production, one city in particular on the Texas waterfront offers something very special to the southern fishing industry, and that is a municipal plant for handling the shrimp brought into this thriving little port.

Port Lavaca is the city. It is an old one, as Texas ports go, from which many years ago in the days before the transcontinental railroads and the Chisholm Trail, cattle were shipped to the New

Orleans market in paddle-wheel steamers. Port Lavaca today has a population of only a few thousand, but its Municipal Market and Ice Plant is an institution which could be profitably studied and emulated by every seafood producing center in the South, if not in the whole country.

On the water side, there is a wide concrete dock, over 300 feet in length, at which the trawlers can be moored for discharging cargo; efficient hoists are built-in features. Abutting on this long dock is an almost equally long building, 130 feet in depth, providing space which is leased to the various shrimping firms. Side by side are the heading and packing plants of the Colter Corporation, (owned by Kroger Grocery & Baking Co.); the Western Shell Fish Co., (the Texas end of Southern Shell Fish, of New Orleans, itself controlled by Wesson Oil); F. V. Gentry Co., a local firm; and General Seafoods, (General Foods) whose 40-Fathom trademark on all sorts of seafoods is nationally famous. The building is all concrete construction, can be maintained in a condition of spotless cleanliness, and to the firms leasing space probably fifty trawlers bring their catches. Besides the shrimp brought here in boats, many more are trucked in from Freeport, Arkansas Pass,

Rockport and Port Isabel for freezing and holding.

Besides facilities for unloading, heading, packing and shipping fresh shrimp, the layout provides for quick-freezing and cold-storage. The original planning of the facilities far undershot the need; the first storage capacity was for 250,000 lbs. of frozen shrimp. In 1945 a big addition was made, adding 1,000,000 lbs. to the storage capacity. Blast freezers were also installed and the plant could freeze 150,000 lbs. daily. Shrimp after being headed and washed are packed in 5 lb. waxed paper cartons; these are loaded into "buggies," which are tiered racks mounted on small wheels; each buggy has 12 racks and holds, when fully loaded, 1200 lbs. of shrimp. There are 3 freezing tunnels, with a capacity each of 25,000 lbs. of shrimp loaded in buggies. Two loadings daily of the tunnels gives the light catches at present only one tunnel-loading a day is practiced.

Besides the freezing and cold storage, the plant also includes ice manufacture, with a capacity of 27 tons per day. This ice is used for furnishing to trawlers and for shipping fresh shrimp.

All refrigerating equipment is Frick, according to

H. G. R.  
the plan  
lished.

The ref  
One 10  
hp. Atla  
for fuel  
General

One 8 in  
Atlas gas  
General

One 11 in  
to a 185

One 17 1/2  
by a simi

One 11 1/2  
driven by  
These la  
refrigerat

For prov  
plant aux  
Bessemer  
at 450 rpm  
Westingho  
furnished  
pressor be  
used for m

The first  
by Atlas,  
the efficien  
thing, the  
Another in  
than Dies  
nance figu  
performan  
more natur  
hundred t  
this enlarg  
sold on ga

Mr. Regan  
engines ot  
was due to  
"They did  
points out,  
buy where  
capacity for  
a predicame  
of any hig  
standard m  
buying and  
standardizin  
would have  
nance reason

The Bruce  
Ohio, are l  
their 185 hp  
in the main



H. G. Regan, chief engineer, who has been with the plant for nine years, since it was first established.

The refrigerating equipment includes:

One 10 in. by 10 in. compressor, belted to a 155 hp. Atlas Imperial gas engine, using natural gas for fuel; this engine is also belted to a 150 kw. General Electric generator.

One 8 in. by 8 in. compressor, belted to another Atlas gas engine of 150 hp., which also turns a General Electric generator of 75 kw. capacity.

One 11 in. by 10 in. compressor, direct connected to a 185 hp. Bruce-McBeth natural gas engine.

One 17 $\frac{3}{4}$  in. by 12 in. booster compressor, driven by a similar Bruce-McBeth engine.

One 11 $\frac{3}{4}$  in. by 8 in. booster compressor, belt driven by at 40 hp. electric motor at 400 rpm. These last two compressors provide two-stage refrigeration for quickly freezing.

For providing electric current for blower fans, plant auxiliaries and lights, there is a Cooper-Bessemer 5 cylinder natural gas engine, 375 hp. at 450 rpm., direct connected to a 750 amp. 220 v. Westinghouse generator. Also driven by electricity furnished by this engine is an 8 in. by 8 in. compressor belted to a 60 hp. Century motor, 300 rpm., used for maintaining a zero temperature.

The first gas engines installed were the two made by Atlas, and they demonstrated to the engineers the efficiency of natural gas as a fuel. For one thing, the cost of this fuel is cheap, in Texas. Another important item is the lower compression than Diesel operation, which shows up in maintenance figures. So satisfactory was the all-around performance that when the plant was enlarged, more natural gas engines were specified. Over two hundred thousand dollars were to be spent on this enlargement and Engineer Regan was too well sold on gas operation to consider other fuel.

Mr. Regan makes it plain that the purchase of engines other than the original make installed was due to no complaint about the Atlas machines. "They did a good job and are still doing it," he points out, "but it was war time and we had to buy where we could get deliveries. The added capacity for our plant was imperative, and in such a predicament an engineer is glad to take delivery of any high grade engine. We did insist on standard makes of high-quality engines, but war buying and delivery problems prevented us from standardizing on any one engine, much as we would have liked to do so for parts and maintenance reasons."

The Bruce-McBeth engines, made in Cleveland, Ohio, are big, heavy duty machines, delivering their 185 hp. at only 300 rpm. The natural gas in the mains is between 30 and 35 lbs. pressure;

this is reduced to an 8 oz. pressure, then passes to a pressure reducing valve which further reduces it to 2 oz., from which it goes to the mixing valve where air is mixed with the fuel before it goes to the cylinders. Ignition is by American Bosch magneto, using two spark plugs to each cylinder. The engines operate at around 110 lbs. compression. Excellent service is reported from these two Bruce-McBeth engines, both installed about two years ago. Good reports are likewise given the Cooper-Bessemer, which is incidentally equipped with a Honan, Crane lube refiner.


Cooling of all the engines is closed circuit, using a Marley forced draft tower.

This whole plant—location, dockage, processing rooms, ice-making, quick-freezing, cold storage—is a splendid example of what can happen when a city decides to support an industry with excellent engineering. The contrast between Port Lavaca's seafood arrangements and those of the average small fishing community is startling. Here, cleanliness has a chance; from here, high quality seafoods are to be expected.



Above: Landside view of Port Lavaca shrimp plant; new cold storage addition extreme right.

Below: Two Atlas gas engines, seen here, are belted to Frick compressors and G.E. generators.



# EUROPEAN MOTORSHIP DEVELOPMENT

## PART I

By A. P. CHALKLEY, Editor of "The British Motor Ship"

*Editor's Note: We are privileged to present the text of A. P. Chalkley's recent address to the Diesel Engine Panel of the recent Marine Conference held in New York. Speaking under the sponsorship of the Diesel Engine Manufacturers Association, Mr. Chalkley built up an impressive case in favor of the Diesel-propelled ship. His paper will be published in two parts, beginning with this issue.*

**T**HE subject of the application of Diesel engines to European ships is too wide to cover in a short talk and therefore I will endeavor to summarize the position by showing the extent to which motor ships are being built, stating the reasons which have influenced owners, and finally, giving a picture of recent European motor ship development with an indication of the lines along which marine men are proceeding.


The first ocean-going motor ship, the *Selandia*, was completed in 1912. Today the numbers and tonnage of motor vessels on order in Europe are double those at any previous time, and the proportion of such ships to steamers is much larger. The total is about 700, of 5,750,000 tons deadweight, and the machinery to be installed exceeds 4,000,000 hp., an impressive total.

Taking Europe as a whole (including Great Britain), 65 per cent of the mercantile tonnage now on order will be equipped with oil engines.

In Sweden, Denmark and Holland, the percentage is over 95, and in Great Britain about 60. In Britain, the only present limitation to the building of motor ships is that imposed by the productive capacity of the Diesel engine factories.

Thus, as a result of 35 years' experience, in good times and bad, in peace and in war, European shipowners have turned to the motor ship—on the Continent almost exclusively, and in Britain to a very large extent.

From the first, those shipowners who adopted the Diesel engine relied on the basic fact that it was thermodynamically by far the most efficient prime mover. In employing it, they took the risk that artificial circumstances, such as relative cheapness of boiler oil or coal, would destroy the advantages of the high efficiency engine. Their attitude has, however, been justified, and never more than today, when the most economical use of our fuel resources is a fundamental need if our standard of life is to be maintained.



Mr. A. P. Chalkley

Time and time again, British shipowners were urged to build coal-fired steamers in order to help the coal industry, and in 1938 a subsidy was given to owners who would build coal-fired steamers instead of motor ships. Had that advice been widely followed, Britain's coal situation would have been far worse than it is.

Table I gives details of the motor ships of over 2,000 tons deadweight on order in Europe on September 1, according to published announcements. In addition, there are about 300 ships totalling 4,000,000 tons deadweight, all below 2,000 tons deadweight.

Owing to the congestion in the shipyards, only about half of the ships are laid down, and in Sweden, not more than 25 per cent are already on the stocks. Deliveries for some of the larger ships extend to 1951. The number and tonnages of various classes of motor ships being built are enumerated in Table II.

The construction of motor tankers forms a large section of the European shipbuilding industry. Table III gives particulars of the vessels of this class on order, but less than half are laid down, and it is anticipated that some of the very large vessels will not be completed for another three years at the present rate of construction.

Norway has more motor ships on order than any country, totalling 2,300,000 tons deadweight (in addition to 300,000 tons of steamers), but as Norway's shipbuilding capacity amounts to less than 50,000 tons per annum, the bulk of the contracts had to be placed abroad, largely in Sweden and Great Britain. Shipbuilding has thus become an important export industry in those countries and in Great Britain the "foreign flag" motor vessels on order total 9,000,000 tons deadweight, while in Sweden, 111 ships of 1,216,000 tons deadweight are to be built for Norway.

In Table IV are given particulars of the merchant ships launched or commenced in Europe for the quarter ended June 30, 1947. These figures give a factual picture of the European shipbuilding position and we may now inquire why there has been this general adoption of the Diesel-engined vessel. Undoubtedly, the main advantage of the motor ship and the chief reason for its employment by European shipowners is the economy in the fuel bill compared with other vessels, allowing for the fact that Diesel oil costs more than that used under boilers.

For propulsion alone, the consumption may be taken at 0.35 lb. per bhp. hr., for a range of output from 60 up to 90 per cent of full continuous rated power, which covers the normal service conditions. In a cargo ship, very little additional fuel consumption has to be debited for auxiliary power because of the employment of Diesel-engined generating plant and electrical machinery. Most modern motor vessels are equipped with exhaust gas boilers and these provide steam for auxiliary services, in some cases sufficient for all auxiliary purposes at sea, in which event the fuel consumption per bhp. of the main engine becomes the total consumption. In large passenger ships where the "hotel" load is heavy, the fuel used is generally in the neighborhood of 0.39 lb. per bhp. hr. for all purposes.

Average fuel consumption of typical European motor ships are shown in Table V. Each vessel is of a class of which a number has been built. The figures are those actually attained in service over a long period, and may be taken as fully representative. They show a very large saving in the fuel bill in comparison with oil-fired steamers on practically all trade routes allowing for the differential between the prices of boiler oil and Diesel oil. See Table V.

Typical  
15 knot,  
are given  
are 475.7  
draught  
chinery p  
Electricity  
sets of 21  
oil-fired  
tion near

In almost  
guarantee  
ice, and  
In fact,  
fuel consu  
service th

### Countries

Britain  
Sweden  
France  
Holland  
Denmark  
Italy  
Belgium  
Norway  
Spain

### Class of Ship

Passenger Line  
Tankers  
Fruit ships  
Refrigerated  
Cargo ships

### Country of Construction

Britain  
Sweden  
Denmark  
Belgium  
Holland  
France  
Spain

### Country

United Kingdom  
Rest of Europe  
Total

United Kingdom  
Rest of Europe  
Total

### Country

United Kingdom  
Rest of Europe  
Total

United Kingdom  
Rest of Europe  
Total

### Fuel Consumption

No. of ships  
of Class

### Table V. Fuel Consumption

Indicated I.H.P.  
Per Hour

Class	Indicated I.H.P. Per Hour
6	7100
20	6400
20	7000
2	7000



Typical voyage results of standard 12,000 ton, 15 knot, motor cargo ships built during the war are given in Table VI. The vessels in question are 475.7 ft. long with a beam of 64.2 ft. and a draught of 29 ft. 6 ins. when fully laden, the machinery power continuous rating being 6,800 bhp. Electricity is provided from two Diesel generating sets of 210 kw. Ships of this class constructed as oil-fired geared turbine steamers have a consumption nearly double that of the motor ship.

In almost all ships, the fuel consumption can be guaranteed to remain constant over years of service, and in some instances, there is a reduction. In fact, it is generally accepted that the daily fuel consumption is slightly lower after six months service than it is at the time of the trial trip, and

as regards the complete life of the ship, the *Selandia*, the first motor vessel, was a classic case, since after 20 years' operation, the daily fuel consumption was, if anything, slightly lower than at the time she put to sea.

Apart from the economy of the fuel bill, owners have found in service that the motor ship possesses many ancillary advantages. The amount of fuel used in an oil-fired steam is at least 50 per cent more than in a corresponding motor ship. Consequently the latter has a larger radius of action without rebunkering, or alternatively, carries more cargo. This characteristic is particularly valuable on long-distance routes and the trend towards higher speeds gives it increased importance.

The importance of the human problem in connection with motor ships cannot be too strongly emphasized, and there is no question whatever that such success or failure in their operation depends far more upon the engineering personnel than it does in steamers. This is a matter that those who contemplate operating oil-engined ships for the first time must take into consideration.

The quality of the engine-room staff is, moreover, reflected in the repair bills for the machinery of motor ships perhaps more than in connection with steam plant. When sufficient care is given to this problem, the upkeep, repair and replacement charges of Diesel-engined vessels are no greater than in steamers. As an example of average figures with well-maintained machinery, the following particulars may be given.

With three ships of a class of 9,000 tons deadweight capacity with double-acting Diesel machinery of 9,900 ihp., over a period of 18 months, the cost of repairs was £1540, the spare parts £1250 making a total of £2790 per annum.

In a series of four 9,160-ton ships with 5,400 ihp. single-acting machinery, the repair bill per annum was £850 and the cost of spare parts £660, making a total of £1510 per annum.

There are recent figures based on present-day repair costs and in both cases they represent about 4/6 per ihp. per year, or, say, \$1.40. It may be added that the original cost of a European motor ship is rather lower than that of a corresponding oil-fired geared turbine steamer.

A factor which has influenced shipowners in favor of oil engines, particularly those with a large fleet of vessels, is the extent to which machinery standardization can be carried out, even when widely differing powers are required in the ships. In cases where differences of power arise, the same type of engine with variation in cylinder numbers is frequently adopted.

For instance, one British owner, is ordering five cargo ships in which the power ranged from 6,600 to a total of 13,200 bhp. employed standard cylin-

der sizes for all ships, some twin-screw and the others single-screw, and the engines were built up of 44 precisely similar cylinders, with many of the other parts of the engines standard throughout. A subsidiary advantage is that the company's engineers become very conversant with the operation of a standard type of engine and interchangeability of staff can be carried out with the utmost efficiency. In motor ships, too, in the same fleet, it is usual to adopt standard auxiliary generating engines and here again, if necessary, the number of cylinders may be varied, so that the cylinder size and most of the engine details are standard.

In this connection it is to be noted that most European Diesel engine builders concentrate upon two cylinder sizes, or three, as a maximum, and as a consequence, the number of spare cylinder liners, etc., which they have to carry in order to be able to supply shipowners rapidly, can be reduced.

There are several reasons why steam propulsion has still retained more hold in British shipping than on the continent. The present tonnage being built in Britain includes a fair proportion of passenger liners, with very high-powered machinery, for which most owners prefer oil-fired boilers and geared turbines, even though recognizing that the fuel bill will be higher.

Moreover, steam machinery can, in most instances, be delivered more quickly than Diesel engines because of the very full order books of the Diesel engine manufacturers, and this is of importance in certain cases where owners feel the necessity of building up their fleets with the least possible delay. It is rare, indeed, however, for a British owner to order a ship with oil-fired boilers and geared turbines when under 6,000 bhp. is required.

A new situation is arising in the possibility of the employment of boiler or residual oil in the machinery of Diesel vessels. In August, 1946 a new 12,000 ton motor tanker belonging to the Anglo-Saxon Petroleum Co. was equipped with a standard 4,000 ihp. four-stroke engine modified to run on a grade of fuel which is of a much lower quality than Diesel oil and is considerably cheaper. It has a viscosity of 1470 secs. Redwood 1 at 100 deg. F., a specific gravity of 0.975 (14 A.P.I.), and a sulphur content of 2.5 per cent. After more than 12 months' service the owners state the results have been wholly successful and it would seem that a step forward has been made towards the employment of lower grade fuels in Diesel engines. The means adopted lies mainly in the careful purifying of the fuel by the employment of two centrifugal separators in series and the heating of the oil up to the time of its admission to the cylinders. The fuel consumption is slightly higher than with Diesel oil, but the fuel bill is reduced £5,000 per annum and a year's service shows no appreciable increase in liner wear. The owners do not anticipate a heavier maintenance bill. The additional capital cost involved is such that it is wiped out in about a year's service.

TABLE I

Motor Ships on Order in Europe over 2000 Tons Deadweight

Country	Number	Deadweight Tonnage
Britain	244	2,277,000
Sweden	173	1,576,000
France	23	405,000
Holland	4	181,000
Denmark	59	343,000
Italy	35	230,000
Belgium	29	291,000
Norway	31	128,000
Spain	24	208,000
<b>Total</b>	<b>629</b>	<b>5,251,000</b>

TABLE II

Types of Motor Ships on Order

Class of Ship	Number	Deadweight Tonnage
Passenger Liners	14	191,000
Tankers	138	2,064,000
Fruit ships	25	82,000
Refrigerated ships	15	210,000
Cargo ships	507	3,125,000
<b>Total</b>	<b>629</b>	<b>5,251,000</b>

TABLE III

Motor Tankers on Order

Country of Construction	Number	Deadweight Capacity
Britain	99	845,000
Sweden	69	806,700
Denmark	8	318,400
Belgium	7	84,700
Holland	3	40,000
France	9	94,800
Spain	7	74,900
<b>Total</b>	<b>138</b>	<b>2,064,500</b>

TABLE IV

European Vessels Launched during the Quarter Ended June 30, 1947

Country	No. Steamers	No. Motor Ships	Total
	No. Gross Tonnage	No. Gross Tonnage	No. Gross Ton
United Kingdom	38 103,905	48 138,324	86 242,229
Rest of Europe	16 17,101	28 171,717	44 188,818
<b>Total</b>	<b>54 121,006</b>	<b>76 310,041</b>	<b>130 431,047</b>

Percentage of Motor Ships Launched

United Kingdom	57
Rest of Europe	43
<b>Total for whole of Europe</b>	<b>100</b>

European Vessels Commenced during the Quarter Ended June 30, 1947

Country	No. Steamers	No. Motor Ships	Total
	No. Gross Ton.	No. Gross Ton.	No. Gross Ton
United Kingdom	36 81,260	49 139,455	85 220,715
Rest of Europe	6 11,060	29 165,827	35 176,887
<b>Total</b>	<b>42 92,320</b>	<b>78 305,282</b>	<b>120 397,602</b>

Percentage of Motor Ships Commenced

United Kingdom	70
Rest of Europe	30
<b>Total for whole of Europe</b>	<b>100</b>

TABLE V

Fuel Consumption of Typical European Motor Ships

No. of ships of Class	Deadweight Capacity Tons	Average Speed in Service knots	Tons of Fuel per 24 hrs. All Purposes
6	11,600	15	25-26
20	9,200	12	11
20	12,100	104	12-5
3	9,000	15.45	24.5
4	9,160	13.15	14.1

X - Tanker

TABLE VI. Fuel Consumption of Typical European Motor Ships

Distance of I.H.P. Run	Speed	Average Fuel Consumption per day for all purposes	Fuel per I.H.P.hrs. per 24 hrs.	Fuel per 24 hrs.
Knots	F.W. Ins.	tons	Pounds	Pounds
100	11.1	18.6	40.9	30
100	14.7	7.7	21.3*	295
100	15.1	5.11	25.	315
100	14.5	2.8	24.7	31

\*Propulsion only

# DIESEL TOWBOATS IN THE PACIFIC NORTHWEST

## Ocean Tow Inc. Inaugurates New Towing Services To Alaska and British Columbia with 8 Diesel Tugs

By W. J. GRANBERG

**T**WO projects, one a new barge line freight service to Alaska and the other a log haul job from British Columbia waters, are engaging the powerful deep-sea, Diesel-powered tugs of Ocean Tow, Inc., in outstanding towing operations. Most important of the two, although perhaps not the most colorful, is the Alaska run for which the newly-organized Alaska Freight Express Corporation is leasing tugs to tow giant steel barges to Seward, port and railhead, in a new shipping service which was inaugurated in November.

Ocean Tow has eight deep-water, off-shore tugs in service. They are twin-screw vessels, 126 feet long, have a molded beam of 27 feet, and a 13-foot draft. Five of them are powered with twin Fairbanks-Morse 690 horsepower Diesel engines and three have twin 600 horsepower Fairbanks-Morse plants. The ships were designed by L. H. Coolidge, Seattle naval architect, and are known as the Miki-Miki type of ocean-going tug, taking their name from the initial vessel which Coolidge designed for Young Bros., Ltd., Honolulu, several years ago. Used by the army during the war, they proved their stamina in trans-ocean hauls

The tugs were built in 1943 and 1944, three by Barbee Shipyards, Seattle; three by Grays Harbor Shipbuilding Co., Grays Harbor, Wash.; one by Sagstad Shipyards, Seattle, and one by Hodgson Green, Long Beach, Calif


The new Alaska Freight Express operates direct service from Tacoma and Seattle to Seward with four steel barges leased, along with the tugs, from Ocean Tow. The barges, ex-navy, are 260 feet long, 48 feet in beam and are 15 feet deep. They are covered barges, built of molded steel, and have double hulls. They can load 4,000 measurement tons, which gives them the carrying capacity of ocean freighters. Converting them to peace-time maritime usage involved an expenditure of \$100,000 on the four of them. These modifications, which included installation of eight huge hatches, were planned by Carl Nordstrom, Seattle naval architect, and carried out by the Lake Union Dry Dock Company for Ocean Tow.

The barges have no motive power, and thus the husky Diesel tugs are depended upon entirely in the new freight service to Alaska. Typical of the five tugs powered with twin 690 horsepower, six cylinder, direct reversible Model 37-E-14 Fairbanks-Morse engines is the Maclofay. These marine

Sea-going workhorse *El Sol*, powered by two 690 hp. Fairbanks-Morse Diesels, is owned by Ocean Tow, Inc. Alongside her is seen steel barge used in Alaska freight service.

Below right, Engine room of *Maclofay* showing two Fairbanks-Morse main engines. At right is 6-cylinder Hercules Diesel generating set.

Far right, Giant log tow from British Columbia on its way to Anacortes, Washington. At head end is tug *Tefon*.



Diesels are of the vertical two-cycle, mechanical-injection type. They are pressure lubricated and have oil-cooled pistons. Excess air for scavenging and charging the cylinders is furnished by built-in scavenging pumps. The brake horsepower of 690 is rated at 300 rpm. The bore is 14 inches and the stroke 17 inches. The piston speed is 850 feet per minute.


All the tugs have a fuel capacity of 28,000 gallons. Consumption by the two engines in the *Maclofay* is about 60 gallons per hour. The engines utilize Fairbanks-Morse fresh water pumps, driven by 15-horsepower electric motors, with a third one on standby duty. The salt water circulator pumps to cool the fresh water and lubricating oil are Dayton-Dowds, driven by 5-horsepower motors, with a third held for a spare and a fourth on fire service. Fairbanks-Morse unit pumps supply fresh water for ship's use and salt water for the sanitary system. Oil purifiers are by Honan-Crane. When the tug's engines are idle, the electric power supply is derived from two 25-kilowatt generators driven by six cylinder 33-1/3 horsepower Hercules Diesel engines. The engine room switchboard, fully automatic, is a Westinghouse Electric Company product. All in all the engine room equipment for these vessels is more than adequate.

The pilot the most ment. All two miles to-shore r oratories p direction room tele Company pany electr meter ru toward m modern as

Although with the cycle, mee Model 37- cycle, mee Diesels. 7 plant is ap horsepower stroke is 1,000 fe

One of th erators is Buda Dies





mechanical-  
ricated and  
r scavenging  
by built-in  
power of 690  
inches and  
speed is 850

000 gallons.  
ne Maclofay  
gines utilize  
driven by  
third one on  
or pumps to  
oil are Day-  
motors, with  
rth on fire  
supply fresh  
the sanitary  
ane. When  
power sup-  
generators  
er Hercules  
witchboard,  
electric Com-  
room equip-  
equate.

PROGRESS

The pilot houses of all the tugs are equipped with the most modern of navigational aids and equipment. All have General Electric radar, ranged at two miles, six, and 30 miles. The 65-watt ship-to-shore radiophones are Intervox or Radio Laboratories products, depending upon the tug, while direction finders are by Bludworth. Bendix engine room telegraphs. Weston Electrical Instrument Company tachometers, Modern Engineering Company electrical steering gear and de Giers Liquidometer rudder position indicators all contribute toward making the pilot houses of these tugs as modern as an ocean liner's bridge.

Although engine room equipment varies somewhat with the builder, the tug Osage may be taken as cycle, mechanical-injection type Fairbanks-Morse Model 37-F-12 six cylinder, 600 horsepower, two cycle, mechanical-injection type Fairbanks-Morse Diesels. The fuel consumption of this power plant is approximately 25 gallons per hour. The horsepower rating is at 400 rpm. The bore and stroke is 12 inches and 15 inches. Piston speed is 1,000 feet per minute.

One of the auxiliary 25-watt electric power generators is driven by a six cylinder, 65 horsepower Buda Diesel and the other by a six cylinder, 65

horsepower Hercules. The engines utilize Moran fresh water pumps, while Dayton salt water circulator pumps are used for cooling. Fairbanks-Morse unit pumps are employed in the ship's fresh water and sanitary systems. Switchboard equipment is Square D, General Electric, or Westinghouse, depending upon the tug's builder.

Whether a tug with a total of 1,380 or 1,200 horsepower is used to tow the steel cargo barges, the trip to Seward from Seattle or Tacoma is made in approximately eight days. Although initial service is to that Alaskan city alone, plans call for extending it to southeastern ports in the Territory in an effort to improve freight service to the coastal cities. Head offices of Alaska Freight Service are at Anchorage, with branches in Seattle and Tacoma. L. B. DeLong is president of the company and T. A. Thronson is traffic manager.

And the tugs of Ocean Tow are distinguishing themselves in another field in addition to the Alaskan run, performing a chore that calls for the ultimate in engine power. This project is the towing of gigantic log rafts from British Columbia waters to Anacortes, Wash. The logs are from the world's largest logging project in the Skagit River Basin which extends from northern Washington

into Canada. The hauling of these logs from woods to the Fraser River in British Columbia demanded the superlative in Diesel trucks (DIESEL PROGRESS, October) and once at the booming grounds it becomes the chore of Diesel-powered tugs to haul them to mills on Puget Sound, thus making the whole operation of transportation one of Diesel from start to finish.

Between April 15 and October 20, 16 tows of approximately 2,200,000 board feet each were made by Ocean Tow tugs from the north arm of the Fraser River to Anacortes. Seventy sections, or rafts of logs make up each tow, and the lumber represented by one tow is enough to build a board walk three feet wide and approximately 140 miles long. Obviously enough, engines with a good deal of hanging-on power are required to haul such tows against the tides and currents of salt water. Once the rafts are nudged into line by small tugs at the booming ground, a single vessel, either a 1200 horsepower or a 1380 horsepower tug, takes the spectacular tow to the United States.

Ocean Tow, owned by Morrison-Knudsen Co., Inc., and DeLong Engineering & Construction Co., is headed by C. R. Shinn. Martin E. Guchee is port captain.

JANUARY 1948

45

# EUROPEAN PILE DRIVER UTILIZES DIESEL CYCLE

By KALMAN J. DE JUHASZ\*

**A**N interesting and unusual war time European development is the pile driver based on the compression ignition principle; manufactured by the Manfred Weiss Steel and Metal Works Company, Budapest, Hungary. This machine is intended for driving piles for foundations of bridges, dams, buildings and other structures, and it is claimed to possess the advantages of easy portability and erection, simple serviceability; reliability and low fuel consumption. Its high impact force renders it suitable for hard soil conditions.


The complete installation is shown in Fig. 1; it comprises a low carriage moveable on wheels, an I-cross section mast fastened to the carriage and supported on it by a tripod framework, the pile driver machine proper slidably mounted on the mast in a vertical position, and a hand operated winch with cable, pulley and a latch gear for raising and lowering the pile driver as a whole, for starting the machine, and for assembling and disassembling it.

The pile driver machine itself is shown in Fig. 2 in side elevation and longitudinal section. In effect it is a two-cycle, compression ignition, slow speed, air cooled, simple cylinder engine. In this application a straight line oscillatory motion is required, therefore no crank mechanism and no flywheel is needed, whereby the construction is greatly simplified compared with the usual internal combustion engines. The machine is set up with its axis vertical, and can operate only in this position, as the force of gravity is required.

The main parts of the machine are: the cylinder assembly comprising the work cylinder (1) guide cylinder (2) and retaining ring (3); the piston (4) and the ram head (5), both movably arranged in the cylinder assembly; the fuel injection pump (6) with the filter (7) and fuel tank (8); furthermore a necessary accessory is the latch gear (Fig. 4).

\* Professor of Engineering Research, The Pennsylvania State College. (Scientific Consultant, Technical Industrial Intelligence Division, Department of Commerce)

Figure 1. Hungarian Diesel-cycled pile driver easily transported and erected. Suitable for hard soil conditions.



The principal data of the machine are the following:

Piston diameter	=	8.27 in.
Piston stroke (average)	=	59 in.
Height of machine	=	118 in.
Largest diameter	=	14 in.
Piston weight	=	1200 lb.
Total weight	=	2300 lb.
Impact force, max.	=	6600 lb.
Rate of blows, approx.	=	50 per minute
Fuel consumption (approx.)	=	0.025 gal./min.

The three main elements of the cylinder assembly, work cylinder (1) guide cylinder (2) and retaining ring (3) are machined out of mild steel tubing, centered to each other by spigot and recess, and fastened together by cap screws passing through lugs welded to the joining ends of these elements; thus the three elements form in effect a long tube open at both ends. To the working cylinder are welded twelve cooling fins (10) of sheet steel, four

lugs (11) for the exhaust and intake openings (all four openings serve for both exhaust and intake), the annular fuel tank (8), the warming-up trough (12), and four brackets (13) to which the sliding paws are fastened with screws. The injection equipment (6) is fastened to the work cylinder with studs and nuts; at the height of the fuel tank a slot is machined in the wall of the work cylinder to allow the lever (14) of the injection pump to protrude into the cylinder, and be actuated by the moving piston. To the guide cylinder are welded: eyelets (15) for lifting the unit and prongs (16) for actuating the latch gear for the release of the piston; a longitudinal slot machined into the wall of the guide cylinder serves to accommodate the lifting finger (30) of the latch gear for engagement with the piston. An arresting pin (2 a) can be made to engage with the groove (4 a)

Figure 2

and thereb  
tion when

The piston  
steel and  
A center p  
driven into  
connect the  
the top of  
lifting or m  
the piston  
machined  
(30) of the  
the bottom  
head forms  
ble for cle  
be closed

The fuel  
forged bod  
pet (23), d  
and cam l  
through a s  
the cylinder  
tion the pi






Figure 2. Pile driving mechanism seen in side elevation and longitudinal section.

and thereby keep the piston in a stationary position when the machine is at rest.

The piston (4) and ram head (5) are of forged steel and are fitted with cast iron piston rings. A center pin in the bottom of the ram head is driven into the center of the top of the pile to connect the machine securely with the pile. In the top of the piston an eyelet can be screwed for lifting or removing the piston. In the middle of the piston a groove (4a) of reduced diameter is machined for engagement with the lifting finger (30) of the latch gear (Fig. 4). The space between the bottom of the piston and the top of the ram head forms the combustion chamber; it is accessible for cleaning through a large hole which can be closed with the tight fitting screw cap (16).

The fuel injection pump, Fig. 3, comprises a forged body (20), barrel (21), plunger (22), tappet (23), delivery valve (24), by pass valve (25), and cam lever (14). The cam lever protrudes, through a slot machined in the cylinder wall, into the cylinder and engages with the piston; in operation the piston, on its downstroke, actuates cam




Figure 3. (left) Fuel injection pump is actuated by piston on its downstroke by means of cam lever.

lever, thereby injecting fuel into the cylinder. The cam lever can be moved out of engagement with the piston by means of pulling a rope attached to the link (27) forming part of this lever, and thereby the pump rendered inoperative. The fuel tank (8) is an annular shaped chamber, made of sheet steel, of about 1.2 gallon capacity, surrounding the work cylinder. The fuel can be admitted to or shut off from the fuel

pump by means of the shut off valve (9) mounted on the top of the tank. At the outflow end, at the bottom of the fuel tank a filter (7) is provided. For fuel the makers recommend a mixture of 85 per cent Diesel fuel and 15 per cent kerosene.

An essential accessory for starting the machine is the latch gear, shown in detail in Fig. 4. Essentially it is a collapsible knuckle joint, slidably fitted to the mast. Through a slot provided in the wall of the guide cylinder the finger (30) protrudes into the cylinder and engages with the circular groove (4a) of the piston which latter then can be raised by means of the hand operated winch.

At a certain height the air passages (11) are uncovered by the piston and the cylinder space is filled with air. On further lifting the release lever (31) comes into engagement with the lug (16) provided on the guide cylinder, whereupon the latch collapses and releases the piston. On its downward fall at a predetermined height the piston actuates the cam lever (14) of the fuel pump whereby fuel is injected into the cylinder air. On its further travel the piston closes the air

ports, and compresses the air-fuel mixture whereby it ignites and burns. It is to be noted that the fuel is injected at the middle of the cylinder and not at the bottom; hence not pure air is compressed but a combustible mixture; this should result in a sudden explosion and not gradual burning, but for the purpose of this machine a sudden explosion is desirable. The combustion pressure acts on the ram head which transmits the force to the pile; the combustion pressure acts also on the piston and accelerates it upwards. On its upward travel the piston uncovers the ports (11) through which the combustion gases leave the chamber and fresh air enters, just like in a two cycle engine; thus the process continues automatically until stopped by the operator.

For stopping the injection pump is rendered inoperative either by screwing out the fuel by pass valve (25), or by pulling the cam lever (14) out of engagement with the piston. A graduation of the blow force can be attained by regulating the fuel by pass valve, and thus the amount of fuel injected. In cold weather it is necessary to warm up the machine; for this purpose an annular trough (12) is provided into which kerosene or other readily combustible fuel is placed for burning to warm up the chamber.

The possibilities of a pile driving machine of this type are many. Its 6600 lb. impact force makes it particularly adaptable in driving piles in hard subsurface terrain. Its light weight, 2300 lbs., combined with its ease of transport takes it out of the "heavy equipment" class for all practical purposes. Its fuel consumption of .025 gallons per minute is so low that for ordinary pile driver usage it could be almost ignored.




Figure 4. Latch gear mounted on mast holds piston in starting position.

# DIESEL OIL FILTRATION

**22-Year Research and Development Program by Filter Manufacturer Discussed.**



Cuno plant as it appears today. Original building occupied since 1912 at center with new administration building left and additional manufacturing space in buildings at right.

C. H. Cuno, Chairman of Board, founder of Cuno Engineering Corporation.

By BRUCE C. SISSON

**T**HIS is a story of Connecticut and Yankee ingenuity. Few people realize the wealth that has sprung from the Connecticut river valley and from the thousands of diversified industries which make up that region. "Production," the word so stressed today has been a byword in Connecticut since the days when Eli Whitney built his first cotton gin and when Hiram Maxim and Colt saved the Union with the mass production of breech-loading rifles.

It was the development of the internal combustion engine that led the Cuno's, father and son, into Connecticut industry and resulted in the present outstanding position the Cuno Engineering Corporation holds today. It was in 1912 that Charles H. Cuno and his father, Charles F. Cuno set up the business, consisting of one room and plenty of ingenious ideas. Their first development was an acetylene gas automotive self-starter. This venture showed great promise but the invention of the electric starter with its even greater possibilities caused the Cuno's to withdraw and seek greener fields. This they did in short order, rapidly developing a series of automotive and marine accessories which established their name in industry. These included a marine timer, automotive dash lights, and cigarette lighters. This latter product was the first successful automotive cigarette lighter


and was first produced in 1917. Today Cuno produces lighters for many of the leading automobile manufacturers.

In 1926 came the product which has made Cuno world-famous, the metal edge-type filter. The importance of this Auto-Klean filter, as it is called today, is that it could filter out foreign particles from a fluid as small as .0035 in. in size and at the same time could be cleaned without interrupting the flow of liquid through the filter itself. Designed for automotive use the filter soon came to the attention of other machinery users and builders with the result that soon it was accepted by many industries, Diesel among them.

The Auto-Klean filter is essentially a stack of thin wheel-shaped discs separated, each from the other by a metal spacer. It is the thickness of the spacer which determines the degree of filtration. The discs are mounted on a rotatable shaft and set in a filter case. Cleaning of the filter is accomplished by turning the stack of discs and spacers past a series of knife-like stationary blades which comb out solids deposited and drop them to the bottom of the case where they are easily removed.

The manufacture of this edge-type filter involves

Cutaway view of Auto-Klean filter showing arrangement of filter discs, spacers, cleaner blades, and cleaner blade spacers.




an unusual stamping o

Usually su but Cuno speed press ings. Anot manufactur metal of th absolute d would resul

Cuno's gre recent war Armed Fo required an two-story b leaving mo move did n were set up storage. In sub-contract midwest hel this effort found their

During the


(Below) Mic show progr right. This







Cuno Micro-Klean filter dismantled showing filter case, cartridges, and other component parts. This filter will handle 25 gallons of 150 ssu oil per min.



Cuno-developed filter stacking machine which automatically stacks filter parts in proper order. Warning signals notify operator if sequence is disturbed. It is called "Dancing Lady" by employees.


an unusual stamping problem inasmuch as each stamping of disc or spacer must be free of burrs.

Usually sub press equipment would be required but Cuno has developed methods whereby high speed press equipment can turn out perfect stampings. Another factor which is important in the manufacture of these filters is the necessity for metal of the proper thickness. Without metal of absolute dimensions serious assembly problems would result.

Cuno's greatest expansion occurred during the recent war with the demand for filters by the Armed Forces. New manufacturing space was required and resulted in the building of a new two-story building for administrative personnel, leaving more space in the original plant. But this move did not solve the problem and two sub-plants were set up in Meriden to handle assembly and storage. In addition to this the company had 26 sub-contractors located throughout the east and midwest helping supply vital parts. As a result of this effort tens of thousands of Cuno products found their way to all parts of the world.

During the war period however Cuno engineers

(Below) Microphotograph of Micro-Klean filter element show progressively greater fibre density from left to right. This resin impregnated fibre media is result of long research and testing.



were not resting on their laurels. As a matter of fact, work had already begun on an entirely new method of filtration. Realizing the need for very fine filtration especially in Diesel applications Cuno engineers using the resources of the Armour Research Foundation in Chicago in the summer of 1942 began their search for a filtering media which would remove a great proportion of harmful solids from lubricating oil and yet be porous enough to permit satisfactory flow characteristics with low pressure drop. Exhaustive studies of all phases of industrial filtration were made. Animal, vegetable and synthetic fibres were tested. Experiments were made with new types of bonding materials. Various methods of controlled felting were investigated. Thousands of tests were run both in the field and in the laboratory. In January 1946 final developments were made on the new filter, preparatory to putting it on the market.

During that same period a series of tests were made in Chicago at the Armour Research Foundation, sponsored by Cuno, which proved beyond any doubt that lubricating oil filtration cut engine wear considerably.

This new filter incorporates the principle of depth filtration. This is accomplished by a special process of controlled felting which permits the control of the density of the felted fibres which make up the cartridge. After felting, the cartridge is specially impregnated with resin to bond the fibres in position and provide structural strength. The felting is so controlled that the outer surface of the cartridge stops only the larger particles while the smaller micronic particles are trapped in depth according to their respective sizes. It is claimed that the cartridge will remove all particles larger

than 25 microns (.001 in.) and the greatest proportion of particles down to one micron. Other cartridges, offering filtration to other micron sizes are also being prepared.

The Micro-Klean cartridge as this cartridge is called has proved itself to have long service life. On a series of recent tests these cartridges ran up a total of 437 hours on a Diesel engine test stand whereas previously no filter had approached this standard of efficiency. The chart below illustrates the performance of the Cuno filters.

#### Test Results

Application: Test Stand Lube Oil—800 H.P. Diesel Engine. Oil: SAE 40, Flow Rate: 75 GPM  
Operating Temperature: 160—180° F  
Cartridges Used: Micro-Klean #2278F1—32 cartridges in competitive housing  
After 174 hours operation  
Inlet Pressure: 15 PSI at filter  
Outlet Pressure: 13 PSI at filter  
After 437 hours operation  
Inlet Pressure: 18 PSI at filter  
Outlet Pressure: 14 PSI at filter  
Total Volume of oil handled: 1,966,500 gallons  
Gallons handled per cartridge: 61,450 gallons  
Flow rate per cartridge: 2½ GPM

The above tests were made by the engine builder and show the effectiveness of the Cuno product. Cuno has continually stressed the advantages of full flow filtration over any partial filtration system. Their position on this point was proven by the test results supplied by the Armour foundation which showed that engine wear rates were considerably lower when full filtration was used in preference to partial filtration. Now, with the Micro-Klean filter available to supplement Cuno's edge type filter, the Diesel engineer is given additional tools to further the development of full flow filtration of lubricating oils.

## D. E. M. A. ELECTS GORDON LEFEBVRE PRESIDENT



View of speakers' table at luncheon during Annual Meeting of Diesel Engine Manufacturers Association.

**G**ORDON LEFEBVRE, President of the Cooper-Bessemer Corporation, was elected the new President of Diesel Engine Manufacturers Association, at the Association's Annual Meeting, held Dec. 10, in Chicago.

Otto H. Fischer, President of The Union Diesel Engine Co., and L. W. Metzger, Vice President of The Baldwin Locomotive Works, were elected new Vice Presidents of DEMA.

Robert H. Morse, Jr., Vice President and General Sales Manager of Fairbanks, Morse & Co., was re-elected Treasurer of the Association and Harvey T. Hill was reappointed Executive Director.

Elected to serve two years on the Board of Directors were George W. Codrington, Vice President of General Motors Corporation and General Manager of Cleveland Diesel Engine Division; E. J. Schwanhauser, Vice President of Worthington Pump & Machinery Corp.; A. W. McKinney, Vice

President of The National Supply Co.; Mr. Morse, and Mr. Metzger mentioned previously.

The following were elected to serve one year on the Board: C. S. Herbert, Executive Vice President, Enterprise Engine & Foundry Co.; W. E. Corrigan, Vice President, American Locomotive Co.; Robert E. Friend, President of Nordberg Manufacturing Co.; Mr. Lefebvre and Mr. Fisher.

The Annual Meeting, together with the DEMA engineers' session held on Dec. 9 and 10, comprised the most important and the most successful gathering that the Association has ever held. It was important because significant issues were discussed and dealt with; successful because real progress was made in the two days that the engineers and executives talked out their problems.

One of these was the growing seriousness of the situation with respect to supply and demand of Diesel fuel oil. To get an authoritative, first-hand

picture of the situation, the DEMA personnel had as their luncheon guests some of the top men in the oil industry, who represented the marketing division of the American Petroleum Institute. They included A. W. Peake, President of Standard Oil Co. (Indiana); L. S. Wescoat, President of Pure Oil Company; P. E. Lakin, Vice President of Shell Oil Co., Inc.; B. L. Majewski, Vice President of Deep Rock Oil Corp.; and John Day, Executive Secretary of Western Petroleum Refiners Association.

Mr. Schwanhauser summarized briefly the mounting demands of Diesel installations for fuel and lubricating oils. Mr. Majewski acknowledged that "you Diesel people have really thrown a load on us." This was amplified by Mr. Peake who said "the demand for all petroleum products—for Diesel engine fuel and lubricating oils in busses, trucks, tractors . . . has increased to a staggering extent since the war. We will not be able to meet all the requirements alone, but will have to bring in foreign production. That will take several years."

Mr. Wescoat explained that a shortage since the war of materials, manpower and transportation had hampered oil production, but said that the industry "was doing everything it could to cope with a problem which developed out of a clear sky, and which was never anticipated."

Mr. Lakin said that any study of Diesel oil specifications on the part of the Diesel industry, "that leads to simplicity and uniformity will enable the oil companies to do a better job." Mr. Majewski put the case more tersely: "If you are not too tough in this matter of specifications, you'll get more Diesel fuel."

Upshot of the discussion was that Diesel Engine Manufacturers Association agreed to make a survey of how much Diesel engine horsepower is now located in each state of the union, together with an estimate of how much this amount of horsepower would increase over the next five years.

\* \* \* \*

The Annual Meeting began with an account of DEMA's 1947 activities, together with its plans for 1948 and succeeding years. Mr. Schwanhauser, retiring President, reviewed the Association's legislative activities, educational program and furthering of public relations. During 1948, he said, DEMA will publish two books: "Marine Diesel Standard Practices" and a Spanish edition of "Standard Practices for Stationary Diesel Engines."

Commenting on the educational program, which is being undertaken with the cooperation of parts, accessory and oil companies, Mr. Schwanhauser said: "It is the finest job being done by any organized group of business men, in working to improve the quality of students being graduated to go to work in their companies."

\* \* \* \*

The engineers who had been delegated by their companies to represent them, met with Ralph

Boyer, Vice President of Cooper-Bessemer. A discussion of the Executive Committee's machinery Committee. Next came a request for preventing Surveying Engineers who was President of Engineers' Association.

T. M. R. Diesel sales including the progress of the American meeting with a session of the day.

In revising Diesel Engineers be well to a pamphlet engineers of separate departments would be n

George H. on the Association's consensus of the states were design. All students should in design w

At DEMA E right—Hans Co.; G. F. N Co.; Carl A. Locomotive V bun, Presiden

Second panel Chief Engineer Chief Engineer Diesel Engine motive Comp

Third panel v Engineer, Ent File, Chief Engineer, CI Motors Corp

Fourth panel Director of E Grieshaber, C Schwanhauser Machinery Co Chief

Fifth panel v in charge of Chief Engineer George Steve



personnel  
the top men  
marketing  
Institute.  
of Standard  
President of  
President  
Vice Presi-  
John Day,  
um Refiners

the mount-  
or fuel and  
pledged that  
a load on  
e who said  
s—for Diesel  
sses, trucks,  
ring extent  
to meet all  
to bring in  
veral years."

ge since the  
nsportation  
id that the  
ald to cope  
of a clear

el oil speci-  
ustry, "that  
enable the  
r Majewski  
are not too  
you'll get

esel Engine  
make a sur-  
power is now  
together with  
at of horse-  
ve years.

account of  
ts plans for  
wanhauser,  
tion's legis-  
and further-  
8, he said,  
rine Diesel  
edition of  
el Engines."

ram, which  
on of parts,  
wanhauser  
ne by any  
working to  
g graduated

ed by their  
with Ralph

L PROGRESS

Boyer, Vice President and Chief Engineer of Cooper-Bessemer Corporation, as their chairman. A discussion of bearings, led by George Steven, Executive Engineer for Worthington Pump & Machinery Corp., was the first event of the program. Next came the formulation of recommendations for preventing crankcase explosions—this at the request of Arthur R. Gatewood, Chief Engineering Surveyor of the American Bureau of Shipping, who was present. Gordon R. Anderson, Director of Engineering for Fairbanks, Morse & Co., discussed dual fuel engines.

T. M. Robie, Manager of Fairbanks, Morse's Diesel sales division, opened the second and concluding day of the engineers' session by reporting the progress made in setting up the meeting, next May, of the Oil & Gas Power Division of the American Society of Mechanical Engineers. The meeting will take place in St. Louis May 19 to 21. A session of DEMA's engineers will be held on the day previous.

In revising "Standard Practices for Stationary Diesel Engines" for its Spanish edition, it might be well to provide a supplement, in the form of a pamphlet, to take care of dual fuel engines, the engineers decided. They also concluded that a separate derating chart for turbo-charged engines would be necessary.

George H. Amberg, of DEMA's staff, gave a report on the Association's educational program. Consensus of the engineers was that most college graduates were interested more in sales work than in design. All the engineers present felt that the students should be given more college instruction in design work.

At DEMA Engineers Meeting: Top panel view, Left to right—Hans L. Wittke, Director of Research, Hallett Mfg. Co.; G. F. Nolte, Chief Engineer, The National Supply Co.; Carl A. Jacobson, Consulting Engineer, The Baldwin Locomotive Works, shaking hands with George J. Rathbun, President, The Rathbun-Jones Engineering Company.

Second panel view: Left to Right—Leslie D. Calhoun, Chief Engineer, Fulton Iron Works Co.; B. G. Valentine, Chief Engineer, Sterling Engine Company; T. H. Murphy, Diesel Engineering Dept. (Schenectady), American Locomotive Company, and Austin Sherman, Vice President, Hallett Mfg. Co.

Third panel view: Left to Right—Roy A. Hundley, Chief Engineer, Enterprise Engine and Foundry Co.; Charles E. Fike, Chief Electrical Engineer, and Knute O. Keel, Chief Engineer, Cleveland Diesel Engine Division, General Motors Corp., and Otto H. Fischer, President of the Union Diesel Engine Co.


Fourth panel view: Left to right—Gordon R. Anderson, Director of Engineering, Fairbanks, Morse and Co.; Emil Grieshaber, Chief Engineer, Nordberg Mfg. Co.; E. J. Schwanhauser, Vice President, Worthington Pump & Machinery Corp., and Ralph Boyer, Vice President and Chief Engineer, The Cooper-Bessemer Corp.

Fifth panel view: Left to Right—Robert S. Ogg, Engineer in charge of Patents, Lima-Hamilton Corp.; J. P. Hyde, Chief Engineer (Phillipsburg) Ingersoll-Rand Co., and George Steven, Executive Engineer, Worthington Pump & Machinery Corp.



# DIESELS MOVE 200-INCH MIRROR

By FRED M. BURT



**I**N 1936 the Belyea Truck Company started hauling steel and items of equipment to the top of Palomar Mountain in San Diego County, Calif., for the housing of a giant mirror which would enable man to peer much further into the secrets of the heavens; extending his vision to a range of one billion light years; a distance so great that no human mind can comprehend and understand it. (If all of the Diesel trucks in the world were to travel 1,000 mph. for 1,000 years, the combined mileages would hardly be a perceptible start on such a huge distance.)

Those were the days when the road up Palomar Mountain was just an improved trail. Loads were delivered to the foot of the mountain and then transferred to single Diesel units in order to negotiate the trail.

Also in 1936, the 200 inch diameter, 24 inch thick, 15 ton glass casting arrived in Pasadena, from Corning (N. Y.) Glass Company. Belyea Truck Company, along with its subsidiary Pacific Crane & Rigging Company, unloaded this valuable cargo from the railroad car to heavy duty trailer, Diesel tractor equipment, and transported it safely to the shops of Pasadena's California Institute of Technology for polishing.

During the next eleven years, work progressed until finally in October 1947, the final polishing was completed, with a surface finished to within two millionths of an inch of absolute accuracy. As a climax of years of fine service to Cal Tech, the Belyea companies were entrusted with the

moving of this most precious of optical instruments, (insured by Lloyds of London for \$600,000) to its mountain home.

Engineers of Cal Tech, together with Belyea key personnel, worked out details of the long trip. Particular attention was paid to the selection of equipment with emphasis being placed on even weight distribution and shock absorption.

The equipment used consisted of one Fruehauf, double goose-neck lowbed trailer pulled by one Diesel tractor. There were 42 Budd wheels and 42 Westinghouse air brakes on this unit. On the last 12 miles, up the mountain, in addition to the tractor in front, a similar Diesel tractor and a Diesel truck were used as pushers. This added up to 62 Budd wheels and 62 Westinghouse air brakes. The power units were Sterlings, F-C-S, with 150 hp. Cummins HB Diesel engines, 7851 Brown Lipe transmissions, 703 Auxiliary transmissions, splicer clutches, drive lines and universal joints. Gear ratio  $8\frac{1}{4}$  to 1, with 15 speeds forward and 3 reverse for a total of 18.

Due to the location of the 120 ft. x 120 ft., air-conditioned, optical shop, it was necessary to disconnect the lowbed trailer and move it about 100 ft. on 4 in. orange-wood rollers to a point under the craneway. The only alterations on the

trailer was the welding of I-beams to the bed to further equalize the stress and strains.

Thin aluminum plywood foil, and brown paper protected the "eye's" surface; the mammoth "cell" with which it will be mounted in the yoke-and-horseshoe telescope fittings, already had been bolted to the waffled underside. Five red-painted I-beams were fastened to this cell. The 50-ton crane picked up this 35-ton package and lowered it onto the trailer bed, fitting it to a sponge rubber base and permanent steel anchors, then bolting it fast. After this 45-minute job, another hour was taken in lowering and fixing the five-ton 20 ft. square, 8 ft. high, packing-box cover over the mirror for protection.

Installed inside the box on top of the mirror, were delicate, vibration-measuring instruments registering on a machine outside the building, to show a red light at a movement danger point, with a good safety factor. Project engineer Bruce Rule and Marcus Brown, in charge of the Cal Tech Optical Shop, watched the instrument while this first movement was made, in which the "Eye" had to make

a 90-degree  
3/4 inch cl  
had been  
the slide  
according to  
whole job.  
Driver Lloyd  
goose-neck  
lowbed tra  
Hill, Chief  
and Harvey  
and Rigg  
the directio  
moving.

The mirror  
vember 12th  
bad weather  
19th, when  
127 mile tri  
3:30 A.M.  
on time. Fi  
led by Sgt.  
big motorca  
relief drive  
that register  
from the ga  
were Cal  
Diesel tract  
up the moun  
lubricants, s  
ing outfit in  
extinguisher  
a master mo

The first leg  
hitch, arriv  
ahead of sch  
1/2 to 15 mi  
to about 20  
light soon in  
sumption fo  
With a 70 t  
preparations  
three small  
was laid wit

At the Galiv  
tribution, th  
insert an ei  
the projecti  
they were re

The second  
for between  
with elevatio  
above sea lev

were being  
from the obs  
due to an un  
But this did  
handled muc  
out too mu  
extraordinary  
tingencies. I





the bed to

rown paper  
smooth "cell"  
the yoke-and-  
had been

red-painted  
The 50-ton  
and lowered  
orange rubber  
then bolting  
er hour was

e-ton 20 ft.  
er over the

mirror, were  
nts register-  
y, to show a  
with a good  
e Rule and  
ech Optical  
s first move-  
ad to make

a 90-degree angle turn around a corner with but  $\frac{3}{4}$  inch clearance. Every inch of this movement had been carefully plotted with a liberal use of the slide rule, and blue-printed, comprising, according to Jack Belyea, "the toughest part of the whole job." Then it was a simple matter for Head Driver Lloyd Green to back the Diesel tractor and goose-neck "jeep" under the gooseneck of the lowbed trailer for a smooth connection. Byron Hill, Chief Engineer of the Palomar Observatory and Harvey Sitton, Chief Rigger for Pacific Crane and Rigging, Inc., were also closely concerned in the direction of the operations of preparation and moving.

The mirror delivery was first scheduled for November 12th and 13th, but the forecast indicated bad weather, so it was postponed to the 18th and 19th, when a good forecast was forthcoming. The 127 mile trip to Escondido was scheduled between 3:30 A.M. and 6 P.M. and the trip started right on time. Fifteen California Highway Patrol officers led by Sgt. C. M. Martin paced and trailed the big motorcade. In the cab with Lloyd Green and relief driver Earl Winston, was the instrument that registered the amount of vibration picked up from the gages on the mirror. In passenger cars were Cal Tech engineers. Following were the Diesel tractor and truck that were to be pushers up the mountain. The latter carried Diesel fuel, lubricants, spare tires, water, a lighting plant, welding outfit including flame cutting equipment, fire extinguishers, and other tools and supplies, also a master mechanic.


The first leg of the journey was made without a hitch, arriving in Escondido at 5 P.M. an hour ahead of schedule. The travel speeds varied from  $\frac{1}{2}$  to 15 miles per hour, except for a speeding up to about 20 mph. on a smooth stretch, but the red light soon indicated a slow-down. Diesel fuel consumption for the three units was 129 gallons. With a 70 ton weight to be provided for, special preparations had to be made at four bridges. At three smaller ones, 4 in. x 12 in. x 18 ft. decking was laid with shoring beneath.

At the Galivan Bridge, to give a wider weight distribution, the trailer was jacked up enough to insert an eight-wheel dolly on each side under the projecting I-beams. After crossing the bridge they were removed.

The second 33 mile leg of the trip was scheduled for between 5:30 A.M. and 3:30 P.M. the next day, with elevations varying from 60 feet to 5500 feet above sea level. A 5 A.M. when the Diesel engines were being warmed up, Byron Hill came down from the observatory to tell of very poor visibility due to an unpredicted flash storm having come up. But this didn't faze Jack Belyea as they had often handled much harder jobs in worse weather, without too much trouble, due to their policy of extraordinary provisions to meet all possible contingencies. He decided to move on to Rincon at



Sterling tractor with Cummins Diesel engine begins long haul up Palomar Mountain with precious cargo.



At the observatory after long haul up mountain mirror rest on trailer. Packing box has been removed.

the foot of the mountain, 12 miles from the destination. Starting at 5:30, this trip was made ahead of schedule at from 4 to 6 mph., without incident. At Rincon, a ranger coming down the mountain through hail and snow, reported zero visibility, but no indication of a freeze to affect traction. So Jack Belyea again decided that his equipment and crew were fully equal to the occasion. The extra goose-neck "jeep" was removed that curves could be negotiated. The pusher tractor and truck units took their places, to complete the trip at 11 A.M., about four hours ahead of schedule. They had to slow down to a mere crawl when crossing about a dozen cattle guards, whose cross members were spaced 8 in. apart.

It rained at first, and at higher altitudes, there was sleet and then snow. When among trees, men in the rear truck couldn't see the head end. A man stood on the mirror case, all the way up, to assist in signalling, in addition to the code of the blinker lights on the sides and rear of the case, controlled from the lead cab.


All of the careful engineering, the skill of the drivers, and the dependable equipment finally paid off when the long rig, with its precious cargo, finally pulled up to the observatory, backed in and the mirror was taken from its case, with the heavy weight of responsibility lifted from Jack Belyea and his crew. One of the Cal Tech officials was seen to point to the sign "Dependable Delivery" on the side of a Belyea truck, as he shook hands with the driver. According to Robert D. Belyea, it was only through the splendid cooperation of the State of California Highway Department, Los Angeles County Road Department and the San Diego County Road Department, that this job was so expeditiously accomplished with no untoward incident.

But if you will ask one of the Belyeas (as I did) they will tell you that in-so-far as difficulty and responsibility is concerned, this was just another job, albeit unusually prominent in public consciousness and widespread press consideration. In fact it can truthfully be said that they are engaged in the moving of anything that needs moving, of any size, quantity, shape or material, that falls within the realm of feasibility. The harder and more unusual the job, the greater the likelihood that the Belyea companies will be called upon for service.

Included in their hundreds of items of diverse equipment, to meet nearly every conceivable need, are lowbed trailers that will move right along with 150 ton loads, pulled by one Diesel tractor. The slogan "Dependable Delivery" is based heavily on the 44 Diesel units, 10 ton and up capacities. The majority have Timken 4-wheel drives, all have three axles. Diesels are used for all of the heavy work. The majority are Sterlings, with some Autocar, Mack, Peterbilt, and White units, all powered with Cummins, 150 hp. Diesel engines, except for three special jobs of 200 hp. 29 are tractors, 15 are trucks.

The three units used on the mirror-moving job, had nothing special about them, just picked out of the big fleet of Diesels kept in top operating condition at all times, under the Belyea standard maintenance and overhaul program. With three extra Cummins Diesel engines on hand, whenever an engine requires an overhaul, it is pulled and a previously overhauled unit takes its place.

Diesel power is also extensively used in the companies' numerous bull-dozer, ditch-diggers, shovels, cats, and various cranes and hoists of up to several hundred tons capacities.



Drawing of "Vapor-Phase" installation at Shepherd Tractor and Equipment Co., Los Angeles, California

**F**IFTEEN years ago anyone who would have stated that Diesel engines could operate most efficiently at cooling water temperatures upwards of 212° F. would have been hooted out of the clan. It was impossible! Cooling water from the engine at 140° F. was a definite risk, let alone 212°. True, many operating engineers had experienced temporary periods, due to cooling system breakdowns, when temperatures reached the boiling point without any apparent damage to the engine, but in such cases engines were shut down and repairs made. In isolated cases, however, it was sometimes necessary to keep the Diesels operating, regardless of cooling system failure. One case in particular is interesting to note. It happened in Virginia at an REA power plant. The supervisor had been called to Washington and had left his young assistant in charge with instructions to keep the plant operating under any conditions.

The day after the supervisor arrived in Washington he received a wire from his assistant to the effect that the cooling tower at the plant was out of commission and that he had better return home pronto. The return trip was the fastest ever made.

As he drove down the mountain pass into the Shenandoah Valley he saw the plant below in the Valley. And, he noted also the bright red of fire engines clustered around it. Fearing an explosion

or some other accident he gave the car a little more throttle.

As he drove up to the plant, he noticed no undue commotion, as a matter of fact everything seemed normal except for the presence of the fire trucks and the fact that the Diesels were a little noisier than usual. He found out what had happened very quickly. As he had been telegraphed the cooling tower was out of commission and his assistant had had the foresight to uncover the cooling pipes leading to the tower and requisition the local fire company to spray them with cold water and thus permit the continued operation of the Diesels.

Inside the plant everything was going as smoothly as could be expected. The engines were knocking and steam was escaping from a return valve. That was all that seemed to be happening. He experimented with the injection timing and cut down the fuel supply slightly and found that the engines could develop rated horsepower with less fuel than previously. In so doing the knock was eliminated and the engine seemed to operate more quietly than he had ever known it to.

In the meantime a valve in the return line was cracked slightly to allow the steam to escape more freely and keep the pressure down.

## DEVELOPMENTS IN HIGH TEMPERATURE COOLING

By FRED M. BURT and BRUCE C. SISSON

The engine operated for three full days under these conditions while the cooling tower was being repaired. That was how one operator learned that Diesels can operate at the boiling point.

The above described event occurred in 1937, just about the same time that experimentation was begun on high temperature cooling in this country. However previous to this beginning, English engineers were studying the effects of high temperature operation on cylinder liners. The research work carried on by E. G. Williams for the British Institute of Automobile Engineers resulted in some very pertinent conclusions. It was found that rapid wear occurred at cylinder wall temperatures below 194° F., while at temperatures from 194° F. to 536° F. liner wear was practically negligible. In addition it was found that while operating in the higher temperature range none of the corrosive elements of burned fuel could condense and form metal-destroying compounds such as sulphuric, nitric and carbonic acids.

In America, as usual, someone decided to take advantage of these tests and use them in a way which would benefit Diesel users. It had long been known that only 1/3 of the fuel energy going into a Diesel combustion chamber came out as shaft horsepower, the rest went into heating jacket water and oil, stack and radiation losses, and mechanical friction. Why, thought the engineers of Engineering Controls, Inc., can't we raise the efficiency of internal combustion engines by raising operating temperatures to the point where useful heat may be extracted from the cooling water and at the same time increase the life of the engine itself. That step was the beginning of the Vapor-Phase system.

They began by taking a page from the steam engineer's handbook, the fact that at 212° F. water under atmospheric pressure requires 970 Btu's per pound to change it into steam at 212° F. Whereas 1 Btu is sufficient to raise one pound of water 1° F. at lower temperature. The advantage of utilizing this latent heat of vaporization for cooling cylinder is that heat is transferred rapidly and efficiently, much faster than by water below the boiling point.

The operation of a Vapor-Phase unit is simple. It does not begin to operate until the engine comes up to boiling temperature. A thin layer of steam bubbles form around the hottest part of the cylinders, these bubbles detach themselves and pass to the "Vapor Phase" unit above the engine where




days under  
ver was being  
learned that  
int.

in 1937, just  
entation was  
in this coun-  
ning, English  
of high tem-  
The research  
or the British  
ulted in some  
found that  
temperatures  
from 194° F.  
ly negligible.  
operating in  
the corrosive  
use and form  
s sulphuric,


ded to take  
m in a way  
ad long been  
going into  
out as shaft  
jacket water  
l mechanical  
of Engineer-  
efficiency of  
ng operating  
ul heat may  
and at the  
engine itself.  
Vapor-Phase

ne steam en-  
2° F. water  
70 Btu's per  
° F. Where  
nd of water  
dvantage of  
on for cool-  
rapidly and  
r below the

it is simple.  
engine comes  
er of steam  
of the cylin-  
and pass to  
engine where



Two Caterpillar Diesel-electric sets used to supply heat and power. Plant Engineer G. G. Thomas Sr. at left. Exhaust boilers seen above engines.



"Vapor-Phase" unit shown at top left flashes steam generated by Diesels. Auxiliary electric immersion heaters at top heat water when additional steam is required.

steam is formed at 212° F. This steam is available for heating or processing work. After this it is condensed and the condensate returns to the Vapor-Phase unit where it is heated to 212° F. again. It then passes to the water pump for recirculation through the engine. No steam is formed in the engine to create steam pockets. Most modern engines are designed for a temperature differential of not more than 10° F. which is suitable for Vapor-Phase. Older engines may require some alteration for use with the "Vapor-Phase" system. This may consist in removing baffle plates, etc. Another factor to be considered is the size of the water passages in the cylinder head. These must not be restricted. However most modern engines have sufficient head cooling capacity.

An operating temperature of 212° F. is not the only one possible with Vapor-Phase. Depending on the pressure of the system, temperatures up to 240° F. can be used. The pressures and the resulting temperatures are dependent upon the amount of pressure the water seals will safely stand. Higher temperatures are useful in processing operations where higher steam temperatures are required.

Some of the advantages of this system of cooling include the following: Faster heat transfer from engine cylinders to cooling water, more uniform liner wall temperatures resulting in uniform piston-cylinder clearances during full stroke, better cylinder lubrication, prevention of condensation within the cylinder, with the result lessening of liner and piston wear.

The operation of the "Vapor Phase" system can best be explained by reference to an actual installation made recently on the West Coast. In the large, new plant of the Shepherd Tractor and Equipment Company in Los Angeles, in addition to the ultra-modern layout and equipment units discussed in the October 1947 issue of DIESEL PROGRESS, a new Diesel plant is now in full and constant operation. Besides producing all the power required for the many shop machines and tools, the air compressor, three 300 ampere arc welders, and various other items of equipment,

the engines through use of the "Vapor-Phase" Cooling and waste heat recovery systems, steam heat is supplied to the huge Parts Department and stock room.

Power is supplied by two "Caterpillar" Diesel-electric sets, 110/220 volts, 3-phase, 60-cycle each of 37.5 kva. They are housed in a 20x40 ft. basement room with a high ceiling. Even with the "Vapor-Phase" unit and exhaust heat exchanger in the room the temperatures never become uncomfortably high.

To outline the heat recovery analysis—the average power load is 45 hp. Diesel fuel consumption at .45 lbs. per bhp. hour gives an hourly fuel consumption of 20.1 lbs. At 19,000 Btu's per pound of fuel, this represents an input of 380,000 Btu's for the 45 hp. output. About 31%, or 118,000 Btu's, is used for power, leaving a balance of 262,000 Btu's as an hourly heat loss without the "Vapor-Phase" heat recovery from the water jackets and exhaust manifold, and the heat recovery from the exhaust boilers. At this average rate of power output, about 55% of this wasteheat, or 145,000 Btu's, is recovered by the "Vapor-Phase" and exhaust boiler systems, thus giving the plant an overall thermal efficiency of approximately 70%—quite a bit better than 31%.

Two 10 kw. immersion heating elements, installed in the line between the waste heat boiler and the "Vapor-Phase" unit, utilize electrical power from the generators to supply more heat when it is required. In this manner the power and heating loads may be balanced off. In addition to supplying heat for the building, the power plant itself is kept at a uniform temperature regardless of engine load with resultant better operation.

The "Vapor-Phase" system has been utilized extensively on the West Coast and has been applied to a wide range of engines including automotive and stationary. In one particular instance the system was chosen for its silencing effect on Diesel exhaust. The installation was made on a Navy sound truck which required a sound level of 50 decibels at 10

feet with the International Harvester Diesel operating at full load. Engineering Controls, Inc., was given the job. The engine compartment was specially insulated to reduce mechanical noise. A special air intake silencer was installed on the engine. A "Vapor Phase" unit and a waste heat boiler were installed on the Diesel and a special blower and condensing unit was installed to condense the steam in the system. The result of the installation was the reducing of the exhaust temperatures to under 250° F. and the reduction of noise to the required minimum which the Navy required.

The U. S. Navy has shown an increasing interest in "Vapor-Phase." One Naval installation in particular aboard an auxiliary vessel utilized a single "Vapor-Phase" unit for 4 Diesels including a 350 hp. Atlas propulsion engine and 3 auxiliaries. The system permitted keeping the engines at operating temperature even when they were shut down by operating one auxiliary. Thus the utilization of engine power without the customary warm up periods was possible. In addition to this the engines supplied hot water and heat to the vessel. The addition of small exhaust boilers on the auxiliary Diesels reduced exhaust temperatures to 230° F. as well as adding considerably to the heat recovery ratio of the system.

The utilization of sewage gas in gas engines is entirely feasible with the "Vapor-Phase" system even if the gas contains the very corrosive H<sub>2</sub>S. No scrubbers or purifiers are required inasmuch as the cooling system operates at temperatures well above the dew point of corrosive substances. Thus all harmful acids are carried out of the engine in vapor form. In addition, the steam generated can be utilized in heating the sludge digesters or other processing equipment.

In addition to increasing the thermal efficiency of internal combustion engines, "Vapor-Phase" is said to increase the mechanical efficiency also as much as five per cent and higher. The reason seems to be the higher operating temperatures which cut down friction losses.

**R**ATED at 35 hp. and 60 hp. per cylinder for the 6¼ in. x 9 in. and the 8½ in. x 11½ in. respectively, the Model 31A is the latest addition to the line of Diesel engines manufactured by Fairbanks, Morse & Co.

A brief announcement of the first of these engines was made in 1944 when it was installed in a "floating laboratory," and given a thorough test in several seasons of sea service. Regular production was also started at that time and numerous installations have since proven the excellence of the design. Construction details have not previously been released and it is therefore believed that a complete description of this engine is of considerable interest at this time.

In the Fairbanks-Morse Model 31 is embodied the experience gained by over a century of precision machinery building augmented by over 5,000,000 hp. of heavy duty Diesel engines.

One of the features of the Model 31 is its cylinder block which is a single casting, incorporating both crankshaft bearings and cylinder bores in the one piece so that proper alignment between the two is assured. Its depth and wall construction give rigidity without excessive weight. Large openings on both sides of the block afford easy accessibility to all main and connecting rod bearings. This one-piece cylinder block also serves as a mounting

for all of the working parts including the cylinders, crankshaft, camshaft and injection pumps thus assuring proper relative alignment and position behind the various parts. Elimination of the possibility of hidden leaks and contamination of the lubricating oil by the cooling water is accomplished by the fact that there are no cored water or lubricating oil passages in the block.

The arrangement of the cylinder liners in the block permits free expansion at the lower end and the use of the integral water jacket avoids the necessity of a water seal at this point. The crankshaft is assembled in the lower part of the block and is held in place with bearing caps carefully fitted between heavy guides.

The engine is equipped with removable cylinder liners of the type used in other models of Fairbanks-Morse Diesels. These have the added advantage of integrally cast, leak-proof, water jackets. With the water confined in a single casting, leakage due to jointed construction is thus eliminated. It is cast of special close-grained iron of great tensile strength, and machined and honed to close tolerances, resulting in a perfect sealing of the combustion gases. All liners are interchangeable and the internal passages between cylinder liner jacket and cylinder head provide uniform distribution of cooling water.

The chief characteristic of the cylinder head proper is its unusual simplicity. There are no exhaust or intake valves; the heads are fully water cooled, with special attention given to cooling the portion of the head surrounding the injection nozzles. Furthermore, the head can be lifted without disturbing either the water or starting air manifolds.

The crankshaft in the Fairbanks-Morse Model 31 Diesel engine is of unique design. It is a one-piece casting from a high strength semi-steel alloy. Extra large main and connecting rod journals are used to provide rigidity of structure. This type of construction allows the use of hollow crank pin and main journals which result in increasing their strength with no increase in weight.

The wearing surfaces are machined to very close limits and the final grinding and lapping operations reduce the journals to their exact dimension, leaving a perfect bearing surface. The crankshaft is dynamically balanced in a special machine while being rotated at engine speed.

Transverse section of the Model 31 F-M Marine Diesel showing fuel, lube and cooling systems.

## TWO-CYCLE MA

The steel connecting rods are die forged and are fitted at the upper end with a precision type bronze bushing so accurately fitted that the assembly requires no hand fitting or special machining. The crankpin bearing shells are also precision type, interchangeable top and bottom and also interchangeable with the main bearing shells. The bearings require no hand fitting and are easily and accurately assembled with no shims being used. The piston and connecting rod can be withdrawn without disturbing the crankpin bearing. This is accomplished by using two sets of bolts—one set to connect the rod to the bearing box and the other set to clamp the two bearing halves together. No compression shims are used at the connecting rod foot as this detail is made a part of the piston construction. The connecting rod bolts are readily accessible through the large openings on each side of the crankcase.

The camshaft is a drop forging, machined all over, with the cam profiles heat treated and hardened. Its construction is simple in that it carries only the integrally forged injection pump cams. It rotates in pressure-lubricated, precision type bearings which are supported by the cylinder block itself. Its location is close to the injection pumps. One central system provides oil under pressure for all parts in the engine requiring lubrication. A built-in lubricating oil pump delivers oil at controlled pressure to the manifold from which it is distributed as required.

The same system also provides for oil cooling the pistons. The cooling oil is forced up through a hollow connecting rod to the piston pin and thence into the crown of the piston itself. From this space the oil circulates down inside the piston, cooling the entire skirt, and is then ejected into the crankcase sump.

The piston is of the trunk type, made of close-grained cast iron. Its length is great in proportion to the diameter, thus reducing the side pressures and increasing the life of both the piston and cylinder. A special feature is that a separate, one piece piston pin bracket, securely bolted to the inside of the piston, permits a smooth unbroken external cylindrical wall.

Cylinder compression is adjusted by means of shims, between the piston pin bracket and piston. With precision bearings there is little need to change these shims. Their location eliminates the possibility of loss or improper assembly when pistons are removed.

Individual inivalve fuel injection pumps are used of the variable beginning type which automatically retards the timing at reduced speeds. The injection pumps located adjacent to each cylinder are

connected to lengths of pumps and fuel oil pump type transfer injection pump nozzle with piece, supplied filter is used in addition, each in filter to g

Engine speed type governor particularly for controls the start wise movement small movement linkage

A balanced, blower is driven from This blower proper pressure fuel required a generous are necessary tical regard


The scavenging through a set valves, per closed after the effect of and at the the cylinder at the moment

The exhaust cooled. It is efficiently a is moved the single exhaust

Cooling water inlet to the directly into uniform dis

The unusual inspection exhaust manifold rings and through the

A starting controlled by system "dead" ing is fast "ahead" to





# CLE MARINE DIESEL BY FAIRBANKS-MORSE

arged and are precision type at the assembly machining. precision type, and also inter-shells. The and are easily shims being can be with-pin bearing. ets of bolts—ring box and aring halves used at the made a part necting rod e large open-

ned all over, d hardened. carries only p cams. It n type bear-inder block tion pumps. der pressure lubrication. ivers oil at from which

oil cooling up through on pin and itself. From e the piston, ejected into

de of close- a proportion de pressures piston and eparate, one lted to the h unbroken

y means of and piston. le need to eliminates the mbly when

ps are used automatically. The injection-cylinder are

connected to the injection nozzles by short, equal lengths of high pressure injection tubing. The pumps are operated by a camshaft. A built-in fuel oil pump of the position displacement gear type transfers fuel from the service tank to the injection pump manifold. A simplified injection nozzle with the needle sleeve and seat in one piece, supplies fuel to the cylinder. A primary filter is used in the low pressure fuel line, and in addition, each injection nozzle has its own built-in filter to give further protection.

Engine speed is controlled by a built-in hydraulic type governor with characteristics designed particularly for Marine service. A single lever controls the starting, stopping and reversing. No end-wise movement of the camshaft is required. A small movement of the air start cam by a positive linkage is only change when reversing.

A balanced, oscillating type, positive displacement blower is built into the main cylinder block and is driven from the forward end of the crankshaft. This blower furnishes an abundance of air at the proper pressure to completely burn the full load fuel requirements with a clear exhaust and with a generous overload reserve. No reversing valves are necessary on the blower as its operation is identical regardless of engine rotation.

The scavenging air is admitted to the cylinder through a set of low-resistance, automatic leaf type valves, permitting the scavenging ports to be closed after the exhaust ports. This eliminates the effect of pressure surges in the exhaust pipe and at the same time makes the air pressure in the cylinder equal to the scavenging air pressure at the moment of port closing.

The exhaust manifold is fully enclosed and water-cooled. It is designed to conduct the burned gases efficiently away from the exhaust ports. The gas is moved through an unrestricted passage to a single exhaust outlet near the center of engine.

Cooling water enters the engine through the inlet to the exhaust manifold jacket and thence directly into the cylinder jackets, thus providing uniform distribution to each cylinder.

The unusual features of design include large inspection covers which are provided in the exhaust manifold so that the cylinder, liner, piston rings and the piston may be easily inspected through the exhaust ports.

A starting air valve in each cylinder head is controlled by means of a pilot air system. With this system "dead spots" are eliminated and maneuvering is fast and reliable. Changing from the "ahead" to the "astern" position on the starting

system involves moving only one small cam. No air cylinders or similar devices are required and the action is positive.

The design of the engine also includes a built-in air compressor, single stage, which is water cooled and which utilizes the same drive as the scavenging blower. It has ample capacity for all normal maneuvering, even in tug-boat service, and is so located as to be readily accessible for piping.

Other built-in engine auxiliaries available on the Model 31 Diesel engine include two identical reversible lubricating oil pumps (pressure and sump), two identical reversible centrifugal water pumps (jacket and raw water), a fuel oil pump, and a slow-speed reciprocating bilge pump.

One of the features claimed for the Model 31 Diesel is its unusual accessibility. A series of conveniently located openings on both sides of the engine allow plenty of room for inspection and servicing without dismantling the entire engine. A crankshaft extension is provided at the forward end of the Fairbanks-Morse Model 31 Marine engine for use in driving such additional equipment as an auxiliary generator, deck wash pumps, etc. In addition, a clutch drive is available except for the 7 and 8 cylinder 8½ x 11½ size, for driving a winch or other deck gear. An extra bearing


located in the pump drive housing supports the shaft extension so that either torsional or side loads may be applied without fear of distortion. The reduction gear is in keeping with the heavy duty design of the other engine parts. The gear ratio is such as to allow the selection of the most efficient propeller. Both high and low speed shafts are of unusually generous proportions and are supported by large double row, spherical roller bearings on each side of the gears. A double cone Timken thrust bearing is provided on the low speed shaft. The gears are single helical type, cut from heat treated alloy steel.

The reduction gear contains its own lubricating oil and a splash system provides copious lubrication to the bearings and gears. The gear case is water-cooled by the engine circulating water.


Alignment with the engine crankshaft is assured by bolting and dowelling the substantial gear case to the same base rails which support the engine. The low speed shaft is fitted with a coupling half.

The Model 31 Fairbanks-Morse Diesel engine is available for marine or mobile service in two cylinder sizes. The 6¼ in. x 9 in. has a rating of 35 hp. per cylinder at 720 rpm. The 8½ in. x 11½ in. engine is rated at 60 hp. per cylinder at 525 rpm. Both sizes are available in 5, 6, 7 and 8 cylinder units.

Operating side of F-M Model 31A6¼ Marine Diesel with reverse gear. New model is fully enclosed and streamlined.



Fuel system assembly showing fuel manifold, injector pumps and short, equal-length tubes to injection nozzles.



# Great Lakes Diesel Cruiser

By DOUGLAS SHEARING



Luxury cruiser *Cappy* has an all-steel hull, is 67 ft. 3 in. l.o.a., 16 ft. wide and is powered with a pair of General Motors "71" Diesels.



Deck house is occupied by the main salon with luxurious appointments.

WHEN a Great Lakes shipping executive buys a Diesel yacht that's news, but when he incorporates her under the name of *Cappy* Inc. of Wilmington, Delaware, that's even better. Gene C. Hutchinson of Cleveland shipping fame named his new 67-footer after his father, the late Captain C. L. Hutchinson, whose nickname now graces the transom of the new boat.

The *Cappy* was built by the Burger Boat Company of Manitowoc, Wisconsin. She was designed by Philip L. Rhodes of New York. Both builder and architect contributed in making her one of the sleekest and most comfortable yachts on the inland waterways. She is 67 feet 3 inches overall, 64 feet 5 inches on water line. Her 16 foot beam and 4½ foot draft round out her vital statistics. She is of all-steel construction with 3/16 and ¼ inch hull plating. Her deck house is 10 and 12 gauge steel.

The *Cappy's* power plant consists of two General Motors Diesels driving through a pair of Twin Disc 2:1 reduction gears. The Diesels are rated at 165 hp. each. She carries 1000 gallons of fuel, enough to give her a cruising range of 1,200 miles. Auxiliary power is furnished by two Sheppard Diesels, a one cylinder 6 kva. and a two-cylinder 13½ kva. set. These auxiliary units carry a heavy power load which includes an electric range, Frigidaire, freezer, and lights as well as the auxiliary and navigating equipment.

The vessel is very roomy as her 16 foot beam will testify. The space above deck is occupied by the pilot house and deck house, the latter serving as

the main salon. It is accessible from the pilot house and is quite spacious. It is finished in bleached mahogany paneling and is handsomely furnished with a table, buffet and chests as well as a built-in leather lounge. Just forward of the deckhouse on the lower level is the galley, completely electrified utilizing 110 volts A.C.


Forward of the galley is the captain's stateroom and the three man crew's quarters. These latter quarters are unused at present inasmuch as Captain Nelson is the only full time crew member. Captain Nelson recently retired, was formerly skipper of the *C. L. Hutchinson*, one of the Hutchinson line ships. The owners' quarters and guest staterooms are located aft, with the owners' quarters extending the width of the ship and having a private bath. The two guest cabins share the remaining bath. 500 watt electric heaters keep these quarters warm.

The pilot house is well equipped and has many of the devices found on much larger ships. A Bludworth direction finder, a 100 watt Western Electric ship to shore phone, a Sperry automatic pilot and Solenaid electric clutch controls round out this department.

Other auxiliary equipment aboard the *Cappy* includes Blackmer bilge pump, Burke water system, Portable Light Co. search light and an Ideal electric windlass with 1 hp. motor.

Inasmuch as her owner has incorporated the *Cappy* in Delaware, her home port of registry is Wilmington but one can be sure that her heart is in the fresh water lakes where she was built.

Below: General arrangement of the *Cappy*.



IMPROV  
fication of  
about severa  
largely the  
factors arisin  
cedented des

To meet suc  
ers are re-e  
In many ins  
credit for the  
longs to the  
design and p  
and means  
blocks, conn  
blower hous  
only has pro  
this planning  
is also treat

Ingenious ne  
developed to  
handling me  
set-up time;  
steadily repl  
individual op

As a result e  
greater accur  
held to closer  
proved. Wit  
focused on th  
ponents, eng  
fied and mad  
improvement  
understandab  
such remarka

It must be r  
not necessari  
from standar

\* Vice Presid  
Lewis Machi



# New Machining Methods Simplify Diesel Engine Manufacture

By E. K. MORGAN\*

**I**MPROVED Diesel engine design and simplification of large engine components has brought about several new concepts of machining. This is largely the result of a combination of important factors arising from an urgent as well as unprecedented demand for Diesels as a power source.

To meet such conditions progressive engine builders are re-evaluating their production facilities. In many instances, it is found that much of the credit for the progress already made rightfully belongs to those engineers who have coordinated design and production plans to develop new ways and means of producing engine beds, frames, blocks, connecting rods, heads, crankshafts, yokes, blower housings, and similar other parts. Not only has production been a first consideration in this planning, but assembly of the finished parts is also treated with equal importance.

Ingenious new tooling ideas are constantly being developed to speed machining; improved work handling methods are devised to eliminate lost set-up time; multiple purpose machine tools are steadily replacing single purpose machines for individual operations.

As a result engine parts are being produced with greater accuracy. Specification requirements are held to closer limits, and machined fits vastly improved. With more and more attention being focused on the value of accurately machined components, engine assembly is automatically simplified and made easier. Granting that this general improvement in the Diesel field exists, it is readily understandable why these engines are establishing such remarkable performance records.

It must be realized that a new tooling idea does not necessarily mean a revolutionary departure from standard machining practices. In short, a

new idea may merely be the use of existing equipment to better advantage. The idea in this instance would be a different approach, a short cut, say, to an ordinary machining problem.

An excellent example illustrating this particular point is that of milling a crankshaft bearing seat bore, see Figure I. With the exception of one large West Coast Diesel engine builder in whose plant this idea recently originated, most companies perform the operation by either boring or planing. In either instance, the engine base, if large, must be placed flat on the machine table. If the circular bearing seats are planed, considerable time is necessarily consumed in this method.

Assuming that bearing seats are bored in the conventional manner, the caps must be bolted in place to obtain matched fits. Then, before removing the caps, they must be properly marked to assist in final crankshaft assembly. When boring bearing seats, the operation is ordinarily performed in one of two ways. They may be bored *individually* or *simultaneously*, depending upon the type of boring bar available.

If bearings are bored one at a time, a single fly cutter type tool is used. In this procedure, it is necessary to remove the tool after each bore is completed. The cutter is then placed in a different slot in the bar to correspond to the succeeding bore. Resetting the tool each time not only requires valuable productive time, but also increases the possibility of error because of repeated settings. In addition, an internal type support must be used to steady the bar. A bore may be bushed in this case, or a simple internal support fixture used. Both, however, require added set-up time.

Bearing seats may be bored simultaneously on smaller type engines. Should this practice be followed, a special type boring bar is required. Cutter slots may be properly spaced in relation to the bearings, and a separate block type cutter

placed in each of these slots. When this work is handled on a horizontal boring machine, the operator places the cutter block in the bar before engaging the machine feed to complete the bore.

Still another method exists for simultaneously boring bearing seats. This method is similar to boring with block type tools but is accomplished with expanding and retracting type cutters, mounted in a special Davis boring bar. When this type of bar is used, it is necessary to mount the bearing caps in place, and also to bolt to the end of the engine case or block, a stop fixture which activates the internal mechanism. This, in turn, expands and retracts the cutters as they are fed through the work—refer to Figure II.

Each of these methods has its particular advantages and disadvantages; through comparison, the progressive manufacturer will readily see how a new tooling idea, such as milling the crankshaft bearing seat bore, can improve production, especially on large engines.

Exploring this new tooling idea further, it is found that the engine base is mounted on the machine table in a vertical position rather than horizontally. The crankshaft bore is now at right angles to the machine spindle. Through the use of a simple angular milling attachment on any standard type horizontal boring machine, it is possible to mill all bearing seats in a single work setting. This method of boring requires a milling cutter of the same diameter as the bore.

Work is rapidly and accurately positioned in relation to the cutter by engaging the machine feeds. As one bearing bore is finished, the machine table or column is moved to the second bore and so on until the entire boring operation is completed. Alignment of the bores in this case depends entirely upon the traversing accuracy of the machine.

Required speeds and feeds are easily obtained. To

\* Vice President in Charge of Sales, Giddings and Lewis Machine Tool Co.




Fig. 1. Above milling crankshaft bearing seat bores on a horizontal boring, drilling and milling machine. An angular milling attachment is used.





Fig. 11. (left) Caps will be bolted in position and all crank bearings bored simultaneously. Expanding retracting type cutters are used. Stop block is bolted to end of engine block to activate cutters.

Fig. 111. (below) Boring cylinder liner seats with a special cutter head. Machine has adequate power to make machining cuts simultaneously.



present the work to the cutter, the table feed is used on table and planer type machines, while column traverse is engaged to feed the cutter on floor type machines.

Milling the crankshaft bearing bore as outlined has definite advantages. It is possible to turn or mill the bearing caps on another machine tool, and the accuracy of the overall operation is such that caps become interchangeable. As a result they do not have to be marked for subsequent assembly.

In those instances where it is necessary to face mill bearing cheek pads, this machining operation can be easily accomplished in the same work set-up and using the same tooling arrangement. The milling cutter is quickly positioned by raising or lowering the machine headstock. Table or column feed is engaged for cut depth. For example, all right sides of pads are milled with the angular milling head in the correct position. When this operation is completed, the milling head is turned 180° and the left sides of the pads are milled.

Ingenious tooling ideas are not limited to any single machining operation. This is clearly indicated by the procedure followed in boring cylinder liner seats illustrated in Figure III. With a special type boring head, seven individual machining cuts are made in a single pass of the tool. These include rough and finish boring the lower liner seat and forming the oil ring gasket groove. The upper liner seat is rough and finish bored, counterbored and chamfered.

An interesting comparison can be made in the floor-to-floor time required for this particular job. Only a single set-up is necessary to mount the eight cylinder block on the machine table; and this takes but one and a half to two hours. In the machining method previously followed on this job, two set-ups were required because of limited machine capacity.

Now all eight upper and lower liner seats are finish machined in approximately two hours as compared to an original time of sixteen to seventeen hours. Overall or floor-to-floor time has actually been reduced from two full working days to four hours.

The simplicity with which this work is completed emphasizes the importance of taking full advantage of a horizontal boring machine's flexibility, as well as the numerous time-saving tools and attachments available to improve work quality and production output.

In these brief examples, it has been shown that ingenious new tooling ideas for machining Diesel engine components are far from exhausted. Consider now how the open construction of horizontal boring machines offers short cuts to work handling methods.

Many engine components present unusual han-



table feed is  
nes, while col-  
the cutter on

e as outlined  
le to turn or  
machine tool,  
ration is such  
a result they  
ent assembly.

ssary to face  
ing operation  
e work set-up  
ement. The  
by raising or  
le or column  
example, all  
the angular  
When this  
head is turned  
s are milled.

imited to any  
clearly indi-  
boring cylin-  
III. With a  
dual machin-  
of the tool.  
ing the lower  
asket groove.  
finish bored,

made in the  
rticular job.  
mount the  
ble; and this  
urs. In the  
ved on this  
e of limited

er seats are  
two hours as  
en to seven-  
r time has  
working days

is completed  
full advan-  
s flexibility,  
g tools and  
quality and

shown that  
ining Diesel  
usted. Con-  
f horizontal  
rk handling

usual han-

L. PROGRESS

ding problems because of their size, shape and weight. In fact, the method of mounting such work on the machine may easily be the determining factor in establishing the total manufacturing cost of that particular part. Too often, the engine builder is limited by the working capacity of a single purpose machine tool, and as a consequence must use several such machines to complete the required operations. Obviously, changing the work from one machine to another increases handling time and sharply raises production costs.

Thus to simplify routing of work that is large, clumsy and unwieldy, many Diesel manufacturers are turning more and more to "open construction" type metal working tools. The horizontal boring machine best typifies this class of equipment.

In this machine there are no interfering columns, brackets, supports or overhead structures to hinder work set-up; the largest part designed (factory space permitting) can be extended in any plane regardless of its length, width or height. Open structure permits placing a frame, bed, block, manifold, base, crankshaft or even a complete engine on the machine. However, this should be considered only as a single step in the manufacturing process. The important point rests in the horizontal boring machine's design, which makes it possible to complete any type of set-up quickly.

This machine offers practically unlimited possibilities for conveniently mounting work for milling, boring, reaming, turning, facing and all similar machining operations. It is worthwhile now to observe how one engine builder places two blocks on a machine table to perform a series of milling operations. Dual set-ups reduce handling time and permit unusual accuracy in machining both blocks, for it is unnecessary to repeat the same cutter setting for each block.

Another progressive method of work handling is shown in Fig. IV. This large crankshaft, together

with workholding fixture, is mounted on box type parallels which are securely bolted to the machine floor plates. After the crankshaft is mounted, it is then indexed in the holding fixture. Rotating the work rapidly presents the throw surfaces to the cutter for milling. This method of handling, together with machining, makes it possible to mill all crankshaft throws in six to seven hours.

A unique set-up is illustrated in Figure V. This shows how a drilling operation is performed in a crankshaft coupling flange without removing the crank from the engine. Thus, if specifications are suddenly changed, or a hole is forgotten in critical work, it is apparent how the horizontal boring machine becomes an extremely valuable asset in the manufacturing plant.

A third essential in the profitable production of Diesel engines is having a single machine capable of performing a broad range of work on different parts. The horizontal boring, drilling and milling machine belongs in this classification.

Adaptability of the horizontal boring machine for a variety of operations has already been indicated in the example discussed. However, the full work potential of this machine is often overlooked, for it is difficult to immediately visualize all of the possible movements and combinations of movements of work and tool.

Fundamentally, there are three characteristic feed motions—longitudinal, lateral and vertical. A fourth movement, rotative, is obtained with either a vertical or a horizontal rotary table. Consequently these movements and their combination permit a broad range of machining possibilities which make it practical to duplicate with one multiple purpose machine those operations ordinarily performed on several single purpose tools. The horizontal boring machine will efficiently bore, drill, ream, tap, backbore, counterbore, face, turn, saw and form many production parts.



Specifically, milling of Diesel engine components proves considerably more advantageous than planing or shaping from the standpoint of time saved and finish produced. Also, without resetting the work, milling operations performed on this machine are readily followed by boring, drilling, tapping, facing or any similar operation or series of operations. Thus, when an engine block is placed on a rotary table, all four sides are rough and finish milled by indexing the table to position each side of the work. After this work is completed, cutters are quickly changed for drilling and tapping cover plate bolt holes, or for boring camshaft bearing holes. To assure complete accuracy in these various operations, machine scales and verniers are used to locate all dimensions and to spot all holes.

It is recognized that individual machining problems are sometimes more complex than the examples of work already described. When unusual or complicated machining work arises because of engine design or assembly requirements, there is usually a practical way to complete such work on the horizontal boring machine. In such cases, time saving accessories and attachments are often employed. These include angular milling attachments that machine hard-to-reach surfaces; continuous feed facing heads, that bore, turn, face and recess; over-arm type arbor supports, used extensively for multiple milling operations; duplicating attachments for machining contours; and, of course, the rotary tables which have already been mentioned. All add to the flexibility and productivity of the horizontal boring machine.

Only a few of the progressive machining practices of several companies have been outlined. Performance facts have been selected to indicate the broad work range of a general purpose machine tool. When the horizontal boring machine is not at work on the jobs shown, its productive time is profitably employed on run-of-the-shop machining operations in general service.

Fig. IV. Box type parallels and holding fixture reduce set-up and machining time in milling crankshaft throws. Single set-up requires 25 minutes, crankshaft throws can be milled in 7 hours.

Fig. V. An unusual work set-up made in order to drill the crankshaft flange without disassembling the engine. Open machine structure permits work extension in any plane.



# RECENT AND FUTURE DEVELOPMENTS IN DIESEL ENGINES\*

By SAUL BELILOVE\*\*

**T**HE Diesel engine is, as our British friends call it, a compression ignition engine in contrast to the spark ignition engine which uses gasoline as fuel. The compression ignition engine has had an increasing demand since the date of its discovery back in the 1890's. At first its uses were confined to stationary applications, then expanded to marine applications. Later, with development of the engine to lower weight and size per horsepower, automotive and railroad engines became more popular. At the present time Diesels are being used for marine and stationary applications up as high as 10,000 hp. The railroad Diesel unit is supplanting the steam engine locomotive almost completely, and in the automotive field, the Diesel engine is becoming increasingly popular for all types of heavy duty road equipment. Probably the best indication of present Diesel popularity is the fact that the United States is now producing about 35 million hp. of Diesels per year compared with only about 2 million hp. only ten years ago.

However, it is unfortunately true that the Diesel engine in America has continued to borrow its ideas from Europe. Almost every recent Diesel development in this country was absorbed from Europe where the basic research was done. In the Diesel field, just like many other fields, the United States has supplied the application rather than the research. Developments such as gas-oil operation, exhaust driven superchargers, opposed piston design, and many others, exceedingly important to our present Diesel industry, are examples of borrowed principles.

Recent major trends in Diesel development are (1) higher speeds for all types of applications despite the fact that the top speed limit of Diesel engines has not changed particularly in the last 10 years, (2) a huge increase in production and therefore a large decrease in relative first cost, and (3) design developments which have considerably increased the loading of engines very appreciably. Probably the greatest gain in the last decade has been made in loading increases. This applies both to 2 cycle engines where improved scavenging and greater supercharging have been the cause, and also in the 4 cycle engine where the exhaust turbocharger has been of tremendous importance in engines greater than 400 hp. in size.

\* Talk presented at meeting of the Northern California Section of the Society of Automotive Engineers.

\*\* Engine Division, Enterprise Engine & Foundry Company, San Francisco, California.

Developments in Diesel engines can be broken down into two major categories. One is design and the other is application. First I would like to discuss developments in the field of design.

One continuing conflict over the years has been the controversy between the two stroke cycle and the four stroke cycle. Abstractly, the two cycle engine appears the better, but engineers do not build Diesel engines in the air, so to speak. The four cycle engine has had many advantages which, coupled with the introduction of the exhaust gas turbocharger to four cycle engines a few years ago, has placed the four cycle engine in a superior position in an appreciable range of powers.

Another way in which engine design development proceeds is with respect to speed. Although peak operating speeds have not increased in the last 10 years—being a maximum of about 2000 rpm.—much headway has been made in increasing the reliability and decreasing the maintenance of engines running at speeds below the peak. Engines are being applied at higher revolutions per minute and greater piston speeds for the same uses than in times past. This has been a result of improvement in combustion and an improvement in materials generally.


Maintenance, of course, is basically a design problem. Thus, the same improvements which help to allow increased loading and increased speed, also help to decrease maintenance. For example, improvement in bearing materials, valve springs, connecting rod bolt materials, fuel injection parts, lubricating oils, all help decrease maintenance costs and improve engine reliability as well as allowing higher loads and speeds. We have also learned enough about engine operation to insist upon better operating conditions in order to decrease maintenance. The use of filters—air, fuel, and lubricating oil—have contributed considerably to that end. Also, the use of higher jacket water temperatures has been of considerable assistance in assisting complete combustion and minimizing cylinder wear.

Let us now take a look at efficiency. The most significant advantage of the Diesel engine lies in the fact that it is the most efficient heat engine known. In fact, the slow speed Diesel engine can actually achieve a thermal efficiency of 40%. The reason for this is simply its high expansion ratio which results from its cycle of operation, therefore allowing considerably greater efficiencies to be attained than from the relatively low expansion ratio gasoline engine.

One method that has shown some thermal efficiency increase in the past few years is that of increasing engine loading. This is simply the result of increasing the mechanical efficiency of the engine by decreasing the relatively fixed friction loss percentage of the total load. As a result, four cycle supercharged engines and two cycle supercharged engines show somewhat higher thermal efficiencies than their unsupercharged counterparts.

Another way to improve efficiency is to use new methods which have resulted from a shift in our thinking. Rather than considering the Diesel engine as strictly a machine for converting the chemical energy in the fuel to mechanical energy in the shaft, we might also consider the production of heat energy as well. By considering the entire needs of the power plant, we may learn how to provide a balanced overall arrangement which utilizes what is now considered waste as an integral by-product of the energy output. Thus, even though the thermal efficiency of the engine itself may not be any greater than 35-40%, it is still possible that the heat rejected to the jacket water and to the exhaust gases may be useful either for space heating or to operate low pressure boilers for process steam or other purposes. It is of course clear that the relatively low temperatures available from most exhaust gas and jacket water cooling systems are not particularly valuable to obtain mechanical work since we must go through another inefficient thermal conversion. But for space heating, for process steam and for other miscellaneous services, this heat has considerable value. As a result, depending upon the way we look upon the problem, we may consider that the overall utilization of the energy within the fuel can be as high as 75% in some plants.

It is interesting to note a new development which has recently arisen. This is the idea of raising the available heat in the jacket water cooling system by raising the temperature of the jacket water. Up to a few years ago any temperatures in the jacket water of a Diesel engine above 125° F. were considered "dangerous." But a few years ago temperatures up to 160° and even 180° F. became





thermally efficient. Now, the "Vapor Phase" idea is to use jacket water under pressure at temperatures as high as 230° and perhaps 250° F. One strange result is that many engines without any design change whatsoever, operate very well on these high jacket temperatures, and there seems to be no reason whatsoever why all engines, although some may perhaps require modification, cannot be operated at these high temperatures. Naturally, the availability of the heat in the jacket water system increases tremendously, and there are certain improvements in engine maintenance as well.

Recent developments have allowed us to increase the average brake mean effective pressure of the Diesel engine from approximately 80 psi. in four cycle non-supercharged engines, to approximately 120 psi. in four cycle, supercharged engines, a gain of approximately 50%. This latter figure is being utilized in countless applications today. For the two-cycle engine, continuous mean effective pressures of over 80 psi. are being utilized compared with the 60-70 psi. of the past. These figures are today's established values. There is considerable evidence to indicate that considerably higher loadings for four cycle engines can be obtained, perhaps as much as 20-25% additional, in the near future. Indeed, for one application where peak power is required only intermittently, one engine manufacturer rates his engine at 150 psi. brake mean effective pressure.

Let us now look into the method of supercharging itself. Originally supercharging of engines was obtained by independent or mechanically driven superchargers of the positive displacement type, which absorb an appreciable amount of the engine output power. However, some ten years ago there was introduced in this country a new Swiss development—the Buchi system—which utilizes the heat and velocity of the exhaust gases for driving the supercharger of four cycle engines.

Not only does this Buchi system use an exhaust turbine to drive a supercharging blower, but also overlaps the intake and exhaust valve openings so that fresh air is forced through the combustion chamber to drive out the residual hot exhaust gases. This process considerably reduces the average cylinder temperatures. The Buchi system not only allows loadings to increase by approximately

50% with little increase in cost, weight, and size, but also has decreased fuel consumption, particularly at partial loads.

The 2 cycle engine is susceptible to exhaust supercharging also, but this has not yet been done in this country, although European concerns have been successful with this development.

A further new development which is very recent includes even higher supercharging pressures than used by the Buchi system. Actually the supercharging pressures used with the Buchi system are rarely more than 6 psi. With this new system, however, there is used even higher charging pressures—up to 15 psi.—which make available a greater weight of oxygen so that a greater quantity of fuel can be burned. Two problems result: The first is a large increase in peak pressures. The second problem is that of heat dissipation and increased engine resistance that is required. For these reasons, the maximum continuous loading with this system is not appreciably above that with the Buchi system—except that higher peak loadings for a short time are obtainable.

#### Loading Limits

Well then, what is the limit to Diesel engine loading. Unfortunately, there is no single one. But I can tell you present thinking about the factors which tend to limit engine loading. One factor is smoke. Smoke tells us that the fuel we are injecting is not all being burned—which fact is, of course, unfavorable for many reasons. But with supercharging, we have so far been able to get enough air into the engine to keep away from smoke formation.

Another way of limiting engine loading is by measuring the carbon dioxide in the exhaust. Another method is to measure exhaust temperature, that is the average temperature of the exhaust gases leaving the cylinder. This criterion, too, is of some value, but is of doubtful significance in two cycle and four cycle supercharged engines.

What we are faced with is the problem of how much heat we can liberate in a given cylinder in a given time without running beyond the limitation where the pistons will operate satisfactorily. It is this temperature problem that is the present barrier. In this connection, recent developments

have been of assistance in increasing the heat resistance of the engine. One major factor is the development of heavy duty lubricating oils which keep carbon contaminants dispersed in the lubricating oil. A second major factor is the use of oil cooled pistons which help to dissipate the heat which is radiated and conducted from the combustion gases into the piston.

Other important improvements are piston rings which are now often chrome plated, chrome plating of cylinder liners, and aircraft type alloyed exhaust valves. It has been these developments that have allowed engine loadings to be continuously increased.



There have been some interesting suggestions regarding decreasing the heat load. Calculations show clearly that the intake air temperature is a major factor in the average gas temperature of the cycle. Even with the conventional Buchi system, the use of a simple cooler will decrease intake air temperature sufficiently to allow loadings to increase appreciably, perhaps as much as 20 to 30% in addition to the standard increase of the Buchi system. Thus, the total increase in loadings over a non-supercharged engine can be as much as approximately 75%. Moreover, for high pressure supercharging, the heat generated in compressing the intake air in the supercharger becomes even greater than in the Buchi system, and the use of an intercooler is even more desirable.

In general, heat engines offer thermal efficiencies which are proportional to the range of temperatures through which they operate. The higher the peak temperature, therefore, the higher the thermal efficiency. The advantage of the reciprocating engine is that the peak temperature occurs for only a small fraction of the operating cycle during that time when the piston is at its innermost position. Lower temperatures prevail during the rest of the cycle. As a result, reciprocating engines can and do obtain high efficiencies.

In contrast, we may consider the steam or gas turbine where many of the working parts are subjected to the peak operating temperatures, continuously during the cycle. As a result, peak temperatures for turbine type equipment are strictly limited although the possible exhaust temperatures are considerably lower than those that are obtainable with the reciprocating type engine.

A "marriage" between the two, therefore, seems particularly advantageous. With a system of this kind both the Diesel and the turbine can be geared to the output, working shaft, or the Diesel might be used purely as a compressor and feeder of high temperature gas to the turbine, with the turbine putting forth all of the mechanical work. It appears that arrangements of this kind, because they more greatly utilize the heat available in the exhaust gases, can offer thermal efficiencies between 40 and 50%.

... And now please turn to page 73 ...



# HAND-IN-HAND...



## SINCLAIR GASCON OIL

By reason of basic characteristics of the crude and built-in qualities GASCON OIL has unusual ability to keep engine interiors clean and also to clear away accumulated deposits.

Oils that permit hard carbon to accumulate cause stuck rings and clogged parts, necessitating engine tear down...adding to maintenance expense and forcing loss of operating time. Reports repeatedly received from users of GASCON over the years show that carbon deposits are kept down with resulting low maintenance costs. May we advise on application of GASCON OILS to your lubrication problems?

IN  
FOR  
SINCLAIR



....**CLEAN ENGINE  
LOW MAINTENANCE**



**SINCLAIR**

**INDUSTRIAL OILS**

FOR FULL INFORMATION OR LUBRICATION COUNSEL WRITE  
SINCLAIR REFINING COMPANY, 630 FIFTH AVE., NEW YORK 20, N. Y.

**OIL**

ON OIL has un  
olated deposit

x rings and  
g to main  
s repeatedly  
carbon de  
ts. May w  
problems

# DIESELS MODERNIZE 80-YEAR-OLD FERRY SERVICE

By KENNETH E. KEENE



The Anderson Ferry, "Boone No. 7," was recently modernized with a Cummins Diesel. This ferry service at Constance, Kentucky has been operated by the Kottmyer family for 83 years.

**I**N 1864, while the Civil War was in progress, a stage coach operator named Charles Kottmyer purchased the Anderson Ferry, which plied the Ohio River almost within sight of the growing city of Cincinnati. Kottmyer drove his team of horses onto the ferry and placed them on the treadmills which drove the ferry's paddle wheels.

Today, Charles Kottmyers' great-grandsons are still operating the Anderson Ferry. But today's

owners have a completely modern boat. The Anderson Ferry, as it carries passengers and automobiles across the broad Ohio at Constance, Ky., now is powered with a recently installed Cummins Diesel-electric plant. Instead of a two-horsepower operation, the ferry now derives its power from an engine capable of producing 150 hp.

In the years since Charles Kottmyer purchased the ferry from George Anderson, the family has fol-

lowed the trends of transportation. First they replaced a treadmill-operated ferry with a steam plant. Finally, in May, 1947, the present owners, Oliver and Henry Kottmyer, turned to the most modern type of power to propel their present boat, *Boone Number 7*.

A Cummins Diesel engine was installed in the boat to drive a 75 kw. Crocker-Wheeler 220 volt DC generator. The generator turning at 1200 rpm., supplies power to two 25 hp. Crocker-Wheeler motors which turn at 750 rpm. Each of the electric motors turns a side paddle wheel through a Falk 7HA herringbone reduction gear with a ratio of 7.5:1. By means of sprockets and chains the speed is reduced to 40 rpm. at the paddle wheels, giving an 18 knot speed.

The Cummins Diesel engine replaced a 50 hp non-condensing steam engine, which had come from the present ferry's wooden-hulled predecessor, *Boone Number 6*. When *Boone Number 7* was built at Covington, Ky., in July, 1937, it was the first steel-hull ferry boat on the Ohio. The paddles of this double-end, side-wheel ferry are 16 inches wide by 78 inches in length. Eleven paddles are mounted on each of the two eight-foot wheels.


The Kottmyer brothers operate *Boone Number 7* seven days a week from 6 a.m. to 9 p.m., making upwards of 50 trips per day. The Cummins Diesel uses approximately 150 gallons of fuel oil per week, operating 15 hours a day. Weighing 58 tons and carrying eight automobiles per trip, *Boone Number 7* maintains an average speed of between 18 and 20 knots.

Oliver Kottmyer points to the fact that the Cummins Diesel enables the ferry to make more trips than the steam engine which it replaced. "This Cummins Diesel-electric set-up has cut our engine operating time in half," he says. "We are averaging three and one-half minutes for each trip now because we can pick up speed so rapidly."

Installation of the Cummins Diesel also made possible a three-inch reduction in the draft of the ferry boat, the Kottmyer brothers report. From horse-operated tread-mills in 1864 to a Diesel automobile ferry, the Kottmyer family has spanned the entire range of river transportation.

Location of the Greater Cincinnati Airport only one and one-half miles from their landing gives promise of increased business for their modern Ohio River ferry.

One of a long line of Anderson Ferries, the Boone No. 4 plied the Ohio River from 1884 to 1889. Steam powered she could do 10 knots.





# FEAR- VICE

. KEENE

First they re  
with a steam  
present owners  
ed to the mos  
their present

stalled in the  
neeler 220 vol  
rning at 1200  
Crocker-Wheel  
Each of the  
wheel through  
a gear with a  
ets and chains  
at the paddle


aced a 50 hp  
ch had come  
ed predecessor  
Number 7 was  
37, it was the  
The paddle  
are 16 inches  
n paddles are  
ot wheels.

ne Number 7  
p.m., making  
mmins Diesel  
fuel oil per  
Weighing 58  
les per trip  
rage speed of

hat the Cum  
ke more trips  
laced. "This  
at our engine  
We are aver  
or each trip  
so rapidly."

I also made  
draft of the  
report. From  
Diesel auto  
has spanned  
ion.

Airport only  
anding gives  
their modern



## CHAIN REACTION

VERY OFTEN a single industrial lubrication problem in your plant, if allowed to run unchecked, can set off a whole chain of costly production hold-ups.

Rust or corrosion, for example, frequently unnoticed in its insidious early stages, may soon affect a vital piece of equipment or machine. Then, suddenly, an entire production line is thrown out of balance.

Furnishing expert counsel and advice on rust and corrosion problems is only one of the many ways Cities Service lubrication engineers can help you. These cost-conscious, production-minded experts are "professional worriers." Their recommen-

dations for exactly the right grade of oils, greases, solvents or other petroleum products to meet your individual needs are based upon a sound, intelligent "situation analysis" made on the spot and backed by experience.

Moreover, behind the recommendations of a Cities Service lubrication engineer is the solid background of a company whose roots go back almost to the beginnings of the petroleum industry.

Why not let a Cities Service lubrication engineer do your "worrying" on all your industrial lubrication problems. Phone, wire or write Cities Service, Sixty Wall Tower, New York 5, N.Y. Room 2.


CITIES





SERVICE

### CITIES SERVICE Means GREAT Service

ALL THE WAY FROM THE REFINERY TO YOUR PLANT




## NEW CATERPILLAR DIESEL



Far left, Individual fuel injection pump for D-311 Caterpillar Diesel. Cam-operated pump is controlled by gear linkage to engine governor.

Left, New Spring-loaded, pressure operated fuel injection valve with single orifice nozzle. Mechanism is calibrated at factory.

Below, Cutaway drawing of new piston—Composite construction includes aluminum alloy body with iron band for top ring groove.



**C**ATERPILLAR Tractor Company has introduced a new Diesel engine, the four-cylinder "Caterpillar" Diesel D311. Embodying the results of several years of research in design changes and improved materials, the new engine offers a marked power increase to users, without increase in size or weight over the D3400 engine which it replaces.

Engineering and manufacturing refinements in the new engine give it a maximum output of 49 hp. with radiator fan and full equipment. The D311 is a four-stroke cycle design with a bore and stroke of 4 in. x 5 in. New manifold and exhaust and inlet passages are streamlined for smooth passage of exhaust gas and inlet air.

The fuel injection valves are of new and simplified design. Gear-type transfer pump supplies fuel through replaceable absorbent filters to individual fuel injection pumps. These pumps deliver fuel under pressure to single orifice fuel injection valves. The pressure-operated spray valve mechanism is completely calibrated at the factory and is enclosed in a metal capsule which is interchangeable as a unit. The system is designed for optimum performance over a wide speed range and has good characteristics at low idle speed as well as maximum performance at full load speed.

The oil cooled pistons are of a composite construction; aluminum alloy body and head with a cast iron band for the top ring groove. The top piston ring is hard chrome plated, a design feature which greatly increases ring and liner life. Pistons are held within close weight limits. Connecting rods are machined on the outer sides of the shank for accurate, uniform weight and are carefully selected to close weight limits.

A new oil pressure control system assures a high oil pressure at the bearings when starting, even in extreme cold weather. A pressure control tube from the center main bearing to a plunger-type valve on the oil pump intake allows the oil pressure to be automatically regulated by the pressure actually within the main bearing. With this system, a high pressure, limited to 90 lbs. per sq. in. by a safety valve, is immediately available to push cold oil to the bearings. As soon as the flow to the bearing is established, the oil pump intake is automatically throttled and oil pressure is maintained thereafter at 30-35 lbs. per sq. in. This system is a marked improvement over the conventional pressure control valve which circulates the excess capacity of the pump under pressure into the sump of the oil pan.

The engine is equipped with new solid aluminum alloy main and connecting rod bearings. Being of one piece, the bearings avoid the hazards of bonding the bearing metal to a backing shell.

A new governor, accurate and quick acting, has anti-friction bearings throughout. The inertia of the moving parts is reduced by connecting the governor linkage directly to the fuel pump rack.



## LUBE MEMO

*Easy way to end sticky valve trouble*

*Sticky gum on our valves*

*Ex. valve on #1 isn't closing - loss of compression and power.*

*Nelson brags RPM DELO Oil keeps his valves clean as a whistle.*

*Nelson says compounds in RPM DELO Diesel Engine Lubricating Oil keeps valves free 3 ways:*


- 1. Anti-oxidant stops gum formation*
- 2. Metal adherent keeps oil film on stem - prevents wear.*
- 3. Detergent cleans away carbon deposits.*

*Mon. - lube change due - get RPM DELO Oil*



STANDARD OIL CALIFORNIA • San Francisco, Calif.  
THE CALIFORNIA COMPANY • Alameda, Calif.

THE CALIFORNIA OIL COMPANY • New York  
STANDARD OIL TEXAS • El Paso, Texas



Actual  
Records  
Prove

More Engine Hours  
Per Maintenance Dollar

More Engine Efficiency  
Per Operating Dollar


with

## HONAN-CRANE OIL PURIFIERS

- The advantages of Honan-Crane Oil Purifiers in diesel engine operation are simply those of continuous operation on clean oil.

By actual records, compiled by users, Honan-Crane Purifiers, without exception have increased engine hours per maintenance dollar and improved engine efficiency per operating dollar—by any standards—in any comparison.

Actual proof of the efficiency of Honan-Crane Oil Purifiers is contained in the data gathered by Polymer Corporation, Ltd., Sarnia, Ontario, Canada, operators of thirty-eight 400 and 800 horsepower engines. We will send you the Polymer Story. Just fill out and mail the coupon.



Please send me the "Polymer Story of Oil Purification Benefits."

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

COMPANY \_\_\_\_\_

CITY AND STATE \_\_\_\_\_

**HONAN-CRANE CORPORATION**

202 Indianapolis Ave., Lebanon, Indiana

Subsidiary of **HOUDAILLE-HERSHEY CORPORATION**

### Dr. Lucke Honored by A.S.M.E.

AT its sixty-eighth annual meeting, held in Atlantic City December 1-5, 1947, the American Society of Mechanical Engineers awarded to Dr. Charles E. Lucke a well-earned honorary scroll bearing the following citation:

• • •

The American Society of Mechanical Engineers Oil and Gas Power Division, Honors Charles Edward Lucke, fellow, for his pioneering part in initiating the Professional Division idea, which has been so fruitful to the Society's growth and progress, and in founding the first of these now known as the Oil and Gas Power Division, which held its initial meeting February 11, 1908.

Signed—Eugene W. O'Brien, President, American Society of Mechanical Engineers; C. E. Davies, Secretary, American Society of Mechanical Engineers; Lee Schneitter, Chairman, Oil and Gas Power Division. Dated: Dec. 1, 1947.

• • •

### Marine Industry on Parade

LATEST progress report of the Third National Marine Exposition which will be held under the sponsorship of The Propeller Club of the United States in Grand Central Palace, New York, the week of May 17-22, includes the names of many leading steamship and shipbuilding companies, manufacturers of electronic apparatus and marine equipment who will take advantage of this opportunity to demonstrate the part they are playing in the operation of the new American Merchant Marine.

In sponsoring the National Marine Exposition, The Propeller Club is rendering a valuable service to the industry in providing the medium by which manufacturers may display their products and others may demonstrate the services they are prepared to offer not only for the construction of ships but for the continued maintenance of a merchant fleet in keeping with the United States position among the world's maritime nations. The general public will be admitted to the Exposition free of charge between 2:00 P.M. and closing time each day during the week; prior to 2:00 o'clock admittance will be by invitation only.

The program for the week's activities is now being developed by the Propeller Club. Leading associations in the industry will be invited to participate, and a large space has been reserved which will be used as headquarters at the Exposition for these associations' members and guests.

Roger E. Montgomery, President and General Manager of National Marine Expositions, Inc., which is managing the Exposition has released a partial list of Exhibitors, totalling some 50, representing all phases of the marine industry.



M.E.

g, held in At  
the American  
warded to Dr  
onorary scroll

cal Engineers  
honors Charles  
eering part in  
idea, which  
s growth and  
of these now  
ivision, which  
1908.

nt, American  
C. E. Davies,  
hanical Engi-  
Oil and Gas



e  
ird National  
ld under the  
f the United  
w York, the  
mes of many  
companies,  
and marine  
f this oppor-  
are playing  
an Merchant

Exposition.  
uable service  
am by which  
roducts and  
they are pre-  
struction of  
enance of a  
nited States  
nations. The  
e Exposition  
closing time  
2:00 o'clock

s now being  
eading asso-  
d to partici-  
erved which  
position for

nd General  
tions, Inc.,  
released a  
e 50, repre-  
try.

PROGRESS



## *There's a Symbol of Great Service behind it*

When you buy a General Motors Series 71 Diesel you get more than efficient, economical power. You get more than an engine designed so well that it is smooth, powerful and easy to tend to. You get an engine that goes dependably on through years and years of useful life.

With this engine you get the integrity and background of a strong organization and all that this means in good service and ready availability of replacement parts.

Spread across the country—never far away from

GM Diesel owners—are GM Series 71 Diesel distributors, dealers and service men all ready to answer a call and see that every engine gives its best. They have the tools, the know-how and a real interest in keeping your engine dependably on the job without interruption.

Think it over. A great measure of your complete satisfaction with an engine rests with its maintenance in operation. We in the Detroit Diesel Engine Division have one service aim—to live right up to the standards set by General Motors.

### DETROIT DIESEL ENGINE DIVISION

DETROIT 28, MICH. • SINGLE ENGINES... Up to 200 H. P.  
MULTIPLE UNITS... Up to 800 H. P.

GENERAL MOTORS

**DIESEL BRAVN WITHOUT THE BULK**



## Marine Diesel Standards Committees Meet

VALUABLE counsel and guidance was recently given to the editorial committee of engineers which is writing the book, "Marine Diesel Standard Practices." Those who gave the editors their constructive criticisms of the material thus far compiled, were seven members of the Society of Naval Architects and Marine Engineers. They were Charles MacPherson, senior engineer surveyor, Lloyds Register of Shipping; A. S. Thaeler, assistant chief engineer, Federal Shipbuilding & Dry Dock Co.; Jorgen S. Nielsen, Diesel engineer, Shipbuilding Division, Bethlehem Steel Co.; Hugo Haas, Diesel engine section, U. S. Navy, Bureau of Ships; Dwight Simpson, naval architect, John G. Alden; A. R. Gatewood, chief engineering sur-

veyor, American Bureau of Shipping, and Eads Johnson, naval architect.



Left to right, rear row: C. MacPherson, J. G. Earle, E. L. Dahlund, H. T. Hill, J. L. Ostberg, A. S. Thaeler, F. K. Baldwin. Left to right, front row: J. S. Nielsen, D. Simpson, E. Frederick, Chairman, W. B. Moore, and H. Haas.

The editors are drawn from the membership of the Diesel Engine Manufacturers Association. They are Edmund Frederick, Chairman, assistant

chief engineer, Cooper-Bessemer Corp.; John G. Earle, special representative, Nordberg Mfg. Co.; Ervin L. Dahlund, assistant director of engineering, Fairbanks, Morse & Co.; John L. Ostberg, chief designing engineer, National Supply Co.; Paul Shirley, consulting engineer, Hooven, Owens, Rentschler Div., Lima-Hamilton Corp.; Wesley B. Moore, Manager, marine engine division, Worthington Pump & Machinery Corp., and Roy A. Hundley, chief engineer, Enterprise Engine & Foundry Co.

At the New York meeting, held in the Waldorf Astoria Hotel, it was announced that the book would be off the press next March. The price is to be \$5.00.

## Bellows Appoints A. S. Terry Sales Manager

A. S. TERRY of Grand Haven, Michigan, has been appointed sales manager of The Bellows Company, Akron, Ohio, manufacturers of Bellows Air Motors and "Controlled-Air" Devices. The appointment was made by L. F. R. Bellows, President.



A. S. Terry

Mr. Terry was formerly head of the Detroit district office for Bellows.

## New Catalog on Herringbone-Gear Reducers

MANY new sizes and types of enclosed herringbone gear units for speed reducing and speed increasing service, are detailed and described in a new Book No. 1819 of 68 pages, recently completed by Link-Belt Company and now available for distribution.

A copy of new Book No. 1819 will be forwarded promptly on receipt of request, which may be addressed to Link-Belt Company, 2045 W. Hunting Park Ave., Philadelphia 40, or other office of the company.

*Where ECONOMY Counts...*

**BUCKEYE  
DIESELS  
PAY!**

150-1440 H.P.  
100-1000 KW

## BUCKEYE POWER = EXTRA PROFITS

Today's narrowed profit margins make low cost power more important than ever before as a logical source of extra profits. Ever since 1908 — in thousands of stationary and marine installations — owners and operators have learned that the name "Buckeye" on an engine means **ECONOMICAL POWER**.

Buckeye owners will tell you that their savings in power cost represent a worthwhile profit that was formerly labeled "Operating Expense."

## BUCKEYE ECONOMY and DEPENDABILITY

Every feature of Buckeye design and construction has been developed to bring the highest standards of dependability and economy to users of Diesel power. For example, Buckeye valve areas are larger because there are no valve cages. This increases combustion efficiency by providing faster air flow and quicker expulsion of gases. Crankshaft and connecting rod bearings are reversible, shell-type, silver alloy — made by an exclusive Buckeye process — and will last, with proper care, for the life of the engine. These and many other features are responsible for the low cost, dependable operation of Buckeye Diesels.

Buckeye engines are appreciated most where the going is tough . . . the service twenty-four hours a day . . . and a low cost source of dependable power is required.

Our engineering staff is always at your service. No obligation—no cost. Just write.



**THE BUCKEYE MACHINE CO.**  
LIMA . . . . . OHIO



Corp.; John G.  
berg Mfg. Co.;  
or of engineer-  
thn L. Ostborg  
al Supply Co.;  
Hooven, Owens,  
Corp.; Wesley B.  
Division, Worth-  
e., and Roy A.  
prise Engine &

## Recent and Future Developments In Diesel Engines

Continued from page 63

The first and basic reason for Diesel popularity is the extremely high efficiency and simplicity of the Diesel engine compared with other types of prime movers.

A second reason has been the improvement in the Diesel engine itself. Due to improvements in mechanical design and lubricating oil, high speeds resulting in lighter and cheaper engines became available.

Let us now look more carefully at the relative efficiencies of the Diesel and other types of prime movers. (See Figure 4). It is to be noted that compared to all, the Diesel is far and away the most efficient.

### Fuel Costs and Supplies

It is important to note, however, that superior efficiency is not the sole determinant of fuel costs in operation. Another factor is certainly the cost of the fuel per unit. Thus, in some instances, coal is sufficiently economical so that almost irrespective of superior Diesel efficiency, the use of coal in the steam boiler gives lower fuel cost than a Diesel burning relatively high priced oil. The same effect holds true elsewhere, and it was and still is the lower cost per gallon of Diesel oil compared to gasoline that is an important factor in the use of many Diesel engines rather than gasoline engines. Because of the importance of fuel costs, many influential forces in this country have urged very strongly that lower grade, lower cost fuel oils be given greater emphasis for the Diesel engine.

The petroleum situation is of great significance to the Diesel engine, and Diesel oil costs have increased considerably in the last year. For petroleum technology has reached the stage where oil is not simply gasoline or Diesel oil or residual oil. We now can convert these oils as we see fit to suit market demand. Thus, whereas in the past Diesel oils had been considered the by-product of gasolines, it is now beginning to be considered a partner so far as end use is concerned, and its cost has been increased in accordance with its importance.

Recently, for security reasons, our government has been sufficiently concerned about the scarcity of petroleum to experiment with two new processes for obtaining new sources of oil. One of these is the process of obtaining oil from shale; in the state of Utah a pilot plant has successfully obtained petroleum oil from shale deposits which are enormous in extent. Although this probably means that costs will be slightly increased, it should not be very great and we are in any event assured of a continued oil supply.


A significant indication of how the Diesel industry has kept its eyes open is an outstanding new

development—the combination gas-oil engine. With this engine we can burn natural gas on the Diesel cycle attaining the full efficiency of this cycle while using only a small amount of oil, 10% or less, for pilot ignition.

This development has become extremely popular within the last year throughout the Middle West where natural gas from Midcontinent oil fields is available, and in engines used in the oil fields themselves.

With the use of natural gas, the savings are actually enormous compared to fuel oil, and, in fact, can halve the fuel cost during the course of a year, when the fuel cost is perhaps 75% of direct operating cost.

## Detroit Diesel Develops Mobile Service Units



G-M Service truck is equipped with necessary tools and parts for field repair work on Series 71 Diesel engines.

# HERE'S MORE POWER To You!

● Do your batteries need recharging often?

Do you have to limit the use of accessories, especially at slow speeds, to safeguard batteries?

Do you hesitate to add accessories for fear of overtaxing batteries?

Answer yes to any one of these questions and our suggestion to you is just this: Install the new kind of generating system—install the higher-output A-c. system perfected exclusively by Leece-Neville. Do this and you can answer no to all three questions. Do this and you can save real money on battery maintenance and longer battery life.

You can specify this more powerful generating system for new trucks, busses and other vehicles—or you can install it easily on your present equipment. Right now, let us send you more complete information.

The Leece-Neville Company,  
Cleveland 14, Ohio



ALTERNATOR  
WEIGHT ..... 31 Pounds  
RATING .. 14 Volts—100 Amperes



3-ELEMENT  
VOLTAGE REGULATOR  
WEIGHT ..... 4½ Pounds  
RATING .. 14 Volts—100 Amperes



RECTIFIER  
WEIGHT ..... 7 Pounds  
RATING .. 14 Volts—100 Amperes

[Similar 3-unit system for 6-volt service weighs 41 pounds, rating 60 amperes—420 watts. For 12-volt service, another system, utilizing same Alternator as shown above, is rated at 60 amperes. COMING—12-volt system rated at 150 amperes.]



# LEECE-NEVILLE


Pioneer and STILL Quality Leader

CRANKING MOTORS • GENERATORS • VOLTAGE REGULATORS • SWITCHES



# THOMAS

Flexible ALL METAL COUPLINGS


Engineered to stand up on the toughest jobs, Thomas Flexible Couplings do not depend on springs, gears, rubber or grids to drive. All power is transmitted by direct pull.



The standard line of Thomas Couplings meets practically all requirements. But if unusual conditions exist we are equipped to engineer and build special couplings.



**BACKLASH  
FRICTION  
WEAR and  
CROSS-PULL**  
are eliminated  
**NO LUBRICATION  
REQUIRED!**



**THE THOMAS PRINCIPLE  
GUARANTEES PERFECT  
BALANCE UNDER ALL CON-  
DITIONS OF MISALIGNMENT**

Write for New Engineering Catalog

**THOMAS FLEXIBLE  
COUPLING CO.  
WARREN, PENNSYLVANIA**

## Electro-Motive Organization Changes

**N. C. DEZENDORF**, Director of Sales and Service, Electro-Motive Division of General Motors, recently announced the following organization changes.



**R. L. Terrell**

**R. L. Terrell**, formerly District Sales Manager at Washington, D. C., is appointed General Parts Manager with headquarters at La Grange, Ill.



**W. D. Davis**

**W. D. Davis**, formerly Parts Manager, is appointed to head a newly created Service Repair Department including five Branch Repair Shops, with headquarters at La Grange.

## Christensen Heads Burmeister and Wain Subsidiary Corporation in U.S.

**POUL A. CHRISTENSEN** was recently named as President of the newly formed Burmeister & Wain American Corporation. The new corporation is a subsidiary of Burmeister & Wain, Ltd., of Copenhagen, Denmark. Christensen was formerly consultant for Burmeister and Wain. The address of the new corporation will be the same as that used by Mr. Christensen formerly—35 West 53rd St., New York 19, New York.

## Moore Named by Crocker-Wheeler



**P. J. Moore**

**CROCKER-WHEELER** Electric Manufacturing Company of Ampere, N. J., a division of Joshua Hendy Corporation, has announced the appointment of **Paul J. Moore** to the newly created position of Director of Sales and Engineering.

## Air-Maze Names Paullin



**E. M. Paullin**

**THE** Air-Maze Corporation recently announced the appointment of **Edward M. Paullin** as factory representative in charge of its Buffalo office, 28 Church Street. He will handle the firm's accounts in the State of New York with the exception of New York City, Long Island and Westchester County.

## Auto-Lite Expands Diesel Equipment Facilities

**DIESEL** equipment for both trucks and special industrial units is being supplied in quantity by **The Electric Auto-Lite Company**, large independent manufacturer of automotive electrical equipment. In addition Auto-Lite also is manufacturing special Diesel equipment for locomotives and marine engines.

## Keel Tow

**THE** keel tow Lines in Avondale River from A. C. In It is dr Motors I tion gea installed Contra-G equipmen designed Michigan be operat five barge integral river equ Avondale some tim

## Bailey New D

**IN** line v Technical announced Director Morris is The Baile Grand Bl

## Descrip

**A** 4-PAG at three and for h cently bee types of n ard variet to bluepri

Available Jos. Dyson land 14, C



### Keel Laid for "Harry Truman" Towboat

THE keel of the towboat for the Federal Barge Lines integrated tow *Harry Truman* was laid at Avondale Marine Ways, Inc., on the New Orleans River front recently. It was designed by Captain A. C. Ingersall, president of Federal Barge Lines. It is driven by two 1600 horsepower General Motors Diesel engines connected through a reduction gear to twin propellers. The equipment installed is of the latest design. Goldschmidt Contra-Guide Rudders were installed on River equipment for the first time. The propellers were designed by Professor Baier of the University of Michigan. The new integrated tow, designed to be operated as a unit, consists of two bow pieces, five barges, and the tow boat. Total length of the integral unit is 1200 feet. It is the latest word in river equipment. James H. Bull, president of Avondale stated that the towboat will be delivered some time in April, 1948.

### Bailey Schools Has New Director



Lee C. Morris

IN line with expanding operations at The Bailey Technical Schools C. W. Bailey, President, recently announced the appointment of Lee C. Morris as Director of Education for the several schools. Morris is already serving in his new capacity at The Bailey Schools which are located at 1651 S. Grand Blvd., St. Louis.

### Descriptive Dyson Folder

A 4-PAGE folder on Large Forged Nuts, starting at three inches and used for large construction and for heavy machinery and equipment, has recently been published. This bulletin describes the types of nuts fabricated, which include the standard varieties as well as the unusual types of nuts to blueprint, heat treated and machined as desired.

Available upon request from the manufacturer, Jos. Dyson & Sons, Inc., 5125 St. Clair Ave., Cleveland 14, Ohio.

### New Ninth Edition of "Results Of Publicly-Owned Electric Systems"


THIS volume of about 400 pages gives a record of the new rates, earnings, production, consumers, operating expenses, free services, taxes paid and other operation statistics of over 600 cities of population 2500 and upward. The record shows Diesel, Steam and Hydro plants.

A free copy goes to every city owning its electric utility and where that city has furnished its rates and operating data. To all others the charge is \$10.00 per copy prepaid. Orders now are being

received by the Publishers, Burns & McDonnell Engineering Company, 95th and Troost, Box 7088, Kansas City, Missouri.

**Order Your Copy of the 1947 DIESEL ENGINE CATALOG now. Thoroughly revised — more complete — indispensable. Convenient order coupon on Page 77 this issue. Mail it today.**


An accident completely wrecked the front section of a 6-LR0 Waukesha engine. A good section was cut from a scrapped engine and the two sections METALOCKED together. This view shows the new section ready for mounting.



ARE YOU USING

**METALOCK**

Both sections were bolted to the base and the crank and cam shafts checked for proper alignment. The sections were secured at all contact points with METALOCKS and METALACE. MASTERLOCKS were inlaid in the frame flanges to add to the strength of the repair.



WRITE TO METALOCK FOR FREE CATALOG

**METALOCK CASTING REPAIR SERVICE, INC.**

LICENSED AGENTS IN PRINCIPAL CITIES

36-15 48th AVE.  
TELEPHONE STillwell 6-0330

LONG ISLAND CITY 1, NEW YORK  
Cable Address: "METLOKCAST NEW YORK"

# THE ENTIRE DIESEL INDUSTRY

# 12<sup>th</sup>

## EDITION OF THE

# DIESEL ENGINE CATALOG

# \$10

Whatever you are looking for in Diesel Engines, accessories, you will find them described and illustrated in the 1947 DIESEL ENGINE CATALOG, Volume 12, edited by Rex W. Wadman. What's more, you will find complete specifications on

## 822 DIFFERENT MODELS

The Products of 53 Engine Manufacturers. Each engine description is complete and accurate — checked and double-checked by the Manufacturer himself. Illustrations include full-page engine views, lube and fuel system diagrams, also cooling systems, many traced in color.

But that is just the Diesel engine section. The Catalog also includes an accessories section carrying valuable information on the various Fuel Injection Systems, Gear Drives, Chain Drives, Turbo-chargers, Blowers, Magnetic Couplings, all fully described and profusely illustrated.

## 53 DIESEL ENGINE MANUFACTURERS BUILDING

## 822 MODELS

American Locomotive Company  
Anderson Diesel Engine Company  
Atlas Imperial Diesel Engine Company

Baldwin Locomotive Works  
Buckeye Machine Company  
The Buda Company  
Burmeister & Wain

Caterpillar Tractor Company  
Chicago Pneumatic Tool Company  
Clark Brothers Company  
Consolidated Diesel Electric Corporation  
Climax Engineering Company  
Continental Motors Corporation  
Cooper-Bessemer Corporation  
Cummins Engine Company

Enterprise Engine & Foundry Company  
Fairbanks, Morse & Co.  
Fulton Iron Works Company

General Machinery Corp. (Hooven, Owens, Rentschler Division)

General Motors Corporation  
Cleveland Diesel Engine Division  
Detroit Diesel Engine Division  
Electro Motive Division

Gray Marine Motor Company

Hallett Manufacturing Company  
Joshua Hendy Iron Works  
Hercules Motor Corporation  
Hill Diesel Engine Company (Division of Rogers Diesel & Aircraft Corp.)

Ingersoll Rand Company  
International Harvester Company  
Kahlenberg Brothers Company  
Kermath Manufacturing Company

Lathrop Engine Company  
Lincoln Diesels (Bolinders Company)  
Lister-Blackstone Inc.  
Lorimer Diesel Engine Company

Mack Mfg. Corporation  
Murphy Diesel Company

National Supply Company (Superior Division)

Nordberg Manufacturing Company

Palmer Bros. Company  
Rathbun-Jones Engineering Company

John Reiner Company

R. H. Sheppard Company

Sterling Engine Company  
Sun Shipbuilding & Drydock Company

Union Diesel Engine Co.  
United States Motor Corporation

Vann-Severin Machine Company

Washington Iron Works  
Waukesha Motor Company  
Witte Engine Works

Wolverine Motor Company  
Worthington Pump & Machinery Corporation

# ORDER YOUR COPY NOW



# NDRY UNDER ONE COVER!

engines, o  
and illust  
S, Volum  
e, you wi  
OR DESIGN AND OPERATING ENGINEERS AND BUYERS

## NOW

## AVAILABLE

There is a Market Place Section—a directory of Diesel engines classified as to ratings speeds with manufacturers' names and addresses — and a Product Directory listing accessories, parts, materials and services — all classified as to products. Market Place tells you at a glance where to find what you want for your engine plant.

otion is comp  
r himself. Illu  
also cooling sy  
OTHER DIESEL BOOK LIKE IT  
er 500 Pages - Really 4 Books In One

The main section is devoted to descriptions, illustrations and specifications of all the Diesel engines manufactured in this Country.

A large section carries complete illustrated descriptions of Diesel engine and plant accessories.


The Market Place — a classified directory of Diesel Engines and Accessories.

Manufacturers' Advertisements—131 pages of Catalog-type copy—informative—helpful.

# NECATALOG

## BUILDINGREVISED ANNUALLY

The most widely-used Diesel reference book published:—Because the book is revised and brought up to the minute each year, thousands of design and operating engineers, purchasing and sales executives, Diesel students buy the DIESEL ENGINE CATALOG each year and constantly refer to it throughout the year. The 1947 Edition, Volume Twelve, embodies sweeping changes — new models and types, revised designs—and carries the basic information published in previous editions. Whatever your interest in Diesels is you will find this Edition of the DIESEL ENGINE CATALOG INDISPENSABLE.



DIESEL ENGINE CATALOG—  
Two West Forty-Fifth Street—New York 19, N. Y.

Enter my order today for a copy of the New 1947 Diesel Engine Catalog, Volume Twelve, Edited by Rex W. Wadman, for which I enclose \$10.00.


NAME .....

ADDRESS ..... CITY ..... Zone ..... STATE .....


PLEASE PRINT NAME AND ADDRESS

# P NOW ...

# GENERATORS *AC and DC*



Well-known for their rugged design, efficient performance, long life and minimum maintenance, whether powered by electric, gasoline, or Diesel equipment. Backed by over 1/2 century of manufacturing and designing experience, Kurz and Root generators are now serving industries throughout the world



DC generator (left) two-bearing, self-excited type. Can also be furnished with direct connected exciter. Both AC and DC generators can be furnished in the single bearing, flange-mounted type for special mounting requirements. Ball bearing construction is used throughout. Complete data upon request.



Illustrated are AC generators, only 2 of the many different types developed and designed to fit specific needs and applications, (upper left) two-bearing self-excited type; (lower right) two-bearing direct connected exciter type.



**KURZ and ROOT Company**  
APPLETON - WISCONSIN  
Since 1898  
.....and 30 motor and motor generator sets

## Ship Repairing

Diesel Overhauling, Repairing, and Redelivering. Foreign and Domestic Pistons, Liners, Cylinders, Covers, Valves, etc.

PIONEERS IN DIESEL REPAIR WORK SINCE 1919

**H. W. RAMBERG, INC.**

37 VAN DYKE ST.

BROOKLYN, N. Y.

SHOP PHONE: MAIN 5-3960

## LET US SOLVE YOUR DIESEL PROBLEMS

**Diesel Specialties, Inc.**

2 VAN DYKE ST., BROOKLYN, N. Y.

Fabricators and Reconditioners of Both Domestic and Foreign makes.

Telescopic Pipes, Governors, Pistons and Lubricators.

Fuel Valves, Pumps, Valve Plungers, and Housings.

H.P., M.P., and L.P. Compressor Valves, Cylinders, Pistons.

Cams and Rollers, Oil Filters, Gears, Injectors, Atomizers and Nozzles.

Slide, Exhaust, Inlet Starting Valves, Inlet and Exhaust Spindles

PHONE MAIN 5-3960

### New Korfund Rubber-Spring Mounting



Patent applied for

Phantom view of Korfund vibration control unit

A NEW low-cost vibration control unit, the Korfund Type RS Conical Rubber-Spring Mounting has been announced recently by The Korfund Co., Inc.

The new Korfund Type RS has been designed primarily for use on compressor units, generator sets, motor generators, pumps, motors, fans and other machinery requiring a highly efficient, economical, standardized vibration isolator. Please write for further details and Korfund RS Bulletin from The Korfund Co., Inc., 48-28 Thirty Second Place, Long Island City 1, N. Y.

### Diesel-Electric Crane

KEEPING pace with the railroads, which are now being revolutionized by Diesel-electric power, the American Hoist and Derrick Company has perfected a new Dieselectric locomotive crane.



Cost and performance studies of this crane, covering extensive operation in many industries, indicate it will earn back its original cost much faster than other type cranes, through greater work output and lower maintenance expense. Capacity 40 tons. A new catalog, now ready for mailing, gives full details and specifications. Write American Hoist and Derrick Company, St. Paul, Minnesota, for full particulars.




## Friendship Train Spans Continent with Diesels



Union Pacific supplied a 6000 hp. Fairbanks-Morse Diesel locomotive for Friendship Train.

CONTRIBUTING their small share to the gigantic effort made by the American people for the relief of suffering abroad. Diesel locomotives hauled this cargo of foodstuffs across the continent to the eastern seaboard where it was transferred for shipment abroad.

### Pressure Operated Switch



Meletron Model 310 pressure operated switch

MODEL 310 is one of Meletron's wide line of switches actuated by the pressure of liquids, air or gases. Its Diesel application is that of actuating warning devices or stopping operating equipment when operating pressures become too high.

Write the Meletron Corporation, 950 Highland Ave., Los Angeles 38, California, for further information.

### Nordberg Appoints Sales Executives


ANNOUNCEMENT is made of the new sales executives in the Heavy Machinery Division of the Nordberg Mfg. Company. In the Heavy Engine Section of that division, L. L. Peterson has been appointed Sales Manager, while H. G. Van Schaack has been given the same position in the Gasoline Marine Engine Section.



Front



Cover removed showing adjustment



Back

## DIESEL COOLING SYSTEM ALARMS

Sarco electric cooling system alarms are rugged, vibration-proof, corrosion proof and thoroughly dependable. The thermostatic system is contained in an immersion stem of brass.

Adjustment is made by removing the cover and turning the adjusting knob with a screw driver over the fully calibrated scale (see above).

Range, 90 to 210 degrees F., accurately calibrated each ten degrees. Fixed differential of plus-minus one degree can be increased to 8 degrees at no extra cost.

Other Sarco products include inexpensive controls for jacket cooling water and strainers for water, fuel and lubricating oil. Ask for the bulletins.

# SARCO

SAVES STEAM

SARCO COMPANY, INC.

Represented in Principal Cities


Empire State Building, New York 1, N. Y.

SARCO CANADA, LTD., TORONTO-S. ONTARIO

## THE... HELIXHAUST

### WATER-COOLED MANIFOLD

The HELIXHAUST reduces temperature of exhaust gasses—makes engine room more livable. It increases permissible supercharged rating of Diesel engines. It's simple, yet highly efficient, neater and more attractive when mounted on the engine. It modernizes 4-cycle Diesels by turbo-charging. Write for literature containing complete specifications on the HELIXHAUST and details on Intake Manifolds, Water Inlet Headers and Water Discharge Pipes. Stewart engineers will be glad to talk over with you further the advantages of the HELIXHAUST Water-Cooled Manifold.



**Stewart**  
FABRICATORS OF  
IRON · STEEL · WIRE

THE STEWART IRON WORKS CO., Inc.  
1581 Stewart Block  
CINCINNATI 1... OHIO



with these

## ADECO SERVICE AIDS



### NEW ADECO NOZZLE SERVICE KIT FOR CLEANING INJECTORS

This handy kit includes all tools needed to clean out clogged nozzles and avoid possible damage to costly injectors. Complete with lapping compounds, in handy metal carrying case, only \$7.50 f. o. b. Chicago.

### ADECO NOZZLE TESTER



Compact, portable, sturdy, precision-built. Enables any mechanic to make quick, accurate tests on injector opening pressure, spray pattern, etc., and detect stuck needle valves and leakage around valve seats. Pressures up to 10,000 p.s.i. Tests large or small injectors. Complete with standard gauge, \$58, f.o.b. Chicago; slightly higher, equipped with Navy-approved gauge.



Manufacturers of dependable Fuel Injection Pumps, Nozzles and Nozzle Holders for the Diesel Industry.

### NEW EQUIPMENT

TWO NEW heavy-duty hydraulic jacks, 30 ton and 50 ton models, have been announced by the Blackhawk Mfg. Co.

A NEW ELECTRIC hand tachometer by Metron Instrument Company features 1% accuracy over a 200 to 10,000 rpm. range. A slow speed model has ranges from 20 to 1000 rpm.

A PRECISION BORER is now being used by Diesel repair shops throughout the country for rocker arm boring operations. This Hydro-Borer is one of a series of precision boring tools designed to handle Diesel parts. Accuracy is to .001 in  $\pm$  0.

TWO NEW DRIVES announced recently by Twin Disc Clutch Company include a multiple engine hydraulic drive and a hydraulically actuated reverse and reduction gear. The first is suitable for Diesel engines developing 150 hp. at 600 rpm. to 325 hp. at 1500 rpm. The reverse gear can be utilized with engines developing up to 160 hp. at 1200-1800 rpm.

UP FROM FLORIDA comes the latest wrinkle in tractor attachments in the form of a root rake designed to clear land to a depth of 16 inches. It will be marketed by the Caterpillar Tractor Co.

A-C GENERATING systems for motor buses, a new development by Leece-Neville, have been adopted as standard equipment by two leading bus manufacturers. High output A-C current is dry-disc rectified.

HIGH TEMPERATURE, high pressure tubing by Titeflex incorporating Inconel is designed to withstand corrosive action of Diesel exhaust as well as the effects of continued vibration.

A NEW EXPANDER SPRING developed by the Sealed Power Corporation for use with oil rings is said to offer greater oil economy because of its open construction and flexibility.

A NEW LINE of expansion joints by Zallea Brothers & Johnson, capable of absorbing movement of high temperature lines in any direction is now under production. Joints are particularly adapted to Diesel exhaust and intake lines in stationary or shipboard installation.


U. S. GAUGE has developed a new absolute pressure gauge, dial reading in inches or millimeters of mercury. It is furnished in a black plastic case.

TO SIMPLIFY the repair of Diesels, Cummins Engine Company have introduced a line of 31 service parts kits, covering a great variety of engine replacement parts. A catalog describing these kits is available from the company.


THE TENDENCY towards full-flow filtration of Diesel lubricating oil is increased by the announce-

As advertised in TIME and NEWSWEEK

## How Air-Maze filters



### kept "dirty" oil clean



### for 3700 bus miles

To show you what true full-flow filtration really accomplishes, our engineers took this photomicrograph of Air-Maze filtered oil, removed from a city transit bus after 3700 miles of strenuous start-stop operation. It's enlarged 400 diameters (each graduation equals .00025"), and reveals that the Air-Maze Type "O" filter left no particles larger than 5 microns (.0002" diameter).

FROM A COLOR STANDPOINT, the oil is dirty. But it isn't the color of oil that protects moving parts from abrasive particles. The important fact about this oil is that it is free of all harmful grit.

PROTECTION LIKE THIS is possible only because Air-Maze oil filters clean all of the oil all of the time. (Conventional filters usually handle but 10% to 15%.)

AIR-MAZE TYPE "O" oil filters are now protecting America's finest engines, hydraulic equipment, fuel systems—and are used in many other liquid filtration applications. If you design or build equipment using noncorrosive liquids, it will pay you to investigate the Air-Maze oil filter today. Send for new bulletin. Air-Maze Corporation, Cleveland 5, Ohio.

Note: Because most existing car and truck lubrication systems are not designed for full-flow filters, Air-Maze Type "O" are not recommended for replacement purposes.





low filtration  
ers took this  
filtered oil,  
after 3700  
eration. It's  
graduation  
at the Air-  
ticles larger  
>.

oil is dirty.  
at protects  
articles. The  
at it is free

only because  
ne oil all of  
ally handle

ow protect-  
ulic equip-  
ed in many  
ns. If you  
noncorro-  
estigate the  
ew bulletin.  
l 5, Ohio.

& Lubrication  
rs, Air-Max  
ent purposes.

ment of Wm. W. Nugent & Co. that they have developed such a system for Diesel engines. A wastetype filter in series with an absorbent cellulose type (for fine filtration) insures the complete filtration of all crankcase oil on each circuit through the pump.

FALK CORPORATION describes its line of "Steel-flex" couplings in a new bulletin. The grid-groove design of the coupling permits a large amount of torsional resistance as well as flexibility.

A NEW FUEL ADDITIVE has been announced recently by the Industrial Chemical Corporation of Los Angeles. It is said to increase engine efficiency as well as save fuel.

A NEW PRESSURE GAUGE utilizing nylon fibre will be introduced soon by Manning, Maxwell and Moore, Inc. The nylon movement of this new Ashcroft Dura-gauge is said to outlast other movements.


A PORTABLE HYDRAULIC unit capable of delivering 3 gpm. at 1000 psi. was recently announced by Hydro-Power, Inc.

A GEAR PULLER set manufactured by the Plomb Tool Company provides equipment needed for majority of pulling jobs. 42 piece set suitable for repair shops and industrial plants.

GENERAL ELECTRIC COMPANY announces a new metal alloy which has a density 50% greater than lead. Hevimet as the new alloy is called is adaptable for weighing and counterweighing rotating parts such as crankshafts, centrifugal clutches and other machinery.

#### R. H. SHEPPARD

Company has developed a Diesel pumping unit suited for handling light petroleum products. Unit comprises a 3½ hp. Sheppard Diesel, single cylinder air-cooled and a 220 gpm., self-priming centrifugal pump. It is stated that



unit will pump 36,500 gallons of water with a fuel expenditure of only one gallon.


INTERNATIONAL Harvester has announced the development of a new engine which is convertible in production as either a gasoline or Diesel engine. The announcement was made by H. T. Reishus, general manager of the company's Industrial Power Division. This new engine will meet the demand for a smaller, lower-priced Diesel.

The major feature of this new engine from a production standpoint, Mr. Reishus pointed out, is that it will enable the company to produce both gasoline and Diesel tractor and industrial engines on the same assembly line.

## Have you ever seen the INSIDE of an EXPLOSION?


OR THE RATE OF  
ENGINE FLAME  
PROPAGATION

Seeing now made possible  
by remarkable new elec-  
tronic features, embodied in



### PRESSUREGRAPH with Syncro-Marker

Reproduces on oscillograph screen, accurate picture of pressures during and after explosion, relates pressure variation to time, top dead center, angular velocity, etc. Also accurate tracing of rate of flame propagation with relation to top dead center and peak pressure. See pressure-time characteristics of automotive, jet and Diesel engines, also compressors, pump, etc. Operates over range from static up to 10,000 cycles at pressures from 0 to 10,000 lbs.




Send for description and full  
engineering data

### ELECTRO PRODUCTS LABORATORIES

549 W. Randolph St., Chicago 6, Ill.

Phone STate 7444



### FOR Dependable DIESEL STARTING

Quincy Compressors for Diesel starting air supply are available in a wide variety of models. Model D320S shown above has proved highly satisfactory as a starting unit. Compressor can be operated by either electric motor or gasoline engine. This provides standby protection against current failure — eliminates extra investment in second compressor. Quincy Compressors are

available in sizes 1 to 80 cu. ft. displacement, up to 500 pounds discharge pressure. Specify Quincy Compressors for dependable Diesel starting.



## ENTIRELY NEW

### Ignition and Combustion System for Compression Ignition Engines

#### Embodies and coordinates:

- ★ Controlled better Mixing
- ★ Controlled faster Ignition
- ★ Controlled better Combustion

#### Designed to:

- Increase Power Output
- Increase Acceleration
- Reduce Fuel Consumption
- Reduce Bearing Loads
- Reduce Engine Weight
- Eliminate Smoky Exhaust

### Applicable to Both 2 and 4 Cycle Engines

Does not use a pre-combustion chamber. Uses proven principles of the modern compression ignition engine in a new way.

For development and manufacturing rights for the U.S.A., write Box 481 DIESEL PROGRESS, 2 W. 45th St., New York 19, N. Y.

## Names in the News



H. L. KNUDSEN retired recently as Vice-President in Charge of Engineering of Cummins Engine Co., after 25 years as a member of the company's Engineering Department. He continues as a Director of the company.



WILLIAM B. PROSSER was recently appointed General Manager of the Perfect Circle Corporation. Prosser joined Perfect Circle as plant manager in 1928. Since 1943 until his recent promotion he served as general factory manager.

D. O. THOMAS, President of Bendix-Westinghouse Automotive Air Brake Company, recently appointed Stephen Johnson, Jr. as Chief Engineer of the company. He will serve directly under E. R. Fitch, Director of Engineering.



DOUBLE SEAL RING has named R. W. Hoyt as Chief Engineer. Hoyt, formerly with Bendix Corporation, joined Double Seal Ring in 1946. He is a graduate of the Mechanical Engineering

School of Purdue University.

J. H. GILL recently took over the job of Engine Sales Consultant for Caterpillar. He joined Caterpillar in 1937 after four years with Wm. C. Holt Machinery Co.

LINK BELT CUSTOMERS of Michigan will be glad to note that Peter Groustra will manage the New Link Belt Company office in Grand Rapids.

MACK TRUCK has announced the appointment of H. J. Fikejs as Manager of the Mack Truck Company's Milwaukee Factory Branch.

SCINTILLA MAGNETO DIVISION of Bendix Aviation Corporation recently named George M. Anger as western states representative. Plans are under way to establish an office in San Francisco where he will maintain headquarters.

J. A. CORTRIGHT, general sales manager of the Clayton Manufacturing Company of El Monte, California, recently announced the appointment of A. G. Orsborn as his assistant in charge of

Sales Promotion. Clayton specializes in Vehicle Analyzers and cleaning compounds.

L. H. BENSON has joined the Tuthill Pump Company as vice-president in charge of manufacturing. Benson, a mass production specialist, will aid considerably in the expansion plans of the company.

WEATHERHEAD COMPANY announces that T. G. Carey has been advanced to the position of purchasing agent of production parts and subcontracting.

LLOYD A. HARRIS, of National Supply Company, has been transferred from the Superior Engine Division to the Plant's Products Division. Harris has assumed his new duties in Houston, Texas which will include sales and service of Superior engines in the oil industry.

D. C. GRAHAM has been appointed by Nordberg Mfg. Company as sales engineer for the eastern territory. His headquarters will be in New York.



ATLAS IMPERIAL Engine Company has named John Seagren as chief engineer. Seagren recently resigned from the position as chief engineer of the Diesel Engine Division of the American Locomotive Company.

FEDERAL-MOGUL CORPORATION recently announced the appointment of M. R. Hunter as general manufacturing manager. Hunter will direct manufacturing operations in all of the company's plants. He will make his headquarters at the Corporation's main offices in Detroit.

ELLIOTT Company recently announced two new district managers. J. M. Maag is now Kansas City district manager. Mr. Maag was a field engineer in the Elliott Chicago office from 1925 until 1941, when he became St. Louis district manager.



J. M. Maag



H. W. Honefenger

H. W. Honefenger who joined Elliott Company in 1936 as field engineer of the St. Louis office, has now been appointed St. Louis district manager succeeding Mr. Maag.

**YOU can make real savings!**

**more than 400 NEW G. M. DIESEL PARTS**

**FROM GOVERNMENT SURPLUS**

*Many of them critical—hard to get. In original packages—new and clean.*

Here are a few of the many "71" DETROIT DIESEL and GRAY MARINE parts. Ready for immediate shipments.

**GRAY MARINE 6D-636C SEA WATER PUMPS**

No.	Description
5226888	Injector Filter Element
8502957	Oil Cooler Element 12 Stack
5227325	Spray Tip and Valve Ass'y
5227231	No. 80 Injector and Case
5157393	Blower Ass'y—Left
5157396	Blower Ass'y—Right
5153737	Exhaust Valve
CS Main Bearings—Std & Undersize	

*Immediate Shipment—Write for Complete List and low net prices.*

**Surplus Automotive Co.**  
1329 S. MICHIGAN AVENUE  
CHICAGO 5, ILLINOIS  
DIESEL PARTS SPECIALISTS



## News Of The Industry

NEW YORK CENTRAL has placed orders for 111 Diesel locomotives including eight road passenger locomotives, 17 road freights, 15 transfer freights, 64 switchers, and 7 road switchers. They will be supplied by American Locomotive, Electro Motive, and Fairbanks-Morse.

SOCONY-VACUUM OIL COMPANY is rushing to completion a new barge with a capacity of nearly three-quarters of a million gallons which will aid materially in relieving the threatened oil shortage in the east. The barge is equipped with Diesel driven 1400 gpm. rotary pumps.

A NEW VISCOSIMETER by Fischer-Porter Company measures viscosity from .0008 to 800,000 centipoises according to a new bulletin issued by the company. Instantaneous reading of viscosity values in a moving fluid stream is possible with this new instrument. Write for Bulletin 88, Fischer Porter Co., Dept. 5E-H, Hatboro, Pennsylvania.

NATIONAL SUPPLY COMPANY has recently put in operation 2 heavy duty Wickes lathes. These lathes used for machining heavy crankshaft forgings are 45-feet long and weigh over 100,000 lbs.

NEW HAVEN RAILROAD will soon have its Bridgeport, Conn., yard completely Dieselized and will only use coal locomotives in emergencies. This is part of a program by the railroad to rid itself of the smoke nuisance.

GREAT NORTHERN RAILWAY announced recently that the acquisition of 9 new 4,500 hp. Diesel-electric locomotives during the past month has permitted the Dieselization of two trains running from St. Paul, Minnesota to Wenatchee, Washington. Great Northern now has 145 Diesel locomotives.

THE BALTIMORE AND OHIO railroad recently ordered 100 Diesel electric switching locomotives. The order for these 1000 hp. switchers is divided between Electro-Motive with 40; Baldwin Locomotive and American Locomotive with 25 each; and Fairbanks Morse and Co. with 10. Delivery is expected by the 3rd quarter of 1948 and will enable the road to completely Dieselize its terminals at Cincinnati, Youngstown, Warren and Pittsburgh.


700 MACK DIESEL BUSES have been ordered by Argentina. For operation in a region where

gasoline sells for two and three times the price of Diesel fuel, Mack is powering all of these buses with a 165 hp. Mack Diesel engine. Paired with the Diesel is the new Mack torque converter designed to absorb the power of the engine at city driving speeds.

THE MILWAUKEE ROAD has ordered 38 new Diesel-electric locomotives at a cost of over \$6,000,000. Included are eight 3000 hp. freight; six 2000 hp. passenger, twenty 1000 hp. switchers and four combination switching and road locomotives. Addition of the new fleet will bring the number of Diesel-electric locomotives on the Milwaukee road to 175.


THE SUPERIOR TUBE COMPANY has published an instructive bulletin describing its complete line of nickel and nickel alloy products, particularly its small tubing. Indexed for easy reference the bulletin describes the company's nickel, Monel, "K" Monel, Inconel, and 30% Cupronickel tubing which is claimed to have great strength, corrosion- and heat-resistance. Ease of fabrication is another claimed advantage. Write the Superior Tube Company, Norristown, Pennsylvania for Catalog section 10.

## MAXIM SILENCERS



THE MAXIM SILENCER COMPANY  
94 HOMESTEAD AVE., HARTFORD 1, CONN.

## EACH CYLINDER EACH BEARING



*Individually Lubricated*

**B**Y faithfully delivering precise amounts of oil to cylinders, bearings, and other points of friction, Manzel Lubricators save engine owners up to 60% in reduced oil consumption and lowered maintenance costs. Write for further information

Manzel Brothers Co. now supplies repair parts for all models of Bowser and Torrington Lubricators.

A Subsidiary of Frontier Industries, Inc.  
275 Babcock Street Buffalo 10, N. Y.

Builders of HIGH PRESSURE  
METERING PUMPS  
Since 1898

*Manzel*  
BROTHERS CO.

## FOR THE OIL GASOLINE & WATER CONNECTIONS VELLUMOID

### A Good Gasket is worth the Price!

It costs just as much to install a poor gasket as it does to make a tight, long lasting seal with VELLUMOID, the standard for nearly thirty-five years.

THE VELLUMOID COMPANY, Worcester, Mass.

**MCCORD**  
*Class S.F.*  
**LUBRICATORS**

A modern lubricator for modern service on Diesel, gas, steam engines and compressors. Supplies dependable cylinder lubrication in metered quantities reducing friction and wear. Capacities: 2 to 24 pt. and 1 to 16 feeds. New catalog on request.

RESULT OF 40 YEARS' LUBRICATOR BUILDING EXPERIENCE

**MCCORD** CORPORATION  
DETROIT 11, MICHIGAN  
LUBRICATOR DIVISION

Send for new Bulletin SPI

**DURABLE**  
**PUMP VALVE SERVICE**

DURABLE MANUFACTURING COMPANY  
NEW YORK

114 Liberty St., N. Y. 6



Forged Steel Design made to special order for all types and sizes of air and gas compressors—from 2" to 16" diameter.

Valve plates and discs of all designs in alloy steel, stainless steel, monel, bronze and other metals.

Write for estimates and send samples or blueprints of your old valves.

**J. H. H. VOSS CO., INC.**

785 East 144th St. corner Wales Ave., New York, N. Y.

### Merger of Automatic Temperature Control Companies Announced

THE Merger of Robertshaw Thermostat Company, of Youngwood, Pennsylvania, The Fulton Sylphon Company, of Knoxville, Tennessee, and the Bridgeport Thermostat Company, Inc., of Bridgeport, Conn., was announced recently by John A. Robertshaw, President of the new organization. J. V. Giesler, former President of the Fulton Sylphon Company and the Bridgeport Thermostat Company was elected Executive Vice President of the new firm in charge of the Fulton Sylphon and Bridgeport Divisions, while T. T. Arden was elected Executive Vice President in charge of the Grayson Controls Division, Lynwood, California.

### Bradford Foote Dies

Bradford Foote Sr., founder and president of the Brad Foote Gear Works, died at his home recently after a short illness. Mr. Foote was born in Chicago on April 16, 1872. In 1924 he founded the company bearing his name.

### New Tumico Micrometer



Tumico Crankshaft Micrometer

A NEW direct-reading crankshaft micrometer making it possible to measure journal diameters without removing the crankshaft from the engine block is announced by Tubular Micrometer Co.

Simple in design, this micrometer provides ample reach for all sizes of crankshafts. It is recommended for use on all types of crankshafts but is primarily designed for combustion engines. Tumico Crankshaft Micrometers insure measurements accurate to .001 in. (one thousandth inch). Capacity of the micrometer is from two to three inches in English calibration or 50 to 75 mm. in metric. For more information write Tubular Micrometer Co., St. James, Minnesota.


### New Gauges Described

FIVE new gauges are illustrated and described in a series of new bulletins recently published by the F. W. Dwyer Manufacturing Company. The bulletins describe plastic tube manometers, hook gauges, air filter gauges, portable and stationary draft gauges. The last bulletin, No. 165, contains useful formulae concerning air flow data as applied to gauge readings. Write F. W. Dwyer Manufacturing Company, 317 South Western Avenue, Chicago 12, Illinois, for bulletins.

### Engineering Society Meetings

THE Annual Meeting of the Society of Automotive Engineers will be held in Detroit, January 12-16. The Annual Meeting of the Oil and Gas Power Division of the A.S.M.E. will be held May 20-22 in St. Louis, Missouri.

### New Line of "Packaged" Generators



E-M generator with built-in voltage regulator

A "PACKAGED" generator recently announced by Electric Machinery Mfg. Company for use in engine-generator sets is a compact, factory-assembled unit including revolving-field generator, direct-connected exciter, automatic voltage regulating circuit, meters, and selector switch for pre-setting voltage.

Operation of the circuit is detailed in Publication No. 186 available from the manufacturer, Electric Machinery Mfg. Co., Minneapolis 13, Minnesota.

### Portable Rock Crushing Plant



A NEW portable two-unit crushing and screening plant has been developed by the New Holland Manufacturing Company. This one-man push button controlled crushing unit on wheels has been fully field-tested with excellent results, according to the manufacturer.

Adaptable to either gravel crushing or quarry operations, a 200 hp. Murphy Diesel operates the 3030 Double Impeller Breaker while an electric generator driven from the same Diesel supplies power for driving the feeder, conveyers, screen and elevating wheel on the screening unit. Individual electric motor drives, controlled from the operator's platform on the crushing unit, eliminates chains, sprockets and counter shafts.



DIESEL PROGRESS

WI  
REVIV  
Camp Se  
net tend  
ft. A-N 5  
Diesels  
motor. A  
erating p  
FROM  
Calif., th  
for Vince  
ered with  
aries, tw  
generating  
POWER  
Diesels, is  
Island Tu  
used in de  
coast.  
FIFTY-F  
Gordon N  
hp. gasoli  
Grandy B  
165 hp. G  
WITH n  
having a c  
per hour  
marine do  
largest tun  
3 in. meter  
apiece, sever  
vide ample  
the tuna se  
installed. I  
Division M  
OCEAN T  
concern in  
moving-pow  
barges, has  
"Miki Miki"  
Fairbanks-M  
THE APC  
rior Diesel  
readied for s  
San Francisco  
ton, Texas.  
TROLLER  
Bellingham,  
eral Motors I  
reduction ge  
Engine and I  
INDIAN Cr  
chased a Cate  
two stage cen  
to raise water  
JANUARY 1948



## WEST COAST DIESEL NEWS

By FRED M. BURT

**REVIVING** the tuna "mothership" idea, Van Camp Sea Food Co. has converted one of four A-N net tenders, purchased as Navy surplus; this 180 ft. A-N 53 has two 750 hp. American Locomotive Diesels hooked to a 1,500 hp. G.E. DC drive motor. Auxiliaries include two 60 kw. Buda generating plants and a 75 kw. "Caterpillar" set.

**FROM** the yards of Master Builders, Alameda, Calif., the 108 ft. purse seiner *Storm King*, built for Vincent Cardinalli of San Francisco, is powered with a 6 cyl. 840 hp. Union Diesel; auxiliaries, two "Caterpillar" 75 kw., 115 hp. Diesel generating sets.

**POWERED** with two 690 hp. Fairbanks-Morse Diesels, is the tug *Island Navigator*, owned by Island Tug and Barge Co., Victoria, B. C., to be used in deep sea service off the British Columbia coast.

**FIFTY-FIVE** ft. purse seiner, *New Sunrise*, owner Gordon Nelson, has recently had her original 140 hp. gasoline engine, installed when built by Grandy Boat Co., Seattle, in 1945, replaced by a 165 hp. General Motors Diesel.

**WITH** new dispensing and pumping facilities having a capacity of 36,000 gallons of Diesel fuel per hour, the newly-modernized Shell Oil Co. marine dock in San Diego Harbor, can fuel the largest tuna clipper in two to three hours. Ten 3 in. meters for Diesel fuel with two 2 in. nozzles apiece, seven meters and outlets for gasoline provide ample service. To prevent fuel shortage in the tuna season, a 5400 bbl. Diesel tank has been installed. E. R. Raphael is Southern California Division Manager.

**OCEAN** Tow, Inc., Seattle, newest tug and barge concern in the Puget Sound-Alaska run, to supply moving-power to their 21 260 ft. and 204 ft. barges, has eight, twin-screw, 126 ft. seagoing tugs, "Miki Miki" type, each powered with two 690 hp. Fairbanks-Morse Diesels.

**THE** APC No. 1, powered with a 400 hp. Superior Diesel engine, is being reconverted and readied for sea at yards of Anderson & Christofani, San Francisco, for Fulton Construction Co., Houston, Texas.


**TROLLER** *Bobetta*, building at Wrang Shipyard, Bellingham, for Henry Brandt, has 165 hp. General Motors Diesel with 3:1 hydraulic reverse and reduction gear also by GM. Supplied by Evans Engine and Equipment Co.

**INDIAN** Creek Industries Corp. recently purchased a Caterpillar Diesel to power a 550 gpm. two stage centrifugal pump at Weaverville used to raise water from river 500 feet to reservoir.

**SEVENTY-FIVE** kw. Caterpillar Diesel-electric set lifted itself aboard LST vessel recently when Diesel was operated at dockside with flexible leads to shipboard crane which lifted it aboard. Generating set was supplied to LST purchasers by Shepherd Diesel Marine of Los Angeles.

**CANNERY** tender *Hydah* repowered with 165 hp. General Motors Diesel. 4.38:1 Twin Disc reduction gear and Twin Disc frontpower take-off also installed by owners, Anacortes Canning Co. Supplied by Anacortes, Washington branch of Evans Engine and Equipment Co.

### New Equipment for Piston Sizing



Wilkening Thermo-sizer

**THERMO**-sizing is a process now being used by Pedrick jobbers to reshape and resize alloy pistons so they fit exactly the cylinders in which they operate.

A machine called Thermo-sizer is used. It is the first machine to utilize "Heat-Shaping" in the reconditioning of pistons. By this process, worn and collapsed alloy pistons may be resized and reshaped as much as .030 in., safely and permanently.

**Order Your Copy of the 1947 DIESEL ENGINE CATALOG now. Thoroughly revised — more complete — indispensable. Convenient order coupon on Page 77 this issue. Mail it today.**

## Aluminum Pistons Cleaned Faster!

Specialized Oakite cleaning compounds can help you make the cleaning of aluminum or cadmium-plated pistons and rings a time-saving, easy and safe procedure. There are hot Oakite alkaline cleaning solutions. Cold and hot. . .


## Oakite Solvent Carbon Removers

These same versatile compounds will also serve for speedy cleaning of cylinder liners, heads, valves, gears, connecting rods. Check with the Oakite Technical Service Representative near you for the procedure that best meets your needs. Or write direct for full, free job data. No obligation.

OAKITE PRODUCTS, INC.  
220 Thames Street, NEW YORK 6, N. Y.  
Technical Service Representatives Located in  
Principal Cities of United States and Canada

**OAKITE**

Specialized Industrial Cleaning  
MATERIALS • METHODS • SERVICE




25 KVA, 1200 RPM,  
A. C. Generator  
with Direct Connected Exciter.

**COLUMBIA**  
**GENERATORS**  
A. C. and D. C.

Columbia, with its years of experience, brings to you a wide line of performance proved, sturdily built, A.C. and D.C. Generators. A.C. Generators: 6 1/4 to 375 KVA. D.C. Generators and Exciters: 2 to 200 KW. Available in Single or Two Bearing Construction. Write today for information. Our engineers will be glad to review your requirements. Prompt delivery.

COLUMBIA ELECTRIC MFG. CO.  
4519 Hamilton Ave., Cleveland 14, Ohio

**IMMEDIATE DELIVERY!  
NEW-25% OFF**



**ATLAS IMPERIAL MARINE DIESEL**

Model 6 HM 2124

424 H.P. @ 325 R.P.M.

6 Cylinder - 4 Cycle - Air Starting  
Direct Reversing

Complete with spares, tools, accessories

**Large Variety Marine Engines**

New 165 H.P. G.M. Diesels

New 141 H.P. Chrysler Royal (Gas)

New 55 H.P. Atlas Skipper (Gas)

Surplus War Materials Marine Crafts of all Types

**UNITED DOCK CORP.**

Executive & Sales Offices

Rm. 7311 Empire State Bldg., N. Y., N. Y.

Longacre 4-8344-8345-8346

Shipyard—209 Carroll St., City Island N. Y. 64, N. Y.

**PETROMETER**



FOR ALL TANKS  
FOR ALL LIQUIDS  
FOR ALL DEPTHS  
FOR ALL DISTANCES

PETROMETER CORP. 5 STAR SQ., L.I. CITY 1, N.Y.

**Highest Quality  
Gaskets & Oil Seals  
by FITZGERALD**

**Gasket Craftsmen  
for 42 Years**

Gaskets of all types and materials to  
give reliable service under all Diesel  
operating conditions.

For full information write—

**THE FITZGERALD MANUFACTURING  
COMPANY**

TORRINGTON, CONN.

Branches: Chicago, Illinois; Los Angeles, California  
Canadian FITZGERALD, Limited, Toronto

**FITZGERALD  
GASKETS**

SINCE  
1906

THE COMPLETE LINE THAT COMPLETELY SATISFIES

**ADVERTISERS' INDEX**

Aerofin Corporation .....	86	Koppers Company, Inc. ....	27
Aircraft & Diesel Equipment Corp. ....	80	Kurz and Root Company .....	78
Air-Maze Corporation .....	80	Lanova Corp. ....	18
Aluminum Co. of America .....	20-21	Leece-Neville Co., The .....	73
Atlantic Metal Hose Co., Inc. ....	85	McCord Corporation .....	84
Benjamin's for Motors .....	86	Madison-Kipp Corp. ....	14
Bolinders Co., Inc. ....	86	Manzel, Inc. ....	83
Buckeye Machine Co. ....	72	Maxim Silencer Co., The .....	83
Burgess-Manning Co. ....	85	Metalock Casting Repair Service .....	75
Caterpillar Tractor Co. ....	10	Murray & Tregurtha, Inc. ....	1
Cities Service Oil Co. ....	67	National Forge & Ordnance Co. ....	86
Cleveland Diesel Engine Div., General Motors Corp. ....	2	Nordberg Mfg. Co. ....	7
Columbia Electric Mfg. Co. ....	87	Oakite Products, Inc. ....	87
Cooper-Bessemer Corp. ....	Fourth Cover	Permatex Company, Inc. ....	86
Cummins Engine Co. ....	25	Petrometer Corp. ....	88
Darien Corp. ....	86	Photovolt Corp. ....	86
Detroit Diesel Engine Div., General Motors Corp. ....	71	Pickering Governor Co. ....	86
Diamond Chain Company, Inc. ....	6	Quincy Compressor Co. ....	81
Diesel Motors Corporation .....	13	Ramberg, Inc., H. W. ....	78
Diesel Specialties, Inc. ....	78	Sarco Company, Inc. ....	79
Durabla Mfg. Co. ....	84	Schoonmaker Co., A. G. ....	29
Eaton Manufacturing Co. ....	24	Scintilla Magneto Div. of Bendix Aviation Corp. ....	9
Electro Products Laboratories .....	81	Sims Co., The .....	85
Elliott Company .....	Third Cover	Sinclair Refining Co. ....	64-65
Enterprise Engine & Foundry Co. ....	30	Standard of California. ....	69
Erie Forge Company .....	22	Standard Oil Co. (Indiana) ....	17
Fairbanks, Morse & Co. ....	15	Stewart Iron Works Co., Inc., The .....	79
Federal-Mogul Corp. ....	16	Sticht Co., Herman H. ....	86
Fitzgerald Mfg. Co. ....	88	Sun Shipbuilding & Dry Dock Co. ....	26
Fram Corporation .....	12	Surplus Automotive Co. ....	82
General Motors Corp., Cleveland Diesel Engine Div. ....	2	Texas Company, The .....	Second Cover
Detroit Diesel Engine Div. ....	71	Thomas Flexible Coupling Co. ....	74
Harrison Radiator Div. ....	19	Tuthill Pump Company .....	85
Globe-Union, Inc. ....	28	United Dock Corporation .....	88
Gulf Oil Corp. ....	5	Vellumoid Co., The .....	83
Harrison Radiator Div., General Motors Corp. ....	19	Voss Co., J. H. H. ....	84
Honan-Crane Corporation .....	70	Walworth Company .....	8
International Harvester Co. ....	23	Worthington Pump & Machinery Corp. ..	4
		Young Radiator Co. ....	11